


Laser Megajoule Facility Control system status report

DE LA RECHERCHE À L'INDUSTRIE

cea



Presented by **J. Nicoloso**

Commissariat à l'Énergie Atomique et aux Énergies Alternatives,
CEA/DIF, Bruyères le Châtel, 91297, Arpajon, France

Email: joel.nicoloso@cea.fr

www.cea.fr

Presentation overview

Presentation of the LMJ facility

Presentation overview

Presentation of the LMJ facility

Command Control Architecture


Presentation overview

Presentation of the LMJ facility

Command Control Architecture

Command Control Integration

LMJ facility overview



LMJ



Zone industrielle
Laseris



Presentation overview

Presentation of the LMJ facility

Command Control Architecture


Command Control Integration

Hardware architecture


Supervisory levels are virtualized using the VMware VSphere Enterprise Plus suite

Logical Architecture:
- 500 virtual machines


Physical Architecture:
- 16 hi-perf servers
- 100 TB disk space




Software architecture



Software common framework



Software technical choices



Platform : PC, Windows

SCADA: Panorama E² from CODRA

Interface protocols: WCF

Specific developments: .Net

Database: SQL-Server, Oracle

CMMS: D7i from Datastream

File exchange: XML, HDF5

Data Acq : TANGO, Python

Presentation overview

Presentation of the LMJ facility

Command Control Architecture

Command Control Integration


Integration issues & solutions

Issues

- 50 Interfaces between 12 contractors

Solutions

- Interface definition management
- Integration process management



The LMJ CC is distributed over the 4 main LMJ Systems :

Laser Subsystems

Experiment Subsystems

Control Command Subsystems

Building and Utilities Subsystems


Interface definition

All external interfaces between subsystems are defined and manage in a central database

Interface definitions are exported as xlm files from that database

Dedicated tools allow to automatically generate from these xml files:

- Supervisory subsystems' skeletons
- Supervisory subsystems' simulators
- The device settings configuration database




Integration process

Proceed to the command control integration outside the facility prior to machine integration

- Reduce as much as possible machine unavailability due to command control issues
- Correct bugs as soon as possible and debug without damaging the machine

Promote the independency of the contractors

Integrate new lines in the LMJ building while using the commissioned ones



Integration process

A 3-step process:

STEP 1 : Factory acceptance tests

- Acceptance tests for equipment
- Acceptance tests for control system

Who ?

Contractors

Where ?

In
Factory

STEP 2 : Command Control Integration with equipment simulators

- Global tests for the supervisory system
- Global tests for each control subsystems
- Tests of the whole control system

CEA

*Subsystem
By
Subsystem*

On
PFI

STEP 3 : Integration with real equipment

- Industrial tests for each subsystem
- System tests of the whole process
- Bundle delivery for validation from operations control room


Contractors

CEA

*Line
By
Line*

In
LMJ

Control system milestones





Thank you for your attention