





The NLC/GLC X-Band Linear Collider

Main Linac RF Power Unit





A Linac RF unit demonstration for the NLC/GLC X-Band Linear Collider



Outline:

The NLC/GLC Main Linac RF 'unit'

Modulator

Klystrons

RF Pulse Compression

Accelerator Structures


NLC/GLC Baseline

'8-Pack' Project Implementation

Further Improvements




NLC/GLC X-Band Linac Baseline RF Unit (One of ~ 2000 at 500 GeV cms, one of ~ 4000 at 1 TeV cms)



Eight 0.6 m Accelerator Structures (65 MV/m Unloaded, 52 MV/m Loaded)



NLC/GLC X-Band Linac Baseline RF Unit (One of ~ 2000 at 500 GeV cms, one of ~ 4000 at 1 TeV cms)



Eight 0.6 m Accelerator Structures (65 MV/m Unloaded, 52 MV/m Loaded)




The Solid State IGBT Modulator

8-Pack Project

Inductively sum many low voltage sources

INDUCTION CIRCUIT (1 OF N)



Hybrid 2-Pack modulator




'8-Pack' IGBT Modulator


8-Pack Project

76 Cores
Three-Turn Secondary
» 1000 Hours of Operation

Waveforms When Driving Four 50 MW
Klystrons at 400 kV, 300 A Each



1.6 μ s: 400 ± 3 kV, $\pm 0.7\%$






Next Generation: The '2-Pack'

8-Pack Project

Features

- 6.5 kV IGBTs with in-line multi-turn 1:10 transformer.
- Industrialized cast casings.
- Improved oil cooling.
- Improved HV feed through.

2-Pack Layout



The Bechtel-LLNL-SLAC Team

A hybrid 2-Pack modulator is currently running at SLAC.




Modulator Performance (1.6 ms Pulse Width)

	Config	Load	Voltage (kV)	Current (A)	Rate (Hz)	Efficiency (%)
Achieved	8-pack	Water	500	1000	10	
	8-Pack	Four XL4 Klystrons	400	1200	60	58
	2-Pack Hybrid	Water	500	500	120	60
NLC/GLC Baseline	2-Pack	Two PPM Klystrons	500	500	120	70

2-Pack efficiency is lower than goal due to hybrid transformer – expect > 70% in next version with integrated transformer.



NLC/GLC X-Band Linac Baseline RF Unit (One of ~ 2000 at 500 GeV cms, one of ~ 4000 at 1 TeV cms)







X-Band Baseline PPM Klystrons

Solenoid-Focused Tubes: Have Twelve, 50 MW Tubes for Testing, However Solenoid Power = 25 kW.


Developing **Periodic Permanent Magnet (PPM)** Focused Tubes to Eliminate the Power Consuming Solenoid.



1.7 m



Axial Magnetic Field ~ 2 kG RMS
(~ 5 kG for Solenoid Focusing)





PPM Klystron Performance (75 MW, 1.6 ms, 120/150 Hz, 55% Efficiency Required)

KEK/Toshiba

Two tubes tested at
75 MW
1.6 ms pulses
50 Hz (modulator limited)
Efficiency = 53-56%



SLAC

Two tubes tested at
75 MW
1.6 ms pulses
120 Hz.
Efficiency = 53-54%
A third tube is under test.






PPM Klystron Performance Overview

8-Pack Project

Klystron Performance Summary

Klystron	Peak Power	Pulse-Width	Repetition Rate
SLAC XP3 S/N 4	75 MW	1.6 μ s	120 Hz
SLAC XP3 S/N 3	75 MW	1.6 μ s	120 Hz
KEK PPM S/N 2	75 MW	1.7 μ s	60 Hz
	68 MW	1.7 μ s	120 Hz
KEK PPM S/N 3	65 MW	1.5 μ s	50 Hz
KEK PPM S/N 4	75 MW	1.6 μ s	25 Hz
SLAC 75 MW Prototype	75 MW	1.5 μ s	1 Hz
	79 MW	2.8 μ s	1 Hz
KEK PPM S/N 1	68 MW	1.5 μ s	5 Hz
SLAC 50 MW	50 MW	1.5 μ s	120 Hz
	55 MW	2.4 μ s	60 Hz
	75 MW	1.5 μ s	120 Hz
Specifications	75 MW	1.6 μ s	120 Hz

TRC R2 Done



Notes: Modulators Limited to 50 Hz

Initial Tubes Not Designed for High Repetition Rates

TRC R2 requirement of 120 Hz operation has been met.


Current Status of the Next Linear Collider X-band Klystron Development Program,
Daryl Sprehn, *et al.* ID: TUPKF063, in these proceedings



8-Pack Project Klystrons


8-Pack Project

Four 50 MW solenoid focused X-Band klystrons





NLC/GLC X-Band Linac Baseline RF Unit (One of ~ 2000 at 500 GeV cms, one of ~ 4000 at 1 TeV cms)





Eight 0.6 m Accelerator Structures (65 MV/m Unloaded, 52 MV/m Loaded)



Over-Height Planar X-Band Waveguide

8-Pack Project


Lower Surface Electric Fields (< 50 MV/m)
and Limited Pulse Heating ($< 40^\circ$ C)
to manage high power levels



Example: Power Splitter



Second Generation SLED II - multimoded





The electrical length of the delay line is the length of the output pulse (400ns). The physical length can be halved by using two RF modes.





TRC R1 8-Pack configuration, Dec. 2003

8-Pack Project





Multimoded SLED-II output




Delivered 580 MW, 400 ns,
to loads

Operated 250 hours at 510
MW (475 MW required)
with required reliability
(pulse rate 30&60 Hz)

TRC R1 Done




NLC/GLC X-Band Linac Baseline RF Unit (One of ~ 2000 at 500 GeV cms, one of ~ 4000 at 1 TeV cms)






NLC/GLC Accelerator Structure

8-Pack Project



Cells with Slots for Dipole Mode Damping




Structure cut-away



System Demonstration and Operation

8-Pack Project

From 8-Pack



Eight accelerator structures
powered in NLCTA, 300 MeV gain


First four structures continue to be
powered by original NLCTA stations.

Running 24/7 since first of April;
>1000 hours of operation
with >90% uptime



Phase 2 beam line installed

8-Pack Project






Changing Structures in NLCTA

Install new structure = 8 hours

Pump down = 16 hours (overnight)

High Power Processing = 30 hours





Structure operation history at NLCTA

8 structures have been running for 1000 hours at NLCTA

Recent structure performance:

April 2004	61.1 MV/m	0.10/hour
------------	-----------	-----------

May 2004	64.9 MV/m	0.16/hour
----------	-----------	-----------

June 20, 2004	64.9 MV/m	0.085/hour
---------------	-----------	------------

TRC R1 Done

→ Performance improves with running time.



June operation of NLCTA
(Based on 150 hours of Operation)

Structure	Manufacturer	Gradient (MV/m)	Trip Rate (#/hr)
H60vg4S17-FXD1A	FNAL	65.4	0.18
H60vg3S17-FXC5	FNAL	64.5	0.10
H60vg4S17-3	KEK/SLAC	65.4	0.04
H60vg3S17-FXC3	FNAL	64.5	0.04
H60vg3-FXB6	FNAL	64.8	0.00
H60vg3-FXB7	FNAL	66.7	0.19
H60vg4S17-1	KEK/SLAC	63.2	0.10
H60vg3R17	SLAC	64.8	0.04
Average		64.9	0.085
Average One Month Ago		64.9	0.163



RF Component Efficiencies

Efficiency	Design	Achieved	Comment
Two-Pack Modulator	70 %	60 %	Use Integrated Transformer (> 70% Expected)
PPM Klystron	55 %	53-56 %	~ 60% Possible
SLED II	81 %	78 %	Improve Flanges/Fab/Assembly
Wave Guide Transport	92 %	77 %	Improve Layout Design & Reduce High-Loss WG
Structures	31 %	29 %	Use rounded cell shape



Further Development:

Modulator:

The hybrid 2-Pack modulator is being installed and will be operated with PPM klystrons.

Klystron:

PPM klystrons continue to be produced and tested at SLAC and at KEK/Toshiba.

RF Pulse Compression:

The power transmission will be improved and compression efficiency increased.


Accelerator Structures:

Structures are being fabricated and installed on the NLCTA and GLCTA.



Conclusions

8-Pack Project



The '8-Pack' system has successfully demonstrated the high power capability and reliability of the NLC/GLC baseline RF system.

The components operate at their design levels, and are robust.

Further improvements in efficiency will come with a move towards high volume production.