




LHC Progress and Commissioning Plans

O. Brüning
CERN, Geneva, Switzerland
(for the LHC commissioning team)

Contents

 LHC layout overview and main parameters


 Project status

 Main challenges for the commissioning

 Commissioning plan

LHC Layout and Main Parameters

- 2-in-1 magnet design
p-p & Pb-Pb collisions
- 7 TeV p-beam energy
→ > 1 TeV CM energy
→ Higgs discovery
- 2 high L experiments with
 $L = 10^{34} \text{ cm}^{-2} \text{ sec}^{-1}$
→ 2808 bunches / beam
with $1.15 \cdot 10^{11}$ ppb
- 2 low L experiments:
ALICE (Pb-Pb) & LHCb




LHC Layout and Main Parameters

■ built in old LEP tunnel
→ 8.4 T dipole magnets
→ 10 GJ EM energy
→ powering in 8 sectors

■ 2808 bunches per beam
with $1.15 \cdot 10^{11}$ ppb
→ 360 MJ / beam
→ crossing angle &
long range beam-beam

■ Combined experiment/
injection regions





[A. Koschik et al, TUPLS014] [A. Koschik et al, WEPCH043]

LHC Layout and Main Parameters

2-in-1 dipole magnet design
8.4 T, 15 m long, 30 Ton

LHC DIPOLE : STANDARD CROSS-SECTION

CERN AC/DT/MM - HE107 - 30 04 1999



Project Status


Main dipole (MB) production and installation (1232)

- almost all MB have been delivered to CERN (November 2006)
- all MB will have passed cold test by end of 2006
- 3/4 have been prepared for installation and slot assigned
- almost 50% have been installed in the tunnel
- installation is expected to progress at rate of 18 MB / week


Main quadrupole (MQ) production and installation (392)


- almost all MQ have been delivered to CERN
- 1/3 of the assemblies have been installed in the tunnel
- 2/3 have been slot assigned
- installation is expected to progress at rate of 6 assemblies / week

→ closure of machine in March 2007, interconnect and pressure test August 2007





Cryodipole overview







SSS overview






Cryogenics overview





Cryogenic distribution line



LHC Installation



cryogenic
distribution
in 12




superconducting link



Q6 with cryogenic connection in IR8


EPAC 2006; 26.-30. June 2006



electrical distribution in IR8

Oliver Brüning 11

LHC Installation




Main Challenges for the Operation

- Mechanical aperture
- Polarity errors
- Global magnet field quality & corrector circuit powering
- Collimation efficiency
- Beam power and machine protection
- Collective effects and impedance
- Triplet aperture and beam-beam
- Electron cloud effect

Mechanical Aperture


■ all magnets are geometrically measured



→ classification & slot compatibility
for installation at critical locations


■ microwave reflectrometer:

→ detection of obstacles



Polarity Errors

the LHC features 112 circuits / beam (+ orbit correctors)



all magnet circuits
are tested before and during
installation

[D. Bozzini et al, WEPLS099]

adjustments during operation

→ non-destructive beam instrumentation



[P. Cameron et al, THPCH105]

Global Magnetic Field Quality


field quality measurement before installation:

- all magnets are measured warm at industry → monitoring
- all magnets are cold tested → electrical integrity & quench
- a subset undergoes cold measurements → warm-cold correlation

→ ‘sorting’ during installation

Sector 78 V1

[S. Fartoukh, EPAC 2004]



-a smaller subset is subject to ‘extended’ measurements

→ field quality modeling during operation → corrector powering!

[N. Sammut et al, WEPLS104] [G. Rijk, WEPLS100]

Collimation Efficiency



Machine operation requires high collimation efficiency:

Collimation inefficiency := #p above 10σ / # p on primary

→ design value of $2 \cdot 10^{-3}$ → below 0.2 h / 2 h are acceptable

→ 2 stage collimation system with ca 100 collimators!

Effect of machine imperfections:



→ requires good optic and orbit control! → feedback loops

[R.Assmann, TUODFI01] [C.Bracco et al, TUPLS018][G Robert-Demolaize TUPLS019]

EPAC 2006; 26.-30. June 2006

[S. Redaelli, TUPLS130 and TUPLS131]


Oliver Brüning 17

Beam Power and Machine Protection

[R. Assmann]

Unprecedented beam power:


- potential equipment damage in case of failures during operation
- in case of failure the beam must never reach sensitive equipment!



Machine Protection System

- Beam Loss Monitors
- Quench protection system
- Beam Interlock System
- reliable Beam Dump system (15)
- dedicated absorbers in case of asynchronous dump

[B. Goddard]



[R. Filippini et al, WEPLS140] [B. Goddard et al, MOPLS008] [B. Goddard et al, TUPLS013]

Beam Power and Machine Protection

Unprecedented beam power:

- all absorbers and the collimation system must be designed to survive an asynchronous beam dump!
(total of up to 136 collimators & absorbers)



Robust collimator jaw design

- fiber reinforced graphite jaws are more robust than Cu jaws
- fiber reinforced graphite has a higher impedance and electrical resistivity




[R. Assmann, TUODFI01] [F. Zimmermann et al, THPCH061]

Collective Effects & Impedance

resistive wall impedance:

- image charges trail behind due to resistivity of surrounding materials
- Wake fields drive beam instabilities
- effect increases with decreasing gap opening of the collimator jaws



- impedance of Graphite jaws either limits the minimum collimator opening → limit for β^* or the maximum beam current

[F. Zimmermann et al, THPCH061]

phased collimation system for the LHC:

- Phase 1: graphite jaws for robustness during commissioning
- Phase 2: nominal performance (low impedance, non-linear or feedback)


[R. Assmann, TUODFI01][J. Resta MOPCH091][A. Faus-Golfe WEXFI03]

Triplet Aperture and Beam-Beam

long range beam-beam:

Operation with 2808 bunches features approximately 30 unwanted collision points per Interaction Region (IR).

→ Operation requires crossing angle



non-linear fields and additional focusing due to beam-beam
efficient operation requires large beam separation at unwanted collision points → separation of 9σ is at the limit of the triplet aperture for nominal β^* values! → margins can be introduced by operating with fewer bunches, lower bunch intensities, larger β^* values (or larger triplet apertures → upgrade studies)


[T. Pieloni, WEPCH095] [U. Dorda WEPCH138]

Electron Cloud Effect

■ Synchrotron light releases electrons from beam screen:

- electrons get accelerated by p-beam → impact on beam screen
- generation of secondary electrons → e-cloud
- heating, instabilities and emittance growth

average arc heat load [W/m]




- effect disappears for low bunch currents or large bunch spacing
- secondary emission yield decreases during operation (beam scrubbing)

[F. Zimmermann]

[E. Benedetto, THPCH018]

Staged Commissioning Plan for Protons



I. Pilot physics run

- ❑ First collisions
- ❑ 43 bunches, no crossing angle, no squeeze, moderate intensities
- ❑ Push performance (156 bunches, partial squeeze in 1 and 5, push intensity)

II. 75ns operation

- ❑ Establish multi-bunch operation, moderate intensities
- ❑ Relaxed machine parameters (squeeze and crossing angle)
- ❑ Push squeeze and crossing angle

III. 25ns operation I


- ❑ Nominal crossing angle
- ❑ Push squeeze
- ❑ Increase intensity to 50% nominal

IV. 25ns operation II

- ❑ Push towards nominal performance

[R. Bailey et al, MOPLS005]

Staged Commissioning: Tolerances@7TeV



Summary

■ Mechanical aperture	careful analysis and definition of procedures during installation → optimization in Stage I
■ Polarity errors	
■ Global magnet field quality & corrector circuit powering	
■ Collimation efficiency	optimization during Stage I
■ Beam power and machine protection	from Stage I to Stage II
■ Collective effects and impedance	only at Stage III
■ Triplet aperture and beam-beam	only > Stage III
■ Electron cloud effect	only at Stage IV

Stage I physics run

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$Eventrate / Cross = \frac{L \sigma_{TOT}}{k_b f}$$

Protons/beam $\lesssim 10^{13}$
(LEP beam currents)

- Start as simple as possible
- Change 1 parameter (k_b N $\beta^*_{1,5}$) at a time

Parameters			Beam levels		Rates in 1 and 5		Rates in 2	
k_b	N	$\beta^*_{1,5}$ (m)	I_{beam} proton	E_{beam} (MJ)	Luminosit y ($cm^{-2}s^{-1}$)	Events/ crossing	Luminosity ($cm^{-2}s^{-1}$)	Events/ crossing
1	10^{10}	18	$1 \cdot 10^{10}$	10^{-2}	10^{27}	$\ll 1$	$1.8 \cdot 10^{27}$	$\ll 1$
43	10^{10}	18	$4.3 \cdot 10^{11}$	0.5	$4.2 \cdot 10^{28}$	$\ll 1$	$7.7 \cdot 10^{28}$	$\ll 1$
43	4 10^{10}	18	$1.7 \cdot 10^{12}$	2	$6.8 \cdot 10^{29}$	$\ll 1$	$1.2 \cdot 10^{30}$	0.15
43	4 10^{10}	2	$1.7 \cdot 10^{12}$	2	$6.1 \cdot 10^{30}$	0.76	$1.2 \cdot 10^{30}$	0.15
15 6	4 10^{10}	2	$6.2 \cdot 10^{12}$	7	$2.2 \cdot 10^{31}$	0.76	$4.4 \cdot 10^{30}$	0.15
15 6	9 10^{10}	2	$1.4 \cdot 10^{13}$	16	$1.1 \cdot 10^{32}$	3.9	$2.2 \cdot 10^{31}$	0.77

Stored energy/beam $\lesssim 10MJ$
(SPS fixed target beam)

Stage II physics run

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$F = 1 / \sqrt{1 + \left(\frac{\theta_c \sigma_z}{2\sigma^*} \right)^2}$$

$$Eventrate / Cross = \frac{L \sigma_{TOT}}{k_b f}$$

- Relaxed crossing angle (250 μ rad)
- Start un-squeezed
- Then go to where we were in stage I

Protons/beam $\approx$ few 10^{13}

Stored energy/beam $\leq$ 100MJ

Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
k_b	N	β^* 1,5 (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity ($cm^{-2}s^{-1}$)	Events/ crossing	Luminosity ($cm^{-2}s^{-1}$)	Events/ crossing
936	$4 \cdot 10^{10}$	18	$3.7 \cdot 10^{13}$	42	$1.5 \cdot 10^{31}$	$\ll 1$	$2.6 \cdot 10^{31}$	0.15
936	$4 \cdot 10^{10}$	2	$3.7 \cdot 10^{13}$	42	$1.3 \cdot 10^{32}$	0.73	$2.6 \cdot 10^{31}$	0.15
936	$4 \cdot 10^{10}$	1	$3.7 \cdot 10^{13}$	42	$2.5 \cdot 10^{32}$	1.4	$2.6 \cdot 10^{31}$	0.15
936	9 10^{10}	1	$8.4 \cdot 10^{13}$	94	$1.2 \cdot 10^{33}$	7	$1.3 \cdot 10^{32}$	0.76

Stage III physics run

$$L = \frac{N^2 k_b f \gamma}{4\pi \epsilon_n \beta^*} F$$

$$F = 1 / \sqrt{1 + \left(\frac{\theta_c \sigma_z}{2\sigma^*} \right)^2}$$

$$Eventrate / Cross = \frac{L \sigma_{TOT}}{k_b f}$$

- Nominal crossing angle (285 μ rad)
- Start un-squeezed
- Go to where we were in stage II


Protons/beam $\approx 10^{14}$

Stored energy/beam ≥ 100 MJ


Parameters			Beam levels		Rates in 1 and 5		Rates in 2 and 8	
k_b	N	β^* 1,5 (m)	I_{beam} proton	E_{beam} (MJ)	Luminosity ($cm^{-2}s^{-1}$)	Events/ crossing	Luminosity ($cm^{-2}s^{-1}$)	Events/ crossing
2808	$4 \cdot 10^{10}$	18	$1.1 \cdot 10^{14}$	126	$4.4 \cdot 10^{31}$	$\ll 1$	$7.9 \cdot 10^{31}$	0.15
2808	$4 \cdot 10^{10}$	2	$1.1 \cdot 10^{14}$	126	$3.8 \cdot 10^{32}$	0.72	$7.9 \cdot 10^{31}$	0.15
2808	$5 \cdot 10^{10}$	2	$1.4 \cdot 10^{14}$	157	$5.9 \cdot 10^{32}$	1.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	1	$1.4 \cdot 10^{14}$	157	$1.1 \cdot 10^{33}$	2.1	$1.2 \cdot 10^{32}$	0.24
2808	$5 \cdot 10^{10}$	0.55	$1.4 \cdot 10^{14}$	157	$1.9 \cdot 10^{33}$	3.6	$1.2 \cdot 10^{32}$	0.24
Nominal			$3.2 \cdot 10^{14}$	362	10^{34}	19	$6.5 \cdot 10^{32}$	1.2

Five geometry sub-classes for the LHC main dipoles and their variants used in the sorting algorithm to preserve aperture



Golden R (GR)



Mid-cell (MC)



Silver L (SL)



Silver R (SR)

$$S \subset SLR = SL \cap SR \subset MC$$


$$G \subset GLR = GL \cap GR \subset SLR$$

$$GL \subset SL \text{ and } GR \subset SR$$

but

$GL \not\subset S$ and $GR \not\subset S$

Golden L (GL)



Global Magnetic Field Quality

field quality measurement before installation:

- all magnets are measured warm at industry → monitoring
- all magnets are cold tested → electrical integrity & quench
- a subset undergoes cold measurements
 - warm-cold correlation
 - ‘sorting’ during installation [S. Fartoukh, EPAC 2004]
- a smaller subset are subject to ‘extended’ measurements
 - field quality modeling during operation → corrector powering!

Identity Card of Cryodipole HCLBBR_000-IN003416

Cold performance	
1st Quench (T)	8.58
2nd Quench (T)	-
Maximum Reached Field (T)	9
Number of Quenches to 9T	1
Number of Cooldowns	1
First Quench After Last Cd (T)	-
Cold Tests Class	G

ok
waiting1
waiting2
off limits

Advancement	
Arrival at CERN	2005-11-24
Connection to Test Bench	2005-11-30
Performance Assent	2005-12-12
MEB Approval	2006-05-16
Data Extraction	2006-05-12
Last Modified On	

Deviation from Geometric Axis

Measurement @ WP08-19

(mm)	V1	V2
α georef (mrad)	-0.367	
δx upstream	-0.302	-0.24
δz upstream	-0.162	-0.081
δx downstream	0.014	0.068
δz downstream	-0.173	-0.28
δx min	-0.316	-0.252
δz max	-0.415	-0.419
δx max	-0.456	0.301
δz min	-0.352	-0.342
δx average	0.016	-0.016
δz average	0	0
r upstream	0.342	0.253
r downstream	0.174	0.288
r body	-0.415	-0.419

Position of correctors

(mm)	V1	V2
MCS- δx	-0.066	-0.142
MCS- δz	0.037	0.03
MCO- δx		
MCO- δz		
MCD- δx		
MCD- δz		

Magnetic Field (Extrapolated to Cold)

Aperture 1 (V1)				Aperture 2 (V2)			
760A	EOI	EOR	11850A	760A	EOI	EOR	11850A
TF	10.109	10.111	N/A	10.051	10.113	10.115	10.055
ML	14.303	14.303	N/A	14.304	14.303	14.303	14.304
FD	N/A	N/A	N/A	N/A	N/A	N/A	N/A
b1	-12.81	-11.33	N/A	-16.12	-8.94	-7.45	-12.23
b2	0.86	0.86	N/A	-0.61	-0.95	-0.95	0.51
b3	-5.16	-3.31	N/A	2.03	-5.94	-4.10	1.25
b4	-0.07	-0.06	N/A	0.13	-0.03	-0.03	-0.23
b5	0.51	0.20	N/A	-0.70	0.44	0.13	-0.77
b6	-0.03	-0.03	N/A	-0.03	-0.04	0.00	0.00
b7	0.64	0.66	N/A	0.95	0.66	0.68	0.97
b8	-0.03	-0.03	N/A	-0.02	0.01	0.01	0.00
b9	0.57	0.55	N/A	0.34	0.56	0.53	0.32
b10	0.00	0.00	N/A	0.00	0.00	0.00	0.00
b11	0.67	0.67	N/A	0.64	0.67	0.67	0.64
a2	1.57	1.54	N/A	1.60	1.77	1.80	1.74
a3	0.25	0.28	N/A	0.24	0.36	0.38	0.34
a4	-0.40	-0.41	N/A	-0.41	0.29	0.30	0.30
a5	0.08	0.08	N/A	0.08	0.14	0.14	0.14
a6	0.03	0.03	N/A	0.03	0.12	0.12	0.12
a7	-0.02	-0.03	N/A	-0.03	-0.03	-0.04	-0.04
a8	-0.01	-0.01	N/A	-0.01	-0.01	-0.01	-0.01
a9	-0.05	-0.05	N/A	-0.04	-0.07	-0.07	-0.06
a10	0.00	0.00	N/A	0.00	0.00	0.00	0.00
a11	-0.08	-0.08	N/A	-0.08	-0.11	-0.11	-0.11

Important Specifications

No remaining non-conformities

Dispositions of the Magnet Evaluation Board

Assigned to the slot LBBRA.13L7 (sector 67)

[N. Sammut et al, WEPLS104] [G. RijkWEPLS100]