

# Design and Construction Progress of a 7 MeV/u Cyclotron

Wang Bing

Institute of Modern Physics,CAS

H.F. Hao, J.Q. Zhang, M.T. Song, Q.G. Yao, L.Z. Ma, S.H. Zhang, X.W. Wang,  
A.M. Shi, Z.M. You, X.T. Yang, D.Q. Gao, X.Q. Zhang, K.D. Man, Y. Cao, H.W. Zhao

# Outline

## ■ Introduction

## ■ Concept design


- Magnet
- rf system
- ECR ion source and axial injection line
- The central region
- The extraction system
- Transmission efficiency
- Vacuum system

## ■ Construction Progress


## ■ Summary

# Introduction

- Injector for the HITFiL(Heavy Ions Therapy Facility in LanZhou) synchrotron
- Compact Commercial Cyclotron
- $^{12}\text{C}^{5+}$   $W_{\text{ex}}=7 \text{ MeV/u}$ ,  $I_{\text{ex}}=10 \text{ e}^{\mu} \text{ A}$ ,  $\varepsilon = 20 \pi \text{ mm.mrad}$ ,  $\Delta W/W \leq \pm 1\%$




# Configuration of the cyclotron






# Magnet

Outer Radius of the Magnet	1440mm
Height of the Magnet	1600mm
Radius of the Pole	840mm
Number of Sectors	4
Sector Angle	56°
Gap between the Hills	50mm
Gap between the Valleys	360mm
Field in Hills	1.87T
Total Weight of Iron	70 t
Ampere-Turn Number of the Main coils	70 kAT




30/??/2010 10:15:57





# rf system

rf Frequency	31.02MHz
rf Voltage	70 kV
Harmonic Number	4
Number of Dee	2
Angle of Dee	30°
Outer Radius of Dee	770 mm
Number of Cavity	2
Q Value	7800
Dissipated Power per Cavity	18 kW




$$\Delta V/V \leq \pm 5 \times 10^{-4}/24h ,$$

$$\Delta f/f \leq \pm 1 \times 10^{-6}/24h ,$$

$$\Delta \phi \leq \pm 1^\circ$$

Tow 50 kW rf amplifiers




# ECR ion source (LAPECR3)

Beam current 200euA

Extraction voltage 22.3 kV

Beam emmitance 120 pi mm mrad

Mw frequency 13.75-14.5 GHz



# Main parameters of ECR ion source

	LAPECR3
Axial magnet (T)	2.0-0.40(~0.43)-0.94(~0.91)
Radial magnet $B_w$ (T)	1.14
Width of magnet mirror (mm)	170
Mw frequency (GHz)	13.75-14.5
Plasma charmer diameter(mm)	50-51
Effective charmer (L)	0.33
Rf feed mode	WR62 rectangle wave guide
Charmer cooling	Water cooling
Max. extraction voltage (kV)	25-30
Max. mw power (kW)	0.75
dimension (mm)	$\varnothing 450 \times 380$
NdFeB weight (kg)	157
Main material	N50M & N42SH

# Axial injection line

$L=3.446$  m,

## 4 solenoids

## 1 quadrupole


1 double 90°magnetic dipole

# 1 buncher

# 1 chopper

## 1 slit


## 1 Farady Cup






# Elements parameters

	Number	Effective length (m)			aperture (cm)	Field strength (kG, kV)		
solenoid	4	0.15			10	3.5		
quadrupole	1	0.15				0.1(kG/cm)		
magnetic dipole ( double 90 ° )	1	radius	0.38		Pole gap	1.0		
		Def. angle	90°					
		Edge angle	in	39 °				
			out	0°				
Chopper	1	0.12			Wid. Gap	8 4		
Buncher Sinoid 31.02MHz	1	—			8	1.5		
Correction magnet	2	0.1			10	0.12		

# Envelope of the beam line











Buncher efficiency 45%




Phase width  $\pm 10^\circ$

# The central region


Electric bend radius	30 mm
Magnetic bend radius	27 mm
Electrod spacing	8 mm
Electrod width	16 mm
Orientation angle	-54°
Voltage of electrodes	$\pm 5.5$ kV









# Configuration of central region




Overlook of the central region




Lateral view of the central region



Median plane electric field map



Accelerating trajectories



Vertical motion


# Extraction system

Extraction system



1 bump coil

1 electrostatic  
deflector

1 deflect magnet




# bump



maximum magnetic  
field 400 Gauss


# E1



Electric field 85 kV/cm

Gap 10 mm




# M2



Magnetic field 1.1 T

Gap 30 mm

Width 30mm



# Transmission efficiency

transmission efficiency=number of particles unlost/number of total particles

- Inflector entrance

- a buncher

- emmitance  $120 \pi \text{ mm mrad}$ ,

- $\Delta \phi = \pm 10^\circ$ ,  $\Delta W/W = \pm 1\%$ , Buncher efficiency 45%

- 10,000 particles

- Central region (5 turns) 7997 particles

- Injection efficiency 35%

- Acelerated to 7 MeV/u and extracted at the end of M2  
extraction efficiency 20%

Total transmission efficiency 7%  
Extracted beam current  $14 \text{ e} \mu \text{ A}$

# Vacuum system

- 4 cryogenic pumps of 5000l/s.
- vacuum of principle chamber was  $5 \times 10^{-7}$  mbar
- vacuum of injection line was  $1 \times 10^{-7}$  mbar.

# Construction Progress

- *ECR Ion Source*  
The engineering design had been completed.  
Integrate the permanet magnetism material in IMP,CAS
- *RF System*  
The construction design of tow 50 kW rf amplifiers had been finished.  
End of Construction: December 2010  
The cavity's engineering design is conducted.
- *Axial Injection Line*  
The engineering design had been finished.
- The power supplies for the magnet coil, injection and ectraction equipments had been contracted.
- The construction of other items, e.g. the magnet, the vaccum chamber, the spiral inflector, the electrostatic deflector is conducted.

# Summary

- The beam dynamic study of the 7 MeV/u cyclotron had been completed.
- The concept design meet the requirement from synchrotron
- Engineering design of the cyclotron is conducted ,except ECR ion source ,rf amplifiers, and injection line.

Thanks