# **Experience with RCS Injection** and Extraction Systems

*Inj. And Ext. of the Main ring(MR)* → Dr. T. Koseki (this morning)

### **Pranab SAHA** for the RCS of J-PARC

August 27, 2008

#### 42nd ICFA

Advanced Beam Dynamics Workshop on High-Intensity, High-Brightness Hadron Beams (HB2008) (Nashville, Tennessee, USA. August 25-30, 2008)

# **Introduction and Outline**

Injection is one of the key issues of RCS and has impact on the whole system, where an well extracted beam reflects the overall performance.

In order to mitigate the space-charge effect, the beam density in the transverse plane is controlled by utilizing the painting injection in RCS

#### General

Injection system, Extraction System

- Beam commissioning of Injection and Extraction Comparison with design stage parameters, System performance
- Painting injection study

Reconstruction of the phase space footprint using (1) BPM pairs with a turn-by-turn mode, (2) Using a tune BPM spectrum

Beam loss at the injection and Extraction

*Comparison with design stage estimation Near future study concerning beam loss related to injection* 

#### Summary

#### **J-PARC** Facility



## **RCS Injection and Extraction Systems**



## **Injection scheme in RCS**



Measured response matrix with ISEP1,2 and MWPM3,4,5
 → Used for controlling X and X' of the inj beam at the foil paint inj parameters in the hori. Plane

Measured response matrix with IVSTR1,2 and MWPM3,4,5  $\rightarrow$  Used for controlling Y and Y' of the inj beam at the foil.

For painting in the vertical plane, measured response with VPB1,2 and MWPM3,4 was used Design twiss parameters at the foil w/ nominal tune

	Inj. beam	Circulating
beam		
$\alpha_{\rm x}$	-1.452	1.550
$\beta_{\rm x}({\rm m})$	11.138	11.275
$\alpha_{ m v}$	-0.400	-1.589
$\hat{\beta_v(m)}$	10.998	11.062
$\dot{\eta_x}(m)$	0.00	0.00
η' <sub>x</sub>	0.00	0.00

Paint area for MLF target: 216π.mm.mrad Paint area for MR inj: 144π.mm.mrad (@ 400 MeV Linac)

To change painting area in the horizontal plane, X' of the inj beam will be change by two pulse steering magnets(PSTR1,2)

# Beam commissioning of Injection and Extraction

#### Linac Energy: 181MeV Peak current: 5mA

\* Run#9 data

#### *Inj.–H0 dump line orbit looking from RCS central orbit*

	IBPM	MWPM2	BigBpm1	MWPM3	MWPM4	MWPM5	BigBpm2	MWPM6	MWPM7
Cal:	418.6	226.0	214.7	<i>133.7</i>	87.70	132.2	213.5	481.0	3416
Meas:	412.0	228.8	214.0*	<i>133.4</i>	87.70	<i>132.3</i>	219.0*	491.1	<i>3435</i>

Comparison of Magnet Parameters (K0)				
	Cal(mrad)	Used(mrad)	Diff(%)	
ISEP1	107.0	110.0	+2.8	
ISEP2	160.4	173.8	+8.35	
DSEP1	146.4	144.0	<b>-1.66</b>	
DSEP2	311.4	317.4	+1.93	

 Measured response matrix near the present orbit was exactly similar with the model cal
 → Efficiently used for the beam commissioning in both the center and paint injection.

Present center inj orbit is very much different than the design painting orbit, while 2 Pulse STR magnets in addition to septum using in the design stage are not available. The beam orbit passes very off-center through ISEP2, where no field measurement through this orbit couldn't reach →May be the main reason!!

w/ paint orbit (100p), the difference becomes: +5.3%
→ Gets better but not sufficient → under study

Concerning extraction, no sufficient data but the overall agreement is satisfactory

Unlike, injection area, there are lack of monitors in the extraction section

# Stability of the injection and extraction beam (system performance)

#### Inj. Beam jitter @ last few BPMs in the L3BT line



In RCS, the fluctuation of the **Shift bump** flat top was within ± 1%, while all other DC magnets both in the injection and the extraction line were just stable!



Stability of the ext. kicker magnets: ~ 0.2%  $\rightarrow$  Dx ~0.1mm at the exit of ext. septum  $\rightarrow$  negligible

Finally, the ext. orbit stability was measured as follows:



## Painting injection study: Run# 16, 17



## Painting injection study: Run#16, 17

The top of the paint bump first fixed with a constant pattern by measuring directly the phase space coordinates at the foil using MWPM 3&4

The decay pattern was then made using following functions: Hori: I<sub>max</sub>[1-Sqrt(t/T)] Vert: I<sub>max</sub>[Sqrt(t/T)]

Pattern for  $150\pi$  and  $200\pi$  were scaled from  $100\pi$  and was perfect !!





## Painting injection study cont'd



## **Checking of both methods first**

( matching of the injection and the closed orbit )



Then, starting with  $100\pi$  painting, at first balance of 4 horizontal paint bump magnets were adjusted by measuring and correcting the COD during the paint bump on(0~1msec). Parameters for  $150\pi$  and  $200\pi$  were then just scaled.

Vertical direction:  $\rightarrow$  By measuring directly Y and Y' of the inj beam at the foil with MWPM3,4

Measured Twiss parameters @ foil			
Inj. Beam:	Circulating beam		
α <b>x=-0.3302</b>	α <b>x=1.714</b> 4		
α <b>y=-0.23088</b>	α <b>y=-1.8712</b>		
β <b>x=3.2207m</b>	β <b>x=12.9575m</b>		
β <b>y=4.8071m</b>	β <b>y=12.3682m</b>		
εx,εy $\approx$ 3.5π.mm.mrad (3σ)			



Normalized phase space plot of the beam center measured by BPM turn-by-turn data



# Painting study results





## **Footprint with Horizontal paint bump**



#### Footprint with vertical decay pattern( $100\pi$ ) Horizontal and vertical together(100 $\pi$ )

**SB(620us)** PB(500us 12 13 14 time Vert. paint bump @ decay pattern

Pattern moved t0~t5 w/ 100 µs step

In the vertical plane, only with  $100\pi$ painting study was performed. Reconstructed footprint in the vertical plane found a bit zigzag but finally gets to the expected position.

A correlated painting study with  $100\pi$  was also performed and the reconstructed results were expected

Basic painting study in Run#16 was done very successfully. BPM with single pass mode was found to very effective and accurate. (Detail with method 2 under analysis)

Y'(mrad)

0

-2

-4

-40

-30

Paint bump patterns made in this study was used for the painting with high power run



Y(mm)

## **Beam loss @ Injection and Extraction areas**



# Beam loss in the RCS injection area (Estimation vs. reality)

Major sources and quantity of the beam loss in the injection area:

(Considering inj beam power of [18kW [0.3MW@RCS extraction])

 Lorentz striping loss of the injection(H-) beam: << 1W</li>
 → Inj beam line clean!!

2. H0 excited states losses: < 2W → 1st foil to the bump region clean!!

3. Nuclear scattering together with multiple coulomb scattering at the charge-exchange foil:
 → Major source among all Total loss: 38W(~0.2%)

P.K. Saha, PAC07 (GEANT + SIMPSONS) Simulation with Real painting process (Space charge: off) Foil size: 32mm x 36mm (design) and with ideal bump systems Average foil hits: 24



## **Summary and future plan**

The injection and extraction systems of RCS are found to be performed well during the beam commissioning so far.

Except one case, design stage parameters are found to be consistent with the beam commissioning parameters, where the relative values were exactly similar each other
 → Beam commissioning proceeded quite smoothly for any operation

Painting study utilizing one intermediate pulse injection was successfully performed by measuring accurately the phase space footprint.. → Phase space control can be done in the painting inj.

Estimation of the beam loss in the design stage was found to be consistent. Detail study with nuclear scattering loss is planned to perform in the next run.

### Discussion on several questions by the committee

#### Does the system perform as expected?

Ans: System performance satisfactory so far! No remarkable trouble concerning inj and ext. Bump system working fine. Problem remains with Bump falling time and hope soon gets better. Foil system gets recovered

# Did the simulations/calculations performed during the design stage accurately predict the actual performance?

Ans: Yes. Inj and ext. beam orbit even with very different parameters goes through expectation. The beam profiles are also quite similar.

The relative parameters of all magnets are exactly similar to the simulation/calculation. Needs more experimental data

#### What are the major limitations in performance? Were they known in the design stage?

Ans: Foil system was one big limitation of the injection commissioning. But it's going to be fine from the next run. So far not face any other big limitation and would be clear with long time (and high power) operation. No BPM in the extraction section is one small limitation concerning extraction.

If someone were to begin now designing the same type of system for a similar machine, what is the one piece of advice that you would give them?

Ans: Please try to have enough monitors, especially in the complicated areas like injection and extraction.

Keep (check for) enough space for not to push nearby magnets/elements nor make thinner the shield at the last moment to install later elements/magnets

#### Backup Slide 1 Results with constant flat top cont'd (for $150\pi$ , $200\pi$ painting)

**150\pi Target:**  $\Delta x = -39.86 \text{ mm}$  $\Delta x' = 5.65 \text{ mrad}$ 

Result from single pass BPM 1101 pair: -35.1 mm, 5.83 mrad 1902 pair: -36.6 mm, 5.92 mrad

Measuring with MWPM3,4

 $\Delta x = -39.30 \text{ mm}$  $\Delta x' = 5.92 \text{ mrad}$ 

w/ inj beam 150π paint orbit but PB off: 1101 pair: 37.2 mm, -6.13 mrad
1902 pair: 36.3 mm, -5.90 mrad **200\pi Target:**  $\Delta x = -47.02 \text{ mm}$  $\Delta x'= 6.67 \text{ mrad}$ 

Result from single pass BPM 1101 pair: -42.5 mm, 6.85 mrad 1902 pair: -42.8 mm, 6.81 mrad

Measuring with MWPM3,4  $\Delta x = -48.05 \text{ mm}$  $\Delta x' = 7.076 \text{ mrad}$ 

Not measured w/ inj beam  $200\pi$  paint orbit but PB off

Backup Slide 2

### Bump pattern@paint inj study





#### Backup Slide 3 Measured beam profile by MWPM



The mean and the width of the measured profiles in the U and V planes were transformed to the X and Y plane as follows:

$$\begin{pmatrix} u \\ v \end{pmatrix} = \begin{pmatrix} \cos\theta & -\sin\theta \\ \sin\theta & \cos\theta \end{pmatrix} \begin{pmatrix} x \\ y \end{pmatrix} \frac{\theta \text{ is the wire inclination:}}{17.7 \text{ deg.}} \begin{pmatrix} \sigma^2 u \\ \sigma^2 v \end{pmatrix} = \begin{pmatrix} \cos^2\theta & \sin^2\theta \\ \sin^2\theta & \cos^2\theta \end{pmatrix} \begin{pmatrix} \sigma^2 x \\ \sigma^2 y \end{pmatrix}$$

#### Backup Slide 4 Ext. Kickers flat top measurement



□ Required flatness = 2 % in the time length of 840 nsec

■The trigger timing of the each kicker was adjusted in order to cancel out the peaks and troughs of the flattop.

The flatness of 2 % was achieved in the time length of 850 nsec!