



Beam diagnostic system of the main ring synchrotron of J-PARC

HB2008

August 25th-29th, 2008

Nashville, Tennessee, USA


K. Satou, T. Toyama, D. Arakawa, M. Arinaga, S. Igarashi, J. Odagiri,
M. Masaki, M. Tobiyama, Y. Hashimoto, S. Hatakeyama, K. Hanamura,
N. Hayashi, S. Hiramatsu, K. Kazami, H. Matsumoto, J. Takano, and S. Lee

KEK/JAEA

Table of Contents

- **Introduction**
 - Location of instrumentations
 - Requirements for beam monitors
 - Day-one beam parameters
- **Countermeasures for noise problems**
- **Present status of instrumentations**
 - Beam position monitor
 - Beam current monitors
 - Tune monitor
 - Beam loss monitor
 - Profile monitors
- **Summary**



J-PARC



Location of instrumentations

List of ring monitor (Blue:future plan)

Monitors	Number
BPM	186
Single-pass BPM	2
Dump/abort BPM	2 + 2
WCM(>100MHz)	3
FCT(~20MHz)	6 + 1 (v-BT)
DCCT(DC-30kHz)	2
MWPM	1 (inj.), 2 (SX, Abort BT)
Flying Wire (H/V)	1 / 1
IPM (H/V)	2 / 1
BLM	Proportional type 238 Ion chamber type 18



Ref. T. Koseki, HB2006

List of 3-50 BT monitor (Blue:future plan)

Monitors	Number
Single-pass BPM	14
FCT(~20MHz)	5
MWPM	5 + 4
BLM	Proportional type 50 Ion chamber type 3


Requirements for beam monitor

J-PARC MR Beam power : $\sim 500 \times$ (KEK-PS beam power)

However,

Beam loss criteria: **0.5 W/m** same as KEK-PS!!

This criteria corresponds to 1.8% (3GeV) $\sim$ 0.1%(50GeV) beam loss



Beam power up to J-PARC

- Beam loss monitoring covering <0.1% to 100%, dynamic range which is over 10^3 level
- Beam halo monitoring because beam loss originating from halo formation may limit beam current
- Beam current monitoring with wide band and high dynamic range for delicate tuning of RF system

Challenging and essential issue!!

Day-one beam parameters (May, June 2008)

- 100-1000 turn 3 GeV DC mode
- 1/100 particle per bunch
- 1 Bunch inj.




	Design	Day-one	
Particle per pulse	3.3×10^{14}	$4-5 \times 10^{11}$	ppp
Number of Bunch	8 (h=9)	1 (h=9)	
Peak current	41.3-220	3	A
Circulating current	12.4-12.8	0.12-0.14	A
velocity	0.9712-0.9998	0.9712	1/c
Bunch half width	180-33.7	40-60	ns
Revolution frequency (1 / f)	186-191 (5.38-5.24)	186 (5.38)	kHz (μ s)
RF frequency (1 / f)	1.67-1.72 (599-581)	1.67 (599)	MHz (ns)

Countermeasures against noise problem

- High shielded cables tested radiation hardness at Co60 yray facility of Takasaki lab./JAEA
- Grounding copper plates along the ring
- Noise cut trans in an AC line
- Common mode choke coil in a signal line




Grounding copper plate




1/6

Connect a electric shield to a grounding copper plate



4 in 1 coaxial cable for BPM



34 in 1 coaxial cable for MWPM and IPM

High shielded cables with radiation hardness
($<2.5\text{MGy}$) for J-PARC Fujikura Ltd.

BPM


Electrostatic type BPMs are installed near almost all QM

Ring BPM:

- Mainly used in the ring
- Good linear response covering full aperture
- Bore: $\Phi 130\text{mm}$ (standard),
 $\Phi 134, 165, 200, 250, 320\text{mm}$ (special)



Calibration : wire method





Error (in rms unit)

- Sensitivity: ± 0.00004
- Offset: $\pm 0.12\text{ mm}$
- Rotation: $\pm 3.6\mu\text{rad}$


Single pass BPM:

- Mainly used at 3-50BT
- Bore: $\Phi 230, 200\text{mm}$




Ring BPM


- Lower cut-off frequency is 17MHz $\Rightarrow$ differential wave form
- 14 bit, 10MHz, 80 MS/s ADC
- Off-line position calc. (COD mode): Raw signal (4096 point) $\Rightarrow$ average over 4 data (1024 point) $\Rightarrow$ FFT $\Rightarrow$ peak search ($3.4\text{MHz} = 2 \times f_{\text{rf}}$) $\Rightarrow$ Position



Raw signals



FFT of the raw signal
Blue: Signal+noise
Green: noise



Measured COD

BPM installation error (in rms unit)

- Offset: $\Delta x = 0.41 \pm 0.96\text{mm}$, $\Delta y = -0.35 \pm 0.50\text{mm}$
- Rotation: $0.96 \pm 3.3\text{ mrad}$


K. Hanamura et al

Not yet calibrated



Present position resolution: $\sim 0.5\text{ mm}$

Single-pass BPM (3-50BT)

- To expand lower cut-off frequency, a transformer has installed at an output connector $\Rightarrow$ 230kHz
- 8 bit, 100MHz, 2GS/s ADC
- Q-mode measurement (future plan)



2:15 transformer at output connector





Beam current monitors

DCCT

S. Hiramatsu *et. al*


- FINEMET (HITACHI metal Ltd.) core
- Frequency band: DC~20kHz
- Gain selection: 0.2A, 2A, 20A
- $\Delta I < 100\mu A \Rightarrow \Delta N_B \sim 6.5 \times 10^9$ ppp(rms)



FCT

D. Arakawa *et. al*

- FINEMET (HITACHI metal Ltd.) core
- Frequency band: 16Hz~180MHz
- RF phase feedback



WCM

D. Arakawa *et. al*


- FINEMET (HITACHI metal Ltd.) core
- Lower cut-off frequency: 150, 380, 400
- Shunt impedance: 92mΩ
- Heat load on resister is 40-50W
 $\Rightarrow$ Air blow system is needed
- RF feedforward for beam loading

Tune meter

- Horizontal and Vertical exciters have been installed
- The maximum exciter power is 2kW input by using white noise with band width of 1-2MHz
- Beam oscillation is analyzed by “Real-time spectrum analyzer”




Photo. of an exciter





Measured betatron oscillation frequency

Resolution of tune: $\Delta\nu \sim 0.007$

Beam fluctuation due to ripple of power supply was measured




BLM1



Gain curve of the BLM measured by using secondary cosmic rays, mainly muon




BLMs have been installed at each QM




Raw signal
bias: 1.6kV, Z_{in} of amp: 50Ω , amp gain: $\times 10$

BLM2

- Sum of beam loss signals from inj. to ext.
- Loss signals are just shown in arbitrary unit
- HV=1.6kV, Zin=1kΩ, amp gain=10



Beam loss distribution



Correlation between sum of all BLM signals
and a number of loss particle

Error: $\pm 18\%$ $\Rightarrow 3 \times 10^{10}$ ppp

© Beam loss criteria

0.5W/m for 0.75MW, 3.3×10^{14} ppp

0.1% for 50 GeV $\Rightarrow 1.6 \times 10^9$ ppp at each BLM



1.8% for 3 GeV $\Rightarrow 29 \times 10^9$ ppp at each BLM

We should study more about


- Error source
- Reliability on AC mode operation
 - Signal dependence on beam energy
- How to determine the HV
 - Space charge problem should be considered on high gain operation

Multi-wire profile monitor: MWPM

- Wire target using tungsten wire of 30 μm for day-one
Number of channel: 32 / 64
Pitch: 2.5, 3.5, 4.0, 4.5 mm
- Carbon ribbon type target is under development






Typical wire target



Measured horizontal beam profile

Flying wire profile monitor

- One horizontal type for day-one
- Vertical one is now under development
- Wire: Carbon fiber of 7 μ m in diameter
- Wire speed: 10m/s
- 1 profile / 0.1s



Residual gas ionization profile monitor: IPM

Ion collection with HV

- 35kV for day-one $\Rightarrow$ will be upgraded to 50kV

Electron collection with magnetic field

- Require for 0.75MW beam profile measurement
 $\Rightarrow$ future plan

Micro Channel Plate (MCP) for signal read out device


- 2 stage MCP assembly with 32 ch strip anode
- Active area: $31 \times 81 \text{ mm}^2$
- Width of each anode: 2.5 mm
- Gain: $\sim 10^6$

Calibration devise to check MCP gain balance


- Electron generator arrays $\Rightarrow$ Photonis Ltd.

Need averaging to reduce the statistical error due to number of ions

- Number of ions is about a several 10000 per bunch for designed beam, that is only a several hundreds for day one beam



Turn by turn beam profile





Cross section of V-IPM


Summary

- Various instrumentations are installed and used on Day-one beam commissioning
- The beam current was 1/100 of designed value, however, the system shows good performances
- Some monitors will be installed until this December
 - Two horizontal IPMs $\Rightarrow$ straight ($\eta=0$) and arc. ($\eta=2.0\text{m}$) sections
 - One MWPM and 2 BPMs for abort dump line
 - Six Screen monitors for slow extraction line
 - One FCT for ν BT line
- The performance tests on AC mode (up to 30 GeV) operations will start from this December


Signal flow diagram of IPM



BLM calibration setup



Peak pos. vs. HV was measured



Energy spectrum of secondary cosmic rays (muons)

FCT: frequency response

