



SRF Cavity Development for Project X



Project X

- Unique proton facility based on a 3 MW, 3 GeV SRF continuous-wave (CW) linac & 3-8 GeV pulsed SRF linac
 - Multiplies low-energy flux of protons at Fermilab by 100
 - Enables a broad program of Intensity Frontier Physics experiments
- Support experiments simultaneously at 1 GeV, 3 GeV, 8 GeV and 60-120 GeV at high beam power
 - Delivers >2 MW to Long Baseline Neutrino Experiments simultaneously with >3 MW for rare decays
- Can serve as a future front end of neutrino factory or muon collider

Project X Layout



PX Reference Design Performance Goals

Linac

Particle Type
Beam Kinetic Energy
Average Beam Current (1/3 GeV)
Linac pulse rate
Beam Power to 1 GeV program
Beam Power to 3 GeV program

H⁻
3.0 GeV
2/1 mA

CW

1000 kW

2870 kW

Pulsed Linac

Particle Type
Beam Kinetic Energy
Pulse rate
Pulse Width
Cycles to Recycler/MI
Particles per cycle to Recycler/MI
Beam Power
Beam Power to 8 GeV program

H⁻
8.0 GeV
10 Hz
4.3 msec

6

2.7×10^{13}

340 kW

170 kW

Main Injector/Recycler

Beam Kinetic Energy (maximum)
Cycle time
Particles per cycle
Beam Power at 120 GeV

120 GeV

1.2 sec

1.5×10^{14}

2400 kW

simultaneous


SRF Cavity and CM R&D at Fermilab

- Adoption of a 3 GeV CW linac followed by a 3-8 GeV pulsed linac for Project X in 2010 results in a powerful new intensity frontier machine, but presents new challenges
 - Need six different cavities optimized for changing velocity (β) of Protons
 - Four different frequencies (162.5, 325, 650, 1300 MHz)
 - Five of these cavities are completely new for Project X (vs. 2 for SNS)
 - CW cavities → large heat loads, 2 K operation → changes to CM designs
 - Operation at significantly higher gradients than SNS to reduce costs
- **The development of these cavities & CM is a major new effort**
 - A strong R&D program is needed to reduce risks and costs
 - Need to design, order, process new cavity types and cryomodules
 - Benefits enormously from the SRF infrastructure and the experience gained with 1300 MHz cavities and CM development for ILC

Technical
Risk →
Prototype
(PXIE)

Project Cost Risk


PX SRF Linac Technology Map



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
HWR ($\beta_G=0.11$)	162.5	2.1-10	9 /6/1	Half Wave, solenoid
SSR1 ($\beta_G=0.22$)	325	10-42	16/8/ 2	Single Spoke, solenoid
SSR2 ($\beta_G=0.47$)	325	42-160	36/20/4	Single Spoke, solenoid
LB 650 ($\beta_G=0.61$)	650	160-460	42 /14/7	5-cell elliptical, doublet
HB 650 ($\beta_G=0.9$)	650	460-3000	152/19/19	5-cell elliptical, doublet
ILC 1.3 ($\beta_G=1.0$)	1300	3000-8000	224 /28 /28	9-cell elliptical, quad

Accomplishments

162.5 and 325 MHz Cavities



- **HWR ($\beta = 0.11$) Half Wave Resonator (collab ANL)**

- Cavity design complete, ordering parts, CM design in progress
- Very similar to cavities & CM already manufactured by ANL
- Optimize to achieve tight packing in PX front end




- **SSR1 ($\beta = 0.22$) Single Spoke Resonator**

- Started under HINS program and is therefore more advanced
- Two prototypes fabricated by industry, processed in collaboration with ANL, and tested at Fermilab as part of HINS
- One cavity dressed with He vessel, coupler tuner
- Two cavities in fabrication at IUAC-Delhi (Q3 FY13)
- Ten cavities fabricated by US industry (6 have arrived, 2 tested)
- Tests in progress (next slides)






- **SSR2 ($\beta = 0.47$)**

- EM design complete
- Mechanical design is advanced
- Prototype in FY13-14




Half Wave Resonators for Project X (ANL)

- 162.5 MHz $\beta_{opt}=0.11$ Half Wave Resonators (HWR) are very efficient for low velocity Protons (or H-)
- Only one cryomodule of HWRs is required for acceleration from 2.1 MeV to 10 MeV in Project X
 - Total accelerating voltage in the HWR CM is 13.6 MV
 - Single Cryomodule < 6 meters long provides comfortable margins
 - Comparable with the ATLAS cryomodules built at ANL (hence collaboration)



325 MHz Test Capabilities Developed




SSR-1 prototypes are tested in the VTS-1 vertical dewar (normally used for 1.3 GHz cavity testing) with the addition of new electronics and tooling.



Spoke Test Facility enables testing of "dressed" 325 MHz single-spoke resonators.

Operated previously at 4.8 K (pulsed RF)
Upgrades for 2 K CW operation in process




Dressed SSR-1
Includes RF couplers, tuners, and magnetic shielding

Prototype tested in STF, excellent results at 4.8K

SSR1 Fabrication at Roark



New SSR1 Prototypes Exceed PX Performance Specs.



- 120-150 micron BCP and HPR at ANL/FNAL processing facility then 120 C bake
- Low FE depends on optimized nozzle design for effective HPR of surface

- Two previous SSR1 spoke resonators performed very well in bare cavity tests
- This is first test of 2 cavities from U.S. Vendor (Roark) production of 10 cavities
- Performance at 2 K is above requirements for Project X in both Q_0 and gradient
- Revised design of helium vessel and tuner are nearly complete
- Ordering parts
- Expect to dress cavities in FY13 for first SSR cryomodule

650 MHz Cavity Development & Prototypes

- 650 MHz cavities/cryomodules are cost drivers for Project X
 - Studying cost reduction methods & Q_0 improvement
- Status & Prototypes:
 - Two single-cell $\beta = 0.6$ cavities prototyped at JLab
 - Six single-cell $\beta = 0.9$ cavities prototyped recently received from U.S. industry, Four five-cell $\beta = 0.9$ cavities ordered (AES)
 - 5 additional single cell and 5 five-cells $\beta = 0.9$ cavities ordered from industry (PAVAC) on ARRA funds
 - Prototypes at both β are also being fabricated in India





5-cell EM and mechanical design complete



650 MHz Cavity Processing & Testing





- **Infrastructure modifications:** for 650 MHz complete
 - FNAL: Vertical Test Stand: Electronics, top plate
 - FNAL: Cavity handling & HPR tooling, etc.
 - FNAL: Optical inspection system modifications
 - ANL: New electro-polishing tool operational for HWR and 650 MHz cavities
- **Prototype tests:** Single cells processed and tested at both JLAB and ANL/FNAL
- Both single-cell $\beta = 0.6$ cavities show excellent Q_0 at Project X gradients (JLAB and FNAL tests)
- Single cell $\beta = 0.9$ cavities will be processed and tested at ANL/FNAL in the Fall
- Expect 1st five cell cavities from AES in Q1 FY13



**650 MHz 1-cell $\beta = 0.6$
test at JLAB**

650 MHz CM Design Status

- Cryomodule conceptual design advanced
 - Very high heat flux (over 200 W per CM)
 - Stand-alone 8-cavity cryomodule, variant of ILC CM
 - Looking at tuner options (blade vs lever vs wedge)
 - 3-D CAD models, collaboration with India




1300 MHz Development for PX

- **Has been driven by:** ILC SRF goals
 - S0 >35 MV/m bare cavities
 - S1 31.5 MV/m dressed cavities in a ILC Cryomodule
 - S2 Beam test of full ILC RF unit (CM, klystron, modulator)
- All of this benefits the 3-8 GeV pulsed linac for Project X

- **Accomplishments:**

- Excellent progress on gradient improvement
 - ANL/FNAL EP facility: world class performance
 - 18 Dressed cavities
 - CM2 populated with 35 MV/m cavities,
 - Parts for 4 more 1.3 GHz cryomodules
 - Cost reduction (e.g. tumbling vs. EP, & cavity repair)
- Excellent progress on all of these
 - **CM1 tests complete, CM2 installation in progress**




NML Status and Plans

CM2 installation





CM1 tests complete, swapping for
CM2, high gradient CM,
All U.S. Processed Cavities

CM1 ave gradient = 23.7 MV/M



CM2 ave gradient = ~35 MV/M




- Learning a lot! (CM assembly, tuners, LLRF, finding leaks in CM, etc.)
- Installing 40 MeV photo-Injector (end of FY13)
- Operating NML as CM test stand
- With the end of ILC funding in FY13, submitting proposal to DOE finish this facility and operate as an AARD facility

SRF Materials Research


- SRF Materials R&D program focuses on
 - Scientific understanding of SRF surfaces leading to:
 - High gradients, Q_0 , and manufacturing yield
 - Nano-scale understanding of performance limitations
 - Targeted cavity process improvements
 - Material Quality Control (Nb spec., eddy current scan, optical inspection)
 - EP Science and CBP @ ICPA
 - Study H uptake and effects which promote hydride precipitates leading to Q slope
 - Leverages collaborations with Universities and other institutions
 - Multiple ongoing university research initiatives ~10 students/post docs
 - Game-changing improvements (Nb film deposition, coatings, plasma cleaning...)
- SRF Materials R&D level of effort:
 - ~7 FTE staff, ~\$600K M&S, including operations of ICPA

Improving the Niobium Supply


Recent batch:
High tensile strength
Too many dislocations
Pitted cavities



Batch delivered in 2009
Low tensile strength
Few dislocations
No pitting after EP



After 30 μm EP
by FNAL at ANL



Niobium vendor found a new process that is less variable and exceeds our spec. Unfortunately, the new sheets were not compatible with later processing. Our SEM upgrade showed why, and led to a tighter specification.

Reference: A. Romanenko results

Centrifugal Barrel Polish




C. Cooper Recipe Media

- Breakthrough in the process @ FNAL
- Drastic reductions in acid use.
- Mirror-like inner surface
- Demonstrated cavity gradients > 35 MV/M
- FNAL CBP design has been adopted by several other SRF institutions




Cavity Results – CBP Repairs



ACC015
Before CBP



After CBP and 40
microns EP – Pit
completely removed



CAT003 After EP




CAT003 After CBP

- Demonstrated as a cavity repair method.
- Likely we can ultimately do NO chemistry!
- Exactly the process you want if you want to apply coatings to cavities (e.g. Nb-Cu)

SRF R&D @FNAL

World record cavity Q0's with NbN




- Early result, but a potential game changer for SRF CW applications! (cavity quench limited by defect)

Summary

- Project X is a powerful and flexible new proton source proposed for construction at Fermilab
- Fermilab is has mounted a large R&D effort to develop the cavities, cryomodules, SRF infrastructure and trained technical staff required to build this machine
- The FNAL SRF program
 - Supports both Project X, ILC, and other Office of Science goals
 - Leverages existing FNAL infrastructure (bldgs., cryo, etc)
 - Lots of infrastructure has been built and is now in operation
 - Focused effort to transfer SRF technology to U.S. Industry
 - Focused effort to understand the science of SRF surfaces with the goal of improving SRF cavity performance (gradient, Q0, reduced costs)
- Making steady progress towards our goals

extras

PXIE Program



PXIE goal = demonstrate:

- Ion source lifetime
- LEBT pre-chopping
- Vacuum management in the LEBT/RFQ region
- Validation of chopper performance
- Kicker extinction
- Effectiveness of MEBT beam absorber
- MEBT vacuum management
- Operation of HWR in close proximity to 10 kW absorber
- Operation of SSR with beam
- Emittance preservation and beam halo formation through the front end



New NML Buildings Complete (ARRA funded)




New Electronics building
above tunnel extension

New Cryomodule
Test Facility


New 500 W @ 2 K refrigerator
(under fabrication in industry)
will be located in CMTF bldg

Compressor building

PXIE




NML: RF Unit Test Facility



New FNAL SRF infrastructure



VTS



VTS



Cavity tuning machine



HTS



String Assembly



MP9 Clean Room



Final Assembly

VTS2 Dewar



New Vacuum Oven