

Acceleration of High-Intensity Protons in the J-PARC Synchrotrons

**KEK/JAEA J-PARC
M. Yoshii**

**HB2012 WE01C04
19 September 2012**

Introduction

- 1. J-PARC consists of 181 MeV Linac, 3 GeV Rapid Cycling Synchrotron (RCS) and 50 GeV Main synchrotron Ring (MR).**
- 2. High Intensity Proton Facility:**

	RCS	MR
Intensity (ppp)	8.3×10^{13}	3.4×10^{14}
Output Beam Power	1 MW	0.73 MW

- 100 times higher than the intensity of KEK-PS (1976-2007)

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high $\gamma_t \rightarrow 9.14$

MR: an imaginary $\gamma_t \rightarrow j31.6$

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high $\gamma_t \rightarrow 9.14$

MR: an imaginary $\gamma_t \rightarrow j31.6$

2. Non AC-line synched timing system

to realize the scheduled extraction for multiple Fermi choppers.

Features

1. Transition-free lattice

to avoid unwanted beam loss during acceleration.

RCS : a high $\gamma_t \rightarrow 9.14$

MR: an imaginary $\gamma_t \rightarrow j31.6$

2. Non AC-line synched timing system


to realize the scheduled extraction for multiple Fermi choppers.

3. Magnetic alloy loaded cavity with a full digital LLRF

to achieve high field gradient system (20kV/m)

to realize precise and reproducible fine longitudinal control


Locations of the RCS and MR RF Stations



RF systems are located the place where is the lowest radiation level for hands-on maintenance.


Beam Commissioning

1. RCS beam commissioning started in October 2007 with 10 RF systems. Protons were accelerated successfully up to 3 GeV in 31 [October 2007](#).
2. MR beam commissioning started with 4 RF stations in May 2008. Proton beam acceleration started in December 2008. Protons were successfully accelerated up to 30GeV in 23 [December 2008](#).
3. The RF systems were upgraded every year.



RCS beam commissioning

Energy	181MeV - 3GeV
Intensity	2.5×10^{13} ppp
Power	300 kW
harmonics / N _b	2 / 2
Frequency	0.938 - 1.67 MHz
# of cavities	11
Peak V _{acc}	400 kV
Cycle	25 Hz



1. RCS rf system: $Q \sim 2$, dual-harmonic ($h=2, 4$) operation.
2. radial feedback: not closed, because it is not necessary.
 - stable and reproducible Linac energy and RCS dipole field
 - frequency pattern is modified offline.
3. phase feedback: closed for high intensity operation
4. Multi-harmonic RF Feed-forward: ON for each of the cavities.

Beam Injection from the Linac


Linac Beam Pulse : 15 mA, 500 μ s
 $d\mathbf{p}/\mathbf{p} , \pm 0.03 \%$

- Chopping by the RCS RF clock
- Chopped pulses are injected into the RCS RF waiting bucket

○ minimize beam loss during bunching process





- Momentum offset
- Amplitude control for 2nd harmonic RF
- 2nd harmonic phase sweep

○ increase bunching factor
○ $B_f > 0.4$ required



Longitudinal painting at J-PARC RCS injection


longitudinal painting using 2nd harmonic voltages



Stable acceleration of 300kW beams in RCS

1. non AC-line synched timing system
2. no radial feedback


Ultra low-jitter extraction (jitter full width: 1deg = 1.7nsec)



Beam phase plot during 1-hour 300kW operation
(190 shots plotted). Right: magnified (19 - 20ms).

MR beam commissioning

Energy	3 - 30 GeV
Intensity	1.1×10^{14} ppp
Power	210 kW
harmonics / N _b	9 / 8
Frequency	1.67 - 1.72 MHz
# of cavities	7
Peak V _{acc}	240 kV
Repetition (period)	2.56 s
Accel. time	1.4 s



1. MR rf system: $Q \sim 25$

Fundamental and 2nd harmonic systems are separated.

2. radial feedback: not closed, because it is not necessary.




- stable and reproducible RCS energy and MR dipole field

- frequency pattern is modified offline.

3. phase feedback: closed.

4. Multi-harmonic RF Feed-forward: ON for each of the cavities.

Demonstration of 210kW equivalent operation



Demonstration of 210 kW eq. beam operation

- Extracted beam is 1.14×10^{14} ppp
 ~ 213 kW at 2.56 s cycle
- Measured beam loss is 410 \sim 520 W in the 210 kW operation.

2nd harmonic RF effect on MR beam





FIGURE: Mountain view, bunching factor and bunch shape at MR injection
- 2nd harmonic operation at RCS extraction and 2nd harmonic system at
MR injection work fine.

Block view of the Multi-harmonic RF Feedforward




- without feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t)$$

The commissioning of the feedforward system is performed for each of the cavities. In the figure, #N is the cavity number.

Block view of the Multi-harmonic RF Feedforward



- without feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t)$$


- with feedforward

$$V_{\text{cav}}(h, t) = H_{\text{dr}}^{\text{cav}}(h, t) \cdot V_{\text{dr}}(h, t) + Z'_{\text{cav}}(h, t) \cdot I_{\text{beam}}(h, t) + Z_{\text{FF}}(h, t) \cdot I_{\text{beam}}(h, t),$$

$$Z_{\text{FF}}(h, t) = -Z_{\text{cav}}(h, t).$$

The commissioning of the feedforward system is performed for each of the cavities. In the figure, #N is the cavity number.

Comparisons of voltage monitor waveforms: in the cases of no beam, w/o and w/ feedforward



The beam intensity is 300 kW equivalent—(left) middle of acceleration period and (right) just before extraction. The distortion of the voltage waveform is reduced.

Beam loading compensation by multi-harmonic RF feedforward




FIGURE: Frequency-domain Impedance seen by the beam:
(RCS cavity#1)





FIGURE: Time-domain Impedance seen by the beam:
(RCS cavity#1)


Impedance at RCS extraction is reduced **from 788Ω to 10Ω** .

Beam loading compensation in MR



Mountain Plots of injection beam
(2 bunches)



$d\bar{p}/p$ measured by BPM



Longitudinal oscillation during the acceleration suppressed with FF



Summary

- Transition-free lattice and non AC-line synched timing system allow to realize clean and high quality beam operation, which also owes to the stabilities of the Linac energy and Bending field of both synchrotrons.
- By using the MA loaded RF systems,
 - ✓ more than 20 kV/m of high field gradient
 - ✓ Dual harmonic operation in the RCS
 - ✓ No radial tuning loop and the full digital LLRF offer simple, precise and reproducible longitudinal beam control.
 - ✓ Time-jitter of extracted beam from the RCS is only 1.7 ns. Scheduled extraction is possible to the Fermi chopper at the MLF facility.
- Multi-harmonic RF feedforward system has been developed to compensate a heavy beam loading.
 - ✓ The systems are used for the routine operations at RCS and MR and reproducible and offer an excellent suppression of impedance seen by the beam.