




Design, construction & commissioning of the Linac4 accelerating structures

F. Gerigk, Y. Cuvet, A. Dallocchio, G. Favre, L. Gentini, JM. Geisser, JM. Giguet, E. Kendjebulatov, Ya. Kryuchkov, S. Mathot, M. Naumenko, M. Polini, S. Ramberger, B. Riffaud, C. Rossi, A. Tribendis, P. Ugena-Tirado, R. Wegner, M. Vretenar

Linac I 2, Tel-Aviv, Israel, 9-14 September 2012

Overview

- highlights & status of RFQ, DTL, CCDTL & PIMS,
- lessons learned,
- installation/commissioning planning,




RFQ

(project eng: C. Rossi)

design (CEA/CERN)
and construction
(CERN): 2009 - 2012

Parameter	Value
frequency	352.2 MHz
length	3.06 m
vane voltage	78.27 kV
maximum aperture a	1.8 mm
maximum modulation	2.36
average aperture r_0	3.3 mm
ρ/r_0	0.85

Parameter	Value
min. longitudinal radius	9 mm
max field on pole tip	34 MV/m
Kilpatrick	1.84
focusing parameter	5.7
acceptance at $I=0$ mA	1.7π mm mrad
final synchronous phase	-22 deg



THPB038: C. Rossi et al, "Assembly and RF tuning of the Linac4 RFQ at CERN"

The assembled RFQ is now installed at the 3 MeV Test Stand, where it is undergoing the accelerating field tuning (supported by CEA team). RF commissioning & beam tests before the end of 2012.

DTL

Drift Tube Linac


project eng: S. Ramberger

construction: industry + collaboration (ESS Bilbao)

Parameter	Value
frequency	352.2 MHz
energy range	3 - 50.3 MeV
E_0T	2.65 - 2.95 MV/m
synchronous phase	-30 → -26 deg
ZT^2 (linac def., operational value)	44 - 52 M Ω
Q_0 (measured, av. p. module)	~39000 - 43000
cavity length	3.8 - 7,3 m
number of cavities	3
total number of drift tubes	108
peak power/cavity	1/2/2 MW
Kilpatrick	< 1.6




DTL highlights



- Rigid (5 cm thick) steel tanks assembled from <2 m long segments.
- PMQs in vacuum for streamlined drift tube assembly (SNS technology).
- Adjust & Assemble: Tightly toleranced Al girders w/o adjustment mechanism.
- Design for zero maintenance (no diagnostics/steering/EMQs inside DTs).
- Spring loaded metal gaskets for vacuum sealing and RF contacts.
- Easy-to-use mounting mechanism filed for patent.
- Increased gap spacing in first cells to reduce peak fields and potential breakdowns in PMQ fields.

DTL assembly status



- The first tank segment is copper plated and assembled with girder and drift tubes.
- Drift tube installation takes 10 min/item thanks to metal gaskets and (“automatic”) alignment.
- Vacuum leak tight.
- First tank completed by the end of 2012, testing in 2013.
- Tank 2&3 to be assembled and tested in 2013.

timeline DTL:

2004	start of a collaboration with VNIIEF and ITEP (Russia) for the design and construction of Linac4 DTL tank
2005	decision to use PMQs
2006-7	start of mechanical design at CERN
2008	construction of DTL prototype in collaboration with INFN Legnaro
2009	successful high-power testing of the CERN/INFN prototype
2010	filing of patent on the “mounting mechanism” to position drift tubes
2008-10	purchase of 30 tons of raw material (~3000 pieces of stainless steel cylinders, Cu drift tubes/stems, Al girders, flanges, etc)
2011	start of construction of tanks (industry) and drift tube parts (collaboration with ESS-Bilbao)
2012	start of girder construction in industry
today	assembly of first tank segment at CERN
start 2013	first tank assembled and ready for testing
2013	assembly and tuning of tank 2,3, low-power testing of tank 1,2,3
2013-14	installation in Linac4 tunnel and high-power testing



CCDTL

Cell-Coupled Drift Tube Linac

Parameter	Value
frequency	352.2 MHz
energy range	50.3 - 102.9 MeV
E_0T	3.6 - 2.7 MV/m
synchronous phase	-20 deg
ZT^2 (linac def., operational value)	40 - 33 M Ω
Q_0 (measured, av. p. module)	~41000 - 44000
cavity length	0.7 - 1.04 m
number of modules	7
cavities per module	3
accelerating gaps per cavity	3
total number of drift tubes	42
peak power/cavity	950 - 1000 kW
Kilpatrick	<1.8

design & construction: BINP, VNIITF
project eng: A. Tribendis (BINP)

CCDTL highlights



- **First ever use of a CCDTL in an operational machine!**
- 3 tanks/9 gaps per module
- **Alignment** of quads outside of RF structure (easy access),
- **Alignment** of complete module (3 cavities) on support (beam apertures within ± 0.3 mm) via mechanical means (successfully tested).
- coupling cell dimensions remain constant for all modules,
- 8 technical meetings (5 in Russia, 3 at CERN),
- France - CERN - Moscow - VNIITF (Snezhinsk) - BINP - Moscow - CERN: **13000 km** until the raw steel has been transformed into cavities,

timeline CCDTL:

1994	J. Billen, F. Krawczyk, R. Wood, L. Young: “A new RF structure for Intermediate Velocity particles”
2000	Conceptual CCDTL design for new proton linac at CERN
2001	13-cell cold model in aluminum
2004/5	design/construction of CERN prototype : 2 half tanks + 1 coupling cell
2006	successful high-power testing of CERN prototype
2006	construction of prototype with 2 complete tanks + coupling cell in Russia (BINP/VNIITF) within ISTC contract
2007	successful high-power testing of ISTC prototype at CERN
2009	start of ISTC contracts to construct 7 CCDTL modules for Linac4
Jan. 2010	shipping of 46 tons of raw material (in ~1500 pieces) to Russia
Nov. 2011	successful vacuum and low-power tests of first complete module at BINP
this week	delivery of first 2 modules to CERN
autumn 2012	assembly and high-power tests of first 2 modules
March 2013	delivery of last modules to CERN

PIMS

Pi-Mode Structure


project eng: R. Wegner

construction: collaboration

(NZBJ, FZJ) + assembly at CERN

Parameter	Value
frequency	352.2 MHz
energy range	102.9 - 160 MeV
E_0T	3.74 MV/m
synchronous phase	-20 deg
ZT^2 (linac def., operational value)	24.6 - 26.6 M Ω
Q_0 (operational value)	~20800 - 22700
cavity length	1.3 - 1.54 m
number of cavities	12+1
accelerating gaps per cavity	7
peak power/cavity	920 - 1000 kW
Kilpatrick	1.8

the guts:



PIMS highlights

- same RF frequency (352.2 MHz) as the rest of Linac4,
- 7 cell pi-mode design with strong cell-to-cell coupling ($\sim 5\%$),
- **first-ever use of PIMS in proton linac,**
- coupling slot design optimized for high shunt impedance,
- high power tested 60% above nominal peak fields!
- assembly of discs and rings via EBW to avoid loss of material rigidity during brazing,



timeline PIMS:

1977	5-cell pi-mode structure used in PEP storage ring (electrons) at SLAC (353.2 MHz)
1989	5-cell pi-mode structure used in LEP (electrons) at CERN (352.2 MHz)
2007	Decision to use PIMS to replace the Side-Coupled Linac (704 MHz) between 100 - 160 MeV in Linac4 for low-β proton acceleration
2007	tendering for 3D forged OFE copper for PIMS construction
2007/8	construction and measurements on scaled aluminum cold model
2008	order of 26 t of 3D forged OFE copper (last piece delivered: Nov 2011)
2009/10	design and construction of full size PIMS prototype at CERN
2010	successful high-power testing at CERN and decision to use prototype as first PIMS cavity in Linac4
Nov. 2010	collaboration with NCBJ (National Centre for Nucl. Research, Poland , formerly Soltan Inst.) and FZJ (Forschungszentrum Jülich, Germany) for the construction of 12 PIMS cavities.
Jan. 2011	first shipment of altogether 31 tons of raw material (~1500 pieces) to Poland
Aug. 2012	most machining and welding operations are qualified, ~half of the discs and rings are rough-machined
autumn 2012	delivery of first series cavity to CERN , assembly (EBW), tuning and subsequent high-power testing at CERN,
March 2014	delivery of last PIMS cavity to CERN

lessons learned I

- **Cu-plating:** use of *stainless enables stripping and re-plating with Cu*. When using soft steel all stripped surfaces have to be re-machined (happened with a prototype..). SS has good enough thermal conductivity for 10% duty cycle and could be procured at reasonable cost.
- **Tolerances:** tight tolerances (e.g. for the DTL “adjust and assemble” principle, CCDTL alignment, PIMS assembly) are possible but need i) more effort when selecting companies, ii) often result in long machining times (~80 hours of milling per PIMS disc) → *spending some extra months on the mechanical design to reduce tolerances may save a lot of time later on!*
- **C-shaped metal gaskets:** extensively used in DTL and CCDTL, handling and surface preparation needs a certain learning curve, 6-12 months to qualify a company, several months for delivery, need to order enough spares until you have “learned” to make leak-tight connections. → *vacuum gasket and RF contact in one piece, no organic material in vacuum, no degradation over time, easy dis- and re-assembly,*

lessons learned II

- **Raw materials:** generally all procured & delivered by CERN (eases quality control), 3D forged steel (found only one small void in a critical location) during the construction, 3D forged copper gives excellent EBW results, less problems with deformation during machining, and a guaranteed high yield strength ($R_{p0.2} > 200$ MPa)
 - ➔ *so far no major difficulties related to material quality,*
 - ➔ *It took ~3.5 years to get the last pieces of forged copper, price for PIMS is comparable to the machining cost.*
- **Shipping to/from Russia:** shipping and customs procedures went smoothly due to combined efforts of ISTC, BINP, and CERN.

lessons learned III

- **Project set-up:** beneficial to have *one (competent) partner* (e.g. BINP as CCDDL project leader in Russia) to take care of final design and *complete construction*: i) no problems with interfaces, ii) quality control handled internally, iii) you only qualify general construction procedures (brazing, welding, Cu-plating, surface quality,..) and the final results (vacuum, alignment, RF)
- **Prototyping:** *plan for 2 prototypes!* One in-house to understand and improve your mechanical concept and machining processes. A second with your partner who will do the series production. Alternative: *do your prototyping together with your industrial partner* (forbidden by CERN tendering rules).

2012 2013 2014 2015 2016 2017 2018

RFQ, DTL, CCDTL:
assembly, tuning, testing

PIMS: assembly, tuning,
testing

DTL: installation &
commissioning

ready for 50 MeV
protons (Linac2 back-up)

CCDTL: commissioning

PIMS: commissioning


160 MeV beam tests













reliability run (on dump)

foreseen connection to
PSB

present
planning

Linac4 in Geneva



BINP, Novosibirsk		CCDTL: design & construction
CEA, Saclay		RFQ: mech. design & measurements
ESS, Bilbao		DTL, jacks, RF coupler: production of DTL drift tubes, support for market survey of Spanish industry,
FZJ, Jülich		PIMS: port weldings (EBW)
INFN, Legnaro		DTL: collaboration on prototype construction, movable tuners: construction
ISTC, Moscow		CCDTL: contract framework with BINP/VNIITF, financing, customs procedures in Russia
KACST, Riyadh		DTL: construction of cold model
NCBJ, Swierk		PIMS: machining of all pieces
RRCAT, Indore		RF coupler: prototyping & construction
VNIITF, Snezhinsk		CCDTL: design & construction
VNIIEF, Sarov		DTL: preliminary mechanical design
ITEP, Moscow		DTL: preliminary designs

BINP, Novosibirsk		CCDTL: design & construction
CEA, Saclay		RFQ: mech. design & measurements
ESS, Bilbao		DTL, jacks, RF coupler: production of DTL drift tubes, support for market survey of Spanish industry,
FZJ, Jülich		
INFN, LNF		
ISTC, Moscow		
KACST, Beirut		
NCBJ, Szopienice		
RRCAT, Kolkata		
VNIITF, Snezhinsk		CCDTL: design & construction
VNIIEF, Sarov		DTL: preliminary mechanical design
ITEP, Moscow		DTL: preliminary designs

Many thanks to the collaborating institutes, our industrial partners and to all the international colleagues, students, fellows, etc who helped and supported us!