

Spallation Neutron Source RF Systems

Tom Hardek

Mark Crofford


Mark Middendorf

Maurice Piller

Yoon Kang

Sung-Woo Lee

Alexandre Vassioutchenko




Outline

- **SNS RF Systems Review**
- **Overview of Performance**
- **RF Related Issues addressed over the past several Years**
- **A Look into the Future**

Layout of Linac RF Modules


 402.5 MHz, 2.5 MW klystron	7 Transmitter	3 Modulators
 805 MHz, 5 MW klystron	4 Transmitter	4 Modulators
 805 MHz, 0.55 MW klystron	14 Transmitter	8 Modulators



Accumulator Ring

- **Ring RF**


- **4 Bunching Cavity/Amplifier stations**
 - Ferrite loaded (Phillips 4M2)
 - Cavity Bias provides dynamic tuning
 - Beam pipe and outer housing used for bias.
- **2 bunching gaps per cavity**
- **3 Buncher Cavities operate at the revolution frequency 1.05 MHz**
 - Maintain a gap to allow the extraction kickers adequate time to reach full field.
- **1 Cavity operates at the 2nd harmonic 2.1 MHz**
 - Reduce the peak beam current to minimize the possibility of exciting instabilities.
- **All cavities and amplifiers are the same.**
 - Resonating capacity reduced for the 2nd harmonic cavity allowing use of the same structure.



Performance Overview

- **RF Systems/Structures running very well**
 - Los Alamos deserves much credit for delivering a reliable RF system and warm Linac
 - JLab deserves much credit for delivering an excellent Superconducting Linac
 - Berkley deserves credit for the RFQ, Ion Source and front end systems
 - Brookhaven deserves credit for delivering a reliable hands-off Ring RF system
- **Delivering production neutrons since April 2006**
- **Reached 1 MW on September 18, 2009**
- **Operating at greater than 85% reliability (88% goal this year)**
- **Run at over 90% reliability for extended periods**

Overall Operating Parameters




Extended Operation at 1 MW

Energy and Power on Target

1022.6 kW on Target


Beam to Target



Improvements to the RF Systems


Ion Source & RFQ

- Developed HV Isolation Transformer
 - Allows 2 MHz Amplifier to operate at ground potential
 - Plan to replace the present gridded tube amplifiers with 120 kW solid state units operating at ground potential.
 - Have 2 each 120 kW Solid State amplifiers in hand



- Replaced original RFQ Drive Couplers
 - Original couplers were hard to balance leaving the power split unequal
 - With the unequal power split there was concern that a coupler could be damaged.
 - Used similar design as SCL Couplers
 - Replaced 8, 100kW couplers with 2, 600 kW couplers
 - RFQ runs at about 700 kW

Medium Energy Beam Transport (MEBT)



- **Original Amplifiers were cavity tuned gridded-tube amplifiers**
 - Difficult to tune and not reliable
 - Replaced with Solid State
 - 402.5 MHz
 - 25 kW
 - 1.2 msec pulse length
 - 4 operational amplifiers + 1 spare
 - Spare can be remotely switched to any cavity

- **4 Rebuncher Cavities**
 - 20 kW each
- **Includes**
 - MEBT Chopper
 - Quadrupole magnets
 - Scraper
 - Beam Stop



Extra Converter Modulator

- **Added Extra Modulator**
 - Original design called for 11 or 12 klystrons/modulator
 - Actual modulators could only run at 69 kV due to an output current limit
 - Klystrons designed to run at 75 kV
 - Extra modulator allows 10 klystrons/modulator and allows operation at 75 kV



Low Level RF

- **Developed 8 channel power meter**
 - Will allow monitoring more coupler ports
 - Useful to record klystron perveance
 - Used to monitor the individual amplifier units of the new MEBT amplifiers
- **Added Picoampere-meters**
 - Original cold cathode vacuum gauges have trouble staying alive
 - We use an electron probe as an additional interlock
- **Have an updated Field Control Module (FCM) Design**
 - Observed beam loss associated with small phase shifts in FCM
 - Traced loss to klystron gallery temperature changes
 - Removed Analog Front End section and moved it to temperature compensated down-converter chassis.
 - Gained factor of 10 in temperature stability
- **Added a workable Quench detection feature to the software.**
- **Replaced irradiated sections of arc detector glass optical fiber with easily replaceable plastic optical fiber jumpers**
- **Implemented a fiber test system**
- **Added slow pulse width and chiller temperature feedback loops to RFQ control page**

A Look Into the Future

- **Power Upgrade (PUP)**
 - Add 36 more SCL Cavities, Klystrons and LLRF Systems
- **Intensity upgrade**
 - Requires more RF Power
 - Will replace some klystrons and upgrade HVCMs
 - Will need to Process some of our SCL Cryo-modules for higher accelerating field in cavities
- **Second Target Station (Currently on-hold)**
- **Existing LLRF modules have obsolete components**
 - Need to be working on next generation system
- **Ring LLRF**
 - Want to replace existing hardware and software with a version more compatible with our Linac systems

Summary

- **SNS reached 1 MW in mid September as promised to DOE**
- **Presently operate with better than 85% reliability**
 - Ultimate goal is 95%
 - We have identified major sources of downtime and are addressing them
- **Ion Source amplifier operating at ground potential.**
- **MEBT RF Upgrade is operational with only minor cleanup work remaining.**
- **SCL RF Power limitation was resolved by adding an extra converter-modulator (running with 10 klystrons per modulator)**
- **We are beginning to acquire Klystron Perveance Data**
 - Analyzing archive data