

**LARP**

**BNL - FNAL - LBNL - SLAC**

# Development of Long Nb<sub>3</sub>Sn Magnets by the LARP Collaboration

**GianLuca Sabbi**

for the US LHC Accelerator Research Program



*2011 Particle Accelerator Conference  
New York, March 30, 2011*

# US LHC Accelerator Research Program

---

## Goal: Extend and improve the performance of LHC


- Progression from the US LHC Accelerator Construction Project
- Collaboration of four national Labs: BNL, FNAL, LBNL, SLAC

## Major focus: Develop Nb<sub>3</sub>Sn quadrupoles for HL-LHC

- Potential to operate at higher field and/or larger temperature margin
- Follows Nb<sub>3</sub>Sn development and demonstration by CDP & US Labs

## Technical challenges: Nb<sub>3</sub>Sn is brittle and strain sensitive


- Requires high temperature coil reaction after winding
  - Materials compatibility (coil parts, insulation)
  - Thermal expansion differentials (more critical for long magnets)
- Large forces are generated in high field magnet coils
  - Need to prevent degradation under stress



LARP

# Overview of LARP Activities

## *Accelerator Systems*




## Instrumentation

- Luminosity monitor
- Tune tracker, AC dipole
- Schottky monitor
- Electron cloud instability
- Beam-beam studies
- Crab crossing
- Rotatable collimators

## Accelerator Physics

## Collimation

## *Magnet Systems*



## Materials

## Model Quadrupoles


## Long Quadrupoles

- Strand characterization
- Cable development
- Technology Quadrupoles
- High-field Quadrupoles
- Coil fabrication
- Structure and assembly
- Instrumentation and Test

## *Program Management*

## Programmatic Activities

- Toohig Fellowship
- Long Term Visitors




# LARP Presentations at PAC11

**LARP**

---

- Design and Test of Long Nb<sub>3</sub>Sn Magnets within the LARP Collaboration
- Field Quality Measurements of LARP HQ Magnets (TUP174)
- Mechanical Design of an Alternate Structure for LARP Nb<sub>3</sub>Sn Magnets for LHC (TUP170)
- Tevatron Accelerator Physics and Operation Highlights
- Beam Losses Due To Abrupt Crab Cavity Failures In HL-LHC
- Studies of RF Noise Induced Bunch Lengthening at the LHC
- Operational Results from the LHC Luminosity Monitors
- LARP LHC 4.8 GHz Schottky System Initial Commissioning with Beam
- Results of Head-on Beam-beam Compensation Studies at the Tevatron
- Advanced Crystal Collimation Studies at the Tevatron (T-980)
- Impact of Arc Phase Advance Tuning on Chromatic Optics in RHIC
- Estimation of Ecloud and TMCI Driven Vertical Instability Dynamics from SPS MD Measurements
- Crab Cavity Simulation in SPS
- Multipacting Analysis for the Half-Wave Spoke Resonator Crab cavity for the LHC Upgrade
- Simulations of the LHC High Luminosity Monitors at Energies from 3.5 TeV to 7.0 TeV
- Simulation of Jitter Effects in Crab Cavity Compensation for LHC Upgrade
- Simulated Performance of an FIR-Based Feedback System to Control the Electron Cloud Single-Bunch Transverse Instabilities in the CERN SPS
- Experimental Study of Magnetically Confined Hollow Electron Beams in the Tevatron as Collimators for Intense High-Energy Hadron Beams
- Direct Numerical Modeling of E-cloud Driven Instability of a Bunch Train in the CERN SPS, and its Mitigation using a Feedback Model



LARP

---

# High Luminosity LHC

## Physics goals:


- *Improve measurements of new phenomena seen at the LHC*
- *Detect/search low rate phenomena inaccessible at nominal LHC*
- *Increase mass range for limits/discovery*

## Timeline and decision points:

- *~2014: complete design study and select technology*
- *~2020: installation (driven by lifetime of existing IR,  $\sim 500 \text{ fb}^{-1}$ )*

## Required accelerator upgrades include IR magnets:

- *Support new optics solutions that directly increase luminosity*
- *Provide design options for overall system optimization/integration*
- *Tolerate high peak ( $10^{35} \text{ cm}^{-2}\text{s}^{-1}$ ) & integrated ( $3000 \text{ fb}^{-1}$ ) luminosity*  
⇒ *Thermal margins, radiation lifetime*



LARP

# Magnet Program Components

## 1. Materials R&D:

- *Strand specification and procurement* Ongoing
- *Cable fabrication, insulation and qualification*
- *Heat treatment optimization*

## 2. Technology development with Racetrack Coils:


- *Subscale Dipole & Quad (SM & SQ, 30 cm long)* Completed
- **Long Racetrack (LR, 4 m long)**

## 3. Cos 2θ Quadrupoles with 90 mm aperture:

- *Technology Quadrupole (TQ, 1 m long)* Completed
- **Long Quadrupole (LQ, 4 m long)** ~75%

## 4. Cos 2θ Quadrupoles with 120 mm aperture:

- *High-Field Quadrupole (HQ, 1 m long)* ~35%
- **Long High-Field Quadrupole (LHQ, 4 m long)** Starting



LARP

---


# Present focus: LQ and HQ

## Long Quadrupole LQ (*90 mm aperture, 4 m long*):

- *LQS01: achieved 220 T/m, 10% above initial LQ target*
- *LQS02: assembly is completed with 4 new coils*
- *LQS03: four coils under fabrication with new conductor design*

## High Field Quadrupole HQ (*120 mm aperture, 1 m long*):

- Achieved  $>155$  T/m gradient in first test, at 4.5K
  - *Already above NbTi intrinsic limit at 1.9K*
- First quench  $>150$  T/m in second test
- Observed coil failures due to insulation & conductor damage
  - *Traced to high compression during coil fabrication*
- New & more challenging design - requires optimization




LARP

# LARP Conductors


Three strand designs, all from Oxford Superconducting Technology:

- *MJR 54/61:* *TQS01, TQC01, SQ*
- *RRP 54/61:* *LR, TQ02, LQS01(2), HQ01a/b/c/d*
- *RRP 108/127:* *TQS03, HQ01a/b/c/d, (LQS03)*



## *RRP 54/61:*

- ☺ Production wire, highest  $J_c$ , long piece length, best characterized
- ☹ Large sub-elements, flux jumps esp. in larger diameter wires





## *RRP 108/127:*

- ☺  $D_{eff}$  reduced by 30%, very good results in TQS03
- ☹ Lower  $J_c$  for same RRR, not fully optimized for production

*New options from the HEP Conductor Development Program:*

- Ti-doped RRP: HQ cable/coil fabricated for evaluation
- RRP 217: promising but still requiring R&D






LARP

# Length Scale-up Projects in LARP

SM

⇒

LR





- From 0.3 m to 4 m
- Started in 2005, completed in 2008
- Racetrack coils, shell based structure

TQS

⇒

LQS




- From 1 m to 4 m
- Started in 2007, exp. completion 2012
- 90 mm aperture  $\cos 2\theta$  coils
- Structure alignment


HQ

⇒

LHQ





- From 1 m to 4 m
- Starting in 2011, exp. completion 2016
- 120 mm aperture  $\cos 2\theta$  coils
- Full coil and structure alignment




LARP

# Long Racetrack (LR)

- Scale up LBNL SM coil and structure: 30 cm to 4 m
- Coil R&D: Cable, handling, reaction, impregnation
- Structure R&D: friction effects, magnet assembly
- *BNL: coil fabrication, magnet assembly and test*
- *LBNL: magnet design, structure fabrication/assembly*
- Fast training: LRS01 first quench at 84% of SSL
- LRS02 achieved 11.5 T, **96% of short sample limit**








LARP

# Technology Quadrupole (TQ)

- Double-layer, shell-type coil
- 90 mm aperture, 1 m length
- Two support structures:
  - *TQS (shell based)*
  - *TQC (collar based)*
- Target gradient **200 T/m**




## Winding & curing (FNAL - all coils)




## Reaction & potting (LBNL - all coils)






LARP

# TQ Studies: Stress Limits




Calculated peak stresses in TQS03c



## Systematic investigation in TQS03:

- TQS03a: 120 MPa at pole, 93% SSL
- TQS03b: 160 MPa at pole, 91% SSL
- TQS03c: 200 MPa at pole, 88% SSL

Peak stresses are considerably higher →  
**Considerably widens design window**






LARP

# TQS03d Cycling Test



- Reduced coil stress to TQS03b levels (160 MPa average)  
➤ *Pre-loading operation and test performed at CERN*
- Did not recover TQS03b quench current (permanent degradation)
- Performed 1000 cycles with control quenches every ~150 cycles
- No change in mechanical parameters or quench levels








LARP

# Long Quadrupole (LQ)


- TQ length scale-up from 1 m to 4 m
- Coil Fabrication: FNAL+BNL+LBNL
- Mechanical structure and assembly: LBNL
- Test: FNAL
- Target gradient 200 T/m






LARP

# LQS01 & LQS01b Quench Performance






LARP

# Next Steps in the LQ Program

*LQ surpassed its initial target by 10%. Current R&D goals are:*



- Fully reproduce the performance of the TQ short models
  - *Higher gradient (240 T/m in TQS03)*
  - *Fast training (plateau in 5-10 quenches, no retraining)*
- Systematic analysis of coil length effects
  - *Detailed modeling of the reaction process*
  - *Understand/optimize coil strain state after reaction*
- Design and process optimization for construction
  - *Coil size control/reproducibility*
  - *Protection heater design, esp. for inner layer*
  - *One-side loading with 4 m keys/bladders*
  - *Cable insulation techniques for production*




LARP

# High-Field Quadrupole (HQ)

- 120 mm aperture, coil peak field of 15.1 T at 219 T/m (1.9K SSL)
- 190 MPa coil stress at SSL (*150 MPa if preloaded for 180 T/m*)
- Stress minimization is primary goal at all design steps (from x-section)
- Coil and yoke designed for small geometric and saturation harmonics
- Full alignment during coil fabrication, magnet assembly and powering





LARP



# HQ: a fully integrated program

- |  |            |
|--|------------|
| • Cable design and fabrication           | BNL        |
| • Magnetic design & analysis             | FNAL, BNL  |
| • Mechanical design & analysis           | BNL        |
| • Coil parts design and procurement      | FNAL       |
| • Instrumentation & quench protection    | BNL        |
| • Winding and curing tooling design      | BNL, FNAL  |
| • Reaction and potting tooling design    | BNL        |
| • Coil winding and curing                | BNL        |
| • Coil reaction and potting              | BNL, BNL   |
| • Coil handling and shipping tooling     | BNL        |
| • Structures (baseline, revised, mirror) | BNL, FNAL  |
| • Assembly (baseline, revised, mirror)   | BNL, FNAL  |
| • Magnet test                            | CERN, FNAL |
| • Accelerator Integration                | BNL, FNAL  |

# Handling High Stress in Magnet Coils



## 1. Understand limits

**TQ** (90 mm, ~12 T)






## 2. Optimize structure and coil for minimum stress

**LQ** (90 mm, ~12 T)



**HQ** (120 mm, ~15 T)








LARP

# HQ Coil Design and Fabrication




- HQ design assumed less space for inter-turn insulation than TQ/LQ
- Based on measurements, but limits expansion during reaction
- As a result, coils are over sized and over compressed






LARP

# Magnet and Coil Electrical QA







LARP

# Next Steps in the HQ Program

- HQ01d cool-down is underway
  - Replaced HQ01c limiting coil, one more coil available





- Two special coils were fabricated with lower compression
  - #12: increased cavity size; #13: one less turn
  - Will be tested in mirror configuration
- Substantial cable R&D is underway for the next series of coils
  - Adjust cable size to preserve x-section, parts, tooling



# Long HQ Development Plan for 2011-2013

LARP






LARP


# Accelerator Quality in LARP Models

Design Features	LR	SQ	TQS/LQS	TQC/LQC	HQ	LHQ
Geometric field quality					✓	✓
Structure alignment		✓	✓	✓	✓	✓
Coil alignment		✓			✓	✓
Saturation effects				✓	✓	✓
Persistent/eddy currents						✓
End field margin			✓		✓	✓
Cooling channels				✓	✓	✓
Helium containment				✓		✓
Radiation hardness						✓

# Accelerator Integration

- Pre-load optimization for high gradient with **minimal training**
- Alignment, quench protection, radiation hardness, cooling system
- Field quality: cross-section iteration; cored cable for eddy current control
- Structure and assembly features for magnet production and installation





LARP

---

# Summary

- A large knowledge base is available after 5 years of fully integrated effort involving three US Labs and CERN
- Demonstrated all fundamental aspects of Nb<sub>3</sub>Sn technology:
  - *Steady progress in understanding and addressing R&D issues*
- R&D effort should now focus on increased reliability, accelerator integration and production-oriented processes
- HL-LHC is a key step for all future high-field applications
- Next few years will be critical and much work is still left to do
  - Integrate effort with CERN, EuCARD, KEK, US core programs

## Acknowledgement



Office of  
Science

