

Thomas Jefferson National Accelerator Facility

UPGRADE AND HIGH CURRENT CAVITY DEVELOPMENTS

Joseph Preble

for the Jefferson Lab


Institute of SRF Science and Technology

And Mechanical Engineering Group

Outline

- Jefferson Lab CEBAF Upgrade
 - Cryomodule/Cavity Requirements
 - Cavity Solution
 - **Cavity Performance**
 - **HOM Issues**
 - **Future Activities**
- Jefferson Lab High Current Program
 - Background
 - **Cryomodule Concept**
 - **Cavity and Critical Component Status**
 - **Future Activities**

12 GeV CEBAF




Requirements Overview

- Add 1 GV, 0.5 GV per Linac
- 1497 MHz CW
- 10 Cryomodules (CM), 100 MV each
- CM has 5.6 m active length, 8ea 7 cell cavities
- Eacc ~ 19 MV/m includes operational overhead
- 400 μ A injected current (up to 6 passes)


Parameter List

Cryomodule	
Total active length	5.6 m
Voltage	108 MV
2 K heat load	≤ 300 W
50 K heat load	≤ 300 W
Cryomodule length	~ 8.5 m


Cavity	
Frequency	1497 MHz
Cavity active length	0.7 m
Geometry Factor	280 Ω
Ep/Eacc	2.17
Hp/Eacc	3.74 mT/(MV/m)
Gradient	19.2 MV/m
Qext Fundamental Power Coupler (FPC)	$3.2 * 10^7$
FPC power rating	13 kW
Dipole mode damping	$< 1 * 10^{10}$ Ω/m



Cavity Performance Upgrade Baseline Plan




- C100 Cavities with standard BCP processing meet project requirements




Cavity Performance with electro-polishing processing

- Aggressive BCP polishing had degraded E_{acc} and Q_0 performance
- EP processing recovers and improves performance



Cavity Performance with electro-polishing, promising results


- Light EP processing improves E_{acc} and Q_0 performance after normal BCP processing



HOMs

- Requirement for injected beam current was increased, 100 \rightarrow 400 μ A
- Dipole mode damping $< 1 * 10^{10} \Omega/\text{m}$
- All requirements are met by existing design but
- Concern over cavity performance prompted extensive simulations and measurements
- End effects (including cavity to cavity) are critical for coupling at the beamline HOM couplers
- FPC coupling and HOM damping in the warm waveguide network is required

C100 cavity dipole impedance



Order of magnitude margin for more stringent requirements

Dipole shunt impedances for C100-1 and C100-2 respectively as derived from measured Q1 values.

C100 Cavity Future

- Continue to investigate EP as an alternative to BCP (possibly a combination of both, BCP with a final EP)
- We will make a few, ~ 8 , more C100 cavities in house
- Production order for 86 cavities has been placed
- Start receiving cavities next spring
- Finalize production processes and documentation before the cavities start to arrive

High Current Program



High Current Program


- JLAB has been in the business of FELs and ERLs for a long time using CW SRF linacs
- Existing Jefferson Lab designs are ok for ~ 10 mA and are in routine use at the existing JLAB FEL
- Beam current requirements have gone from ~ 1 mA to ~ 10 mA to ~ 100 mA and talk of ~ 1 A
- Design and fabrication of 1 Amp and 100 mA cavities, 748.5 and 1497 MHz respectively, are complete (748.5 scaled to 1497 MHz)
- Conceptual designs for 1 A and 100 mA cryomodule is complete and design work continues on the 100 mA cryomodule

High Current Application, 1 Example

High-average power ERL's face many challenges on the “current” frontier. Some similar to storage ring e+e- colliders, e.g. HOM damping, RF power.

Typical “industrial-strength” FEL:

- ~100MeV beam energy,
- ~100kW+ optical power
- ~100mA+ beam current
- Compact layout (e.g. Dave Douglas)
- High real-estate gradient
- CW
- Low cryogenic load
 - Low wall losses
 - Warm HOM loads




1 Amp Cryomodule


- Requirements
 - Voltage 100-120 MV
 - Length $\sim 10\text{m}$
 - Frequency 750 MHz
 - Beam Aperture $>3''$ (76.2mm)
 - BBU Threshold $>1\text{A}$
 - HOM Q's $<10^4$
 - Beam power 0-1MW
- Other concerns:
 - Low cryogenic losses
 - Maintainability, flexibility, cost.

1 Amp Cryomodule Concept


6 each, 5 cell cavities



1 Amp Cryomodule Concept



6 cavity string



Spaceframe / Thermal Shield Assembly

1 Amp CM Cryogenic Heat Load

- Dynamic Heat Load @ 2K ~ 400 W
 - **Cavity Dissipation = 55 W per cavity**
 - $E_{acc} = 16.7 \text{ MV/m}$, $Q_0 = 8E9$, $R/Q = 636$
 - **HOM Dissipation ~ 8 W per cavity**
 - 4 kW Power, 1.5 GHz
- Dynamic Heat Load @ 50 K ~ 190 W
 - Due to heat-stationed HOM waveguides
 - FPC waveguides are gas-cooled
 - 200 kW operation requires 4x SNS-flow per coupler
 - 0.15 g/sec/coupler
- **Totals with Static Heat Load**

2K ~455 W

50K ~550 W

High Current Cavities

- Design considerations
 - Keep trapped modes away from beam resonances avoiding extremely large HOM power
 - Good HOM damping
 - Avoid multipacting barriers




1497 MHz 5 cell HC
(100 mA) cavity



Prototype 1497 MHz cavity with endgroups

Cavity design

- Cell shape
 - Comparison with other SRF projects
 - JLAB uses a single geometry for center and end cells, end cells trimmed differently



- Multipacting simulation using FishPact




Final JLab High Current cavity cell shape design

Cavity Performance

- Extensive bench testing of Copper and Niobium single cell and multi cell cavities




Bead-pull HOM measurement setup





Cavity Performance

- 1497 MHz Vertical Test Data



Components


- HOM Waveguide Coupler
- Combination HOM/FPC Waveguide Coupler





Components

- HOM Load, 4 kW
- RF planar window, M. Stirbet THPPO056


Lossy ceramic tiles



Water cooling channel




Temperature distribution



High power load design and simulation results

100 mA Cryomodule Design

- Use existing 1497 MHz cavities
- Use existing horizontal test bed cryostat
- Complete designs of “critical” components, FPC, HOM couplers and loads, RF window



Conceptual design of a cavity-pair cryomodule

100 mA Cryomodule Plans

- Complete design, fabrication, and assembly
- Tests in FY10
 - Acceptance testing in the Cryomodule Test Facility
 - Beam tests in the FEL

High Current Program

- Actively prototyping and testing critical components
 - Cavities
 - RF couplers, FPC and HOM
 - RF windows
 - HOM loads
- Cryomodule designs going forward existing components as much as possible
- Beam test in FY10

Summary

- 12 GeV Upgrade cavity work is in good shape and the order for 86 cavities has been placed
- Work continues on improving processes for best cavity performance
- High current program at Jefferson Lab is alive and well
- Design, prototype, and testing of components is ongoing
- Design work for a beam test cryomodule has started
- Beam test is planned for FY10