

# Status of the Spiral 2 project at GANIL

T. Junquera

IPNO Orsay (CNRS) and GANIL

SRF09, Berlin, September 21<sup>st</sup>, 2009


# What is Spiral 2 ?

- In 2001 A new Radioactive Ion Beam facility (Spiral) start to operate at GANIL (ISOL principle, using the former cyclotrons as a Driver, and a new cyclotron for post-acceleration)
- In 2005: decision by the french Ministry of Research to construct a new facility: Spiral 2. Financial support is given by CEA, CNRS and Normandy Regional Council.

Based on a SC Linac Driver, associated to a High Power Production System (converter, target, ion source) delivering RI beams to cyclotrons for post acceleration and using new and existing experimental areas.

**2009 : we are in the middle of the road ...**


# ISOL (Isotope Separation On Line) technique to produce Rare Isotope Beams




Spiral 2 Goals
UCx target: $10^{14}$ fissions/s
RIB ( $60 < A < 140$ ): $10^6$ to $10^{10}$ pps



- ⇒ light-ion stable beams
- ⇒ heavy-ion stable beams
- ⇒ RIB induced reactions




## Spiral 2 construction phases




+ Annexes = Conventional facilities for PH 1 & 2



# Reference planning (September 2007)



## SPIRAL2 DRIVER ACCELERATOR Baseline Configuration: October 2006



beam	p+	D+	ions	ions
Q/A	1	1/2	1/3	1/6
I (mA) max.	5	5	1	1
$W_0$ min. (Mev/A)	2	2	2	2
$W_0$ max. (Mev/A)	33	20	14.5	8.5
CW max. beam power (KW)	165	200	44	48

Total length: 65 m (without HE lines)

D<sup>+</sup>: ECR ion source

Heavy Ions: ECR Ion Source

Slow and Fast Chopper

RFQ (1/1, 1/2, 1/3) & 3 re-bunchers

12 QWR beta 0.07 (12 cryomodules)

14 QWR beta 0.12 (7 cryomodules)

1 KW Helium Liquifier (4.2 K)

Room Temperature Q-poles


30 Solid State RF amplifiers (10 & 20 KW)

# Injector construction

Grenoble, Saclay, GANIL, Lyon,  
Strasbourg

RFQ design & follow-up  
by CEA Saclay


- first module: end 2009
- final assembly and test at GANIL (2011)



RFQ ( $q/A=1/3$ )

Re-Bunchers

- $q/A=1/3$  ion source and LEBT installed and tested at Grenoble (2009-2011)



ECR Ion Source  
 $D^+, p$




ECR Ion Source  
(Heavy Ions)

- $q/A=1, 1/2$  ion source and LEBT installed and tested at Saclay (2009-2011)

# SC Linac construction

Orsay, Saclay, GANIL, Grenoble




Each cryomodule is installed on independent supports with alignment adjustments


Room temperature sections : Q-poles

**reducing beam losses ( $< 1W/m$ )**

- ⇒ **space for corrections and diagnostics**
- ⇒ **room temperature Q-poles**
- ⇒ **special supports for precise alignment**



Beam Position Monitor



Steerers coils

Chamber adjustments



Alignment

Support adjustments

# SC Linac construction

Orsay, Saclay, GANIL, Grenoble

## Low energy cryomodules (beta 0.07): CEA Saclay



### First cryogenic tests (july-december 2008)

- Cryomodule static losses 4K : 7 W
- Valve box + cryo. lines + cryomodule: 25 W
- tests with power coupler: November, December 2008
- pre-series cavities: reception and test July 2009 (OK)

(QWR fabrication: Zanon and SDMS)



⇒ More details in  
G. Olry presentation  
Thursday 24th.

# SC Linac construction


Orsay, Saclay, GANIL, Grenoble

High energy cryomodules (beta 0.12): CNRS/ IPN Orsay

- QWR fabrication by RI
- cryostats by SDMS



$\beta=0.12$	
$\frac{E_{peak}}{E_{acc}}$	5.5
$\frac{B_{peak}}{E_{acc}}$	10.1 mT/(MV/m)
$\frac{R_s}{Q}$	521 $\Omega$
$Q_0 \times 10^9$	1.7



## First cryomodule test January - February 2008

- 8 MV/m with RF Power Coupler
- static losses at 4K: 13 W
- total losses (including cryo lines and valve box) : 25 W
- tuner, alignment, contamination tests (OK)

⇒ More details in G. Olry presentation Thursday 24th.



# SC Linac construction

Orsay, Saclay, GANIL, Grenoble

## RF Power Couplers



developed at CNRS Grenoble

- test station 40 KW, clean room
- prototypes: fully tested at 40 KW CW
- nominal operation between 5 and 15 KW
- Contract for series production (30 units) in September 2008
- first prototypes couplers tested on A and B cryomodules : 2008
- first series couplers assembled and tested on cryomodules: end 2009



# SC Linac construction


(gallery)



New QWR tuner



Delivery of QWR (RI manufacturing)  
waiting for assembly and test (Orsay)



Assembly of power coupler (Saclay)




Delivery of  
power couplers  
waiting for test  
(Grenoble)

# SC Linac construction

## Cryogenic Plant

		Load	
		4.3 K	60K
Linac		643 W	1500 W
LHE	Beam line	80 W	300 W
Total		723 W	1800 W
Liquefier request		1000 W	2400 W
Others	Ganil	10 l/h	

↗ 1200 W




### Call for Tenders

- two companies: on going technical discussions
- contract signature: November 09
- installation 3rd Qr. 2011

### Cryogenic distribution

- independent valves boxes
- special box to connect the cryoplant
- pressure stability  $\pm 5$  mbar



# SC Linac construction

Orsay, Saclay, GANIL, Grenoble


## RF Systems developed by GANIL, Saclay, Orsay

### Solid State / modular RF Amplifiers




### RF Amplifiers Test Stand

- Digital Low Level RF system
- RFQ amplifiers: 4 x 50 KW vac. tubes prototype tested in may 2009
- Solid State amplifiers: prototypes tested end 2007 and 2008.
- Contracts for series: end 2009
- Master oscillator, clocks, reference pulses: developed by LAL Orsay



## Spiral 2 safety goals

• *calculations (with correction schemes) :  $< 10 \text{ mW/m}$*



• *reasonable goal :  $< 1 \text{ W/m}$*

### Activation and dose calculations

- *MCNPX 2.5 code*
- *modelling of all components*
- *maintenance schemes*

### Doses rates

	<i>Technical Staff</i>	<i>People/Environment</i>
<i>Normal operation</i>	$< 2 \text{ mSv/year}$	$< 10 \text{ }\mu\text{Sv/year}$
<i>Incidental situation</i>	$< 10 \text{ mSv/year}$	$< 10 \text{ }\mu\text{Sv/incident}$
<i>Major incident</i>	$< 20 \text{ mSv/incident}$	$< 100 \text{ }\mu\text{Sv/incident}$
<i>Major accident</i>	<i>Variable according to situation and potential impact</i>	$< 1 \text{ mSv/accident}$


- offices, labs and workshops limit  $7.5 \text{ }\mu\text{Sv/h}$ ,
- maintenance operations limit  $100 \text{ }\mu\text{Sv/h}$

### Licensing procedure:


First Safety Report was presented in April 2009

# Phase One Construction


Underground level: - 9.50 m



## Phase 1 : Buildings Cross section views



**Filling up layer (most probably using the calcareous stone extracted during the excavation)**



## Phase 1 Ground level Buildings



**Goals:** in two years from now (at the next SRF conference)

- SC Linac installation in progress
- First complete beam tests of injector