



The SARAF 40 MeV Proton/Deuteron Accelerator

I. Mardor, D. Berkovits, I. Gertz, A. Grin, S. Halfon, G. Lempert, A. Nagler, A. Perry, J. Rodnizki, L. Weissman Soreq NRC, Yavne, Israel K. Dunkel, M. Pekeler, C. Piel, P. vom Stein RI Research Instruments, Bergisch Gladbach, Germany

SRF09, Berlin-Dresden MOODAU04, September 21th, 2009

Soreq Applied Research Accelerator Facility



Current Range	0.04 – 2 mA (4 mA)	
Operation mode	CW and Pulsed	
Maintenance	Hands-On (beam loss < 1 nA/m @ 40 MeV)	A. Nagler et al., LINAC 2006

21/9/2009

I. Mardor, SRF09, MOODAU04

SOREQ

SARAF Phase I – Upstream View

ACCEL G

A. Nagler, Linac-2006 C. Piel, EPAC-2008 A. Nagler, Linac-2008 I. Mardor, PAC-2009

SARAF Phase I – Downstream View





EIS: measured emittance values

EIS has been in routine operation since 2006

ε _{rms_norm100%} [π mm mrad]				
Particles Beam current	Protons X / Y	Deuterons X / Y		
5.0 mA	0.20 / 0.17	0.13 / 0.12		
2.0 mA	0.13 / 0.13	0.14 / 0.13		
0.04 mA	0.18 / 0.19	0.05 / 0.05		
Specified value $= 0.2 / 0.2 [= mm mrad]$				

Specified value = 0.2 / 0.2 [π mm mrad]



176 MHz 4-Rod RFQ

RFQ Beam Properties					
Beam Parameter	Protons	Deuterons			
Energy (MeV)	1.5 (1.5)	3.0 (3.0)			
Maximal current [mA]	4.0 (<i>CW</i>) (4.0)	2.5 (<i>10</i> -4) (4.0)			
Transverse emittance, r.m.s., normalized, 100% [π·mm·mrad]					
(@ 0.5 mA, closed LEBT aperture)	0.17 (0.30)	NM			
(@ 4.0 mA, open LEBT aperture)	0.25 / 0.29 (0.30)	NM			
Longitudinal emittance, r.m.s., [π·keV·deg/u] (@ 3.0 mA)	30 (120)	NM			
Transmission [%] (@ 0.5 mA)	80 (90)	NM			
(@ 2.0 mA)	70 (90)	NM			
(@ 4.0 mA)	65 (90)	70 (90)			

	RF Conditioning Status		
Deuteron operation	Input Power [kW]	Duration [hrs]	
requires 260 kW CW over 3.8 m rods (65 kV)	190 (CW)	12	
	210 (CW)	2	
	240 (CW)	0.5	
	260 (DC - 80%)	0.5	





SOREQ

Prototype SC Module (PSM)



General PSM Design:

- Houses 6 176 MHz β=0.09 HWRs and 3 sc solenoids
- Accelerates protons and deuterons from 1.5 MeV/u
- Very compact design in longitudinal direction
- Cavity vacuum and insulation vacuum are separated

Linac Lattice:

- 2 SC modules
 - Each housing 6 β=0.09 HWRs
- ✤ 4 SC modules
 - * Each housing 8 β =0.15 HWRs
- Total of 44 SC cavities

M. Pekeler, LINAC 2006

SOREQ

HWR peak fields and dissipated power

	At RI (single cavity	7)	At Soreq (i	inside PSM)		
Cavity #	Vertical Test [W]	Be Proces	efore sing [W]	After H Process	elium ing [W]	RF Processing: Closed loop
	25 MV/m	20 MV/m	25 MV/m	20 MV/m	25 MV/m	voltage controlled oscillator (VCO)
1	7.3	1.9	7	2.2	5.5	
2	7.3	3.0	6.3	4.8	8.7	He Processing: 99.9999% purity
3	6.3	12.3	16.8	7.0	14.8	4×10 ⁻⁵ mbar Pulsed 43 MV/m
4	6.3	11.1		3.9	10.6	
5	5.5	5.4	15.1	3.3	8.8	
6	7.3	9.6		5.4	10.7	
Total	40	43.3		26.6	59.1	More details:
Target	72		72		72	

21/9/2009

I. Mardor, SRF09, MOODAU04



SOREQ

D-Plate for beam commissioning

C. Piel, PAC 2007 L. Weissman, DIPAC 2009



Deuteron beam operation through PSM

- A deuteron beam was passed through a detuned PSM
 - Measure the needed RFQ power for deuteron operation
 - Check alignment of all Phase I components





Deuteron beam – RFQ power and transmission

- Energy reaches its nominal value at lower power.
- D-Plate FC current and MEBT BPMs mark the nominal value
- Nominal deuteron power is 252-253 kW, (including ~7 kW of beam loading)
- ✤ Higher than 4×58 = 232 kW
- Similarity of MEBT and D-Plate FC curves indicate that beam transmission is dominated by RFQ



I. Mardor, SRF09, MOODAU04



Deuteron beam – transverse alignment

- The Y profile was centered by adjusting the field in the quadrupole between the PSM and the D-Plate
- The X profile was less sensitive to this device
 - Beam entered that quadrupole off its axis in the Y plane
- The steerers down stream of the PSM were not used
- Up to DC = 30% In the RFQ power, there is hardly an effect on the beam profiles
 - No significant thermal movements of the rods in the average power range of 26 through 78 kW.



I. Mardor, SRF09, MOODAU04



Proton beam operation through PSM

- A proton beam was accelerated through the PSM with all 6 cavities in locked operation
 - Check stability of cavities and LLRF
 - Compare measurements to beam dynamics simulations





Proton beam – fields, phases, beam energy

- Synchronous phase was found for each cavity by maximizing energy
- Fields, phases and magnet currents were set according to simulations
- The first cavity is used for bunching
- Energy was measured by ToF and compared to simulations

HWR	V _{acc} [kV]	E _{peak} [MV/m]	E _{acc} [MV/m]	Sync. Phase [deg]
1	150	4.5	0.9	-95
2	85	2.6	0.5	0
3	700	21.0	4.3	0
4	550	16.5	3.4	-20
5	550	16.5	3.4	-20
6	900	27.0	5.6	-20





Proton beam – cavities and LLRF stability

- 6 cavity operation tripped every 15-20 minutes, mainly due to cavities 4 and 5
- Detuning 4 and 5 increased stability to many hours
- Observe correlation between cryoplant and cavities stability





Proton beam – Longitudinal emittance

- HWRs 4 and 5 detuned. HWRs 1 - 3 in nominal value
- Measured energetic width using Rutherford scattering
- Varied HWR 6 phase and extracted beam matrix at HWR 3 exit

 $\sigma_{66x}(X_1) = (\sigma_{55e} + 2Y_1\sigma_{56e} + Y_1^2\sigma_{66e})X_1^2 + 2(\sigma_{56e})X_1^2 + 2(\sigma$

***** HWRs 4 and 5 detuned.
HWRs 1 – 3 in nominal value
***** Measured energetic width using Rutherford scattering
***** Varied HWR 6 phase and extracted beam matrix at HWR 3 exit
$$\begin{bmatrix} \sigma_{55x} & \sigma_{56x} \\ \sigma_{65x} & \sigma_{66x} \end{bmatrix} = R^* \begin{bmatrix} \sigma_{55e} & \sigma_{56e} \\ \sigma_{65e} & \sigma_{66e} \end{bmatrix} R_r; R = \begin{bmatrix} 1 & Y_2 \\ 0 & 1 \end{bmatrix} \begin{bmatrix} 1 & 0 \\ X_1 & 1 \end{bmatrix} \begin{bmatrix} 1 & Y_1 \\ 0 & 1 \end{bmatrix}$$

$$\begin{bmatrix} \sigma_{55x} & \sigma_{56e} \\ \sigma_{65e} & \sigma_{66e} \end{bmatrix} R_r; R = \begin{bmatrix} 1 & Y_2 \\ 0 & 1 \end{bmatrix} \begin{bmatrix} 1 & 0 \\ X_1 & 1 \end{bmatrix} \begin{bmatrix} 1 & Y_1 \\ 0 & 1 \end{bmatrix}$$

$$\begin{bmatrix} \sigma_{65x} (X_1) = (\sigma_{55e} + 2Y_1 \sigma_{56e} + Y_1^2 \sigma_{66e})X_1^2 + 2(\sigma_{56e} + Y_1 \sigma_{66e})X_1 + \sigma_{66e} \\ X_1 = \text{Energy gain per degree} \end{bmatrix}$$

Energy ' 0.5

0L -6

-2

0 Energy Gain [keV/degree]

-4

• Longitudinal emittance extracted from polynomial fit parameters Non polynomial behavior indicates non linear operation region

$$\varepsilon_z = 120 \pm 5 \pi \cdot \text{deg} \cdot \text{keV/u}$$
 (30 at RFQ exit in 2008)

I. Mardor, SRF09, MOODAU04



Proton beam - Transversal emittance

- Cavities 4-6 detuned
- Measurements with D-Plate slit-wire system
- X-X' plot and emittance values generated by SCUBEEx and internal Soreq algorithm
- Beam ellipse and satellite distribution recognized
- Emittance value extraction excluded the effect of the satellite distribution

 $\varepsilon_t = 0.14 \pm 0.02 \ \pi \cdot \text{mm} \cdot \text{mrad}$ (0.30 at RFQ exit in 2008)

Low RFQ transmission might be cutting off phase space



21/9/2009

I. Mardor, SRF09, MOODAU04



Summary and Outlook

- 2.7 and 2.1 mA deuteron and proton beams (DC = 10⁻⁴) have been accelerated through the RFQ and PSM up to energies of 3.0 and 3.7 MeV
- RFQ Transmission is low
 - Probable causes: high LEBT emittance, LEBT-RFQ mis-alignment, nonuniform RFQ field
- Longitudinal emittance is high
 - Probable causes: choice of non-linear conditions, non-uniform RFQ field
- Transversal emittance is low
 - **Probable cause**: Low transmission cuts off part of the beam's phase space
- Proton and Deuteron beam commissioning continuing
- RFQ conditioning with new internal parts is ongoing
- Continuation to Phase II is foreseen for the beginning of 2010