

Advances and Performance of Input Couplers at KEK


E. Kako, S. Noguchi, M. Sato, T. Shishido,
Y. Yamamoto, K. Watanabe (KEK, Japan)
H. Jenhani (LAL-Orsay), Zhao T.X. (IHEP-Beijing)

- Introduction
- **STF-I Couplers for STF-1 at KEK**
- STF-II Couplers for S1-G at KEK
- **LAL TTF-V Couplers at KEK**
- cERL Injector Couplers at KEK
- Summary




Coaxial Disk RF Windows (1)

Tristan-type Coaxial Disk Ceramics RF Window




972 MHz RF Window





Coaxial Disk RF Windows (2)

805 MHz Pulsed Coupler
for SNS (ORNL)



Test Stand : 2 MW
Cryomodule : 550 kW
1.3 ms, 10~30 Hz

972 MHz Pulsed Coupler
for ADS (KEK/JAERI)



Test Stand : 2.2 MW
Cryomodule : 350 kW
3.0 ms, 25 Hz



Coupler Activities at KEK (1.3 GHz)



STF-I Couplers



STF-II Couplers



TTF-V Couplers



cERL-Injector Couplers



Required RF Power Level

. for XFEL (TTF-III coupler)

Test stand : 1 MW ($<400\mu\text{s}$), 500 kW (1.3ms, 2/4 Hz)

Cryomodule : 250 kW ($<400\mu\text{s}$), 125 kW (1.3ms, 2 Hz)

Beam operation : 122 kW (1.4ms, 10Hz) at 23.6 MV/m

. for ILC (STF-I, STF-II coupler & TTF-V Coupler)

Test stand : **2 MW ($<500\mu\text{s}$)**, 1 MW (1.6ms, 5 Hz)

Cryomodule : 500 kW ($<500\mu\text{s}$), 250 kW (1.6ms, 5 Hz)

Beam operation : 350 kW (1.6ms, 5Hz) at 31.5 MV/m



. for cERL-injector

Test stand : **200 kW (CW)**

Cryomodule : 50 kW (CW)

Beam operation : 170 kW (CW) at 14.5 MV/m



STF-I Coupler and TTF-V Coupler



STF-I Couplers at KEK (1)

Coupler processing at the test stand

Sept - Dec., 2006



At the Test Stand
under matching condition




STF-I Couplers at KEK (2)


Assembly of STF phase-1 Cryomodule ; Jan.~Apr. 2008




String assembly of
four cavities
&
Installation of
cold couplers



Installation of warm coupler




Attachment of doorknob WG



Connection with high power
rf system


STF-I Couplers at KEK (3)

Coupler processing in the cryomodule at room temp.



In the cryomodule
under total reflection condition

STF-I Couplers at KEK (4)




Max. Input RF Power into Cavity

A/#3 Cavity : 220 kW @ 27.7 MV/m
 B/#4 Cavity : 210 kW @ 27.3 MV/m
 C/#2 Cavity : 360 kW @ 33.9 MV/m
 D/#1 Cavity : 190 kW @ 24.6 MV/m

After warm-up to room temperature,
 C/#2 Cavity : 625 kW (1.5 ms, 5 Hz)


Qext of Input Couplers



$Q_{in} = 1.2 \sim 1.5 \times 10^6$



Deviation ~30 %

STF-II Couplers for S1-Global



TTF-V Couplers at KEK (1)

FJPPL Collaboration
between KEK and LAL



TTF-V couplers ;
Original RF design by DESY,
Mechanical design by LAL,
Fabrication by RI (ACCEL).

TTF-V Couplers at KEK (2)



TTF-V at LAL (#1 and #2)


1.0 MW / 400 μ s, 2 Hz
0.5 MW / 1.3 ms, 2 Hz

Total processing time
~ 25 hours



TTF-V at KEK (#3 and #4)

2.0 MW / 400 μ s, 5 Hz
1.0 MW / 1.5 ms, 5 Hz



TTF-V Couplers at KEK (3)

January, 2009



Assembly in clean room ;
pumping ports & vacuum gauges



Baking at 130°C for 60 h



Set-up of
High Power Test Stand



Step 1 : Target for XFEL (Feb. 2009)

400 μ s, 1.0 MW

1.5 ms, 0.5 MW, 5 Hz

Step 2 : Target for ILC (Mar. 2009)

400 μ s, 2.0 MW, 5 Hz


Step 3 : Target for ILC (May. 2009)

1.5 ms, 1.0 MW, 5 Hz


TTF-V Couplers at KEK (4)

Step 1 ; Target for XFEL (Feb. 2009)

1.0 MW / 400 μ s, 500 kW / 1.5 ms, 5 Hz




TTF-V Couplers at KEK (5)



TTF-V Couplers at KEK (6)


Step 3 ; Target for ILC (May, 2009)

1.0 MW / 1.5 ms, 5 Hz






ERL-Injector Couplers at KEK



2 Input Couplers / Cavity



SUMMARY

- Four STF-I input couplers had been operated at the rf power level of 200~360 kW in the cryomodule tests at 2 K. One coupler was processed in the cryomodule at room temperature up to 625 kW in the 1.5ms and 5 Hz pulsed operation.
- LAL TTF-V input couplers were successfully processed up to the rf power level of the ILC target, 2 MW (400 μ s) and 1 MW (1.5 ms, 5 Hz).
- RF processing of the STF-II input couplers for S1-G and ERL-injector couplers will be started in the next month.

Conditioning of LAL TTF-V Input couplers at KEK-STF



Acknowledgement
Wolf-Dietrich Moeller
(DESY)

Thank you
for your attention.....