

# SRF Challenges for Improving Operational Electron Linacs

C. E. Reece

# Outline

What is the real growing-edge experience with SRF systems for operational electron linacs?

- **Contamination control** → field emission and heat
- **Magnetic field environment** → heat
- **Seals and gaskets** → vacuum leaks
- **Cavity processing protocol** → reliable peak results
- **Fabrication tolerances and HOM damping** → BBU
- **Heat management** → operational limitations & cost
- **Microphonics management** → power efficiency

# Outline


- CEBAF
  - Reworking 20-year-old cryomodules -- **C50**
  - Learning from upgrade prototype cryomodules
  - 12 GeV Upgrade project
- S-DLINAC
  - Improving  $Q$ 's and increasing energy
- ELBE
  - Field emission limited energy
  - Developing SRF gun

# Rework of CEBAF Cryomodules – C50 program

- **Objective**


- Clean-up field emission
- Raise useful gradients from  $\sim 5.5$  MV/m to 12.5 MV/m

- Ten cryomodules were fully disassembled
- Cavities (fabricated 1991)
  - Baked @ 600°C
  - Tuned
  - 30  $\mu\text{m}$  BCP
  - HPR UPW
- Cold rf window moved outboard of new “dogleg” waveguide section
- Cavity pairs assembled under improved cleanroom conditions
- Cryomodules were reassembled, tested, and reinstalled in CEBAF



M. Drury, et al., “Summary Report for the C50 Cryomodule Project”  
TPU108, PAC2011


# Rework of CEBAF Cryomodules – C50 program



Operating range in CEBAF is limited to 13.5 MV/m by RF power

- Excellent improvement in gradient, FE effectively eliminated
- But  $Q$ 's still low in cryomodule – now attributed to **unrecognized magnetized CM components**


Example



# Rework of CEBAF Cryomodules – C50 program

- Established a solid 6 GeV base for the 12 GeV upgrade, but cryo heat load is higher than expected
- Operational setup now considers cavity 2K W/MV as well as MV/m in gradient distribution algorithm

Max 5-pass Exp Energy (GeV)



Evolution of CEBAF energy with C50 progress

# CEBAF Prototype Upgrade Cryomodule Challenges

- **New CM design** – 8-cavity string suspended in space frame
- **New cavity designs** – “HG” and “LL”
- **New Tuners** – two designs tested, “scissor-jack” selected
- **Feedthroughs** – leak tight and thermally stable
- **RF waveguide windows** - leak tight and thermally stable
- **Cu-plated SS waveguide** – low rf loss, low static loss, no particulates
- **Flange seals** – cavity waveguide coupler – serpentine gasket
- **Cavity fabrication tolerances** – HOM damping → BBU

- A.-M. Valente, et al., *Production and Performance of the CEBAF Upgrade Cryomodule Intermediate Prototypes*. TUPKF072, EPAC2004
- C. E. Reece et al., *Performance of the CEBAF Prototype Cryomodule Renascence*,”WEP32, SRF2007
- F. Marhauser , *JLab Cavity Fabrication Errors, Consequences, and Lessons Learned* JLab TN-10-021
- R. Kazimi, et al., *Observation and Mitigation of Multiturn BBU in CEBAF WEPP087*, EPAC08
- F. Marhauser et al. *Critical Dipole Modes in JLab Upgrade Cavities*, THP009, LINAC10


# CEBAF 12 GeV Upgrade

First **two** cryomodules - installation 2011

**Eight** more CMs in 2012-2013

$\geq 108$  MV avg.

300 W @ 2.07K




Cavity: 0.7 m, "Low loss" cell shape, 1.497 GHz  
8 cavities/cryomodule

# 12 GeV Upgrade Cavities

- **Production process – press for reliable efficiency**
  - **160  $\mu\text{m}$  BCP** and pre-tuned **by vendor**
  - Receipt inspection – mechanical and rf
  - US >> Bake: **600 C, 10 hrs**
  - US >> EP: **30  $\mu\text{m}$ , @20°C** regulated by external water spray
  - US >> **Tune**
  - Helium vessel welding
  - Flange lapping
  - **HPR**
  - Partial assembly
  - **HPR** >> dry in Class 10 cleanroom
  - Final assembly, leak check
  - Bake: **120° C, 24 hrs**
  - **Vertical test @ 2.07 K**
  - **HPR** >> dry in Class 10
  - String assembly


A. Reilly et al., *Preparation and Testing of the SRF Cavities for the CEBAF 12 GeV Upgrade*,"**TUPO061** **this conference**.

# 12 GeV project cavities – to date





# 12 GeV project cavities

Vertical acceptance test of the 8 cavities in C100 string #3



# 12 GeV Upgrade Cavities


- Improved electropolishing process is now standardized and controlled



C. E. Reece and H. Tian, *Exploiting New Electrochemical Understanding of Niobium Electropolishing for Improved Performance of SRF Cavities for CEBAF THP010, LINAC10*

# State-of-the-art production SRF cavity

C100-6



3 Nov 2010

(Q is BCS-limited)

# 12 GeV Upgrade Cryomodule




First cavity string @ completion

Installation of super-insulation on upgrade cryomodule





# Other CEBAF Upgrade SRF Challenges

- Found weak specification on SS helium vessel material
  - High permeability, **degraded cavity Q**
  - Found early, material replaced
  - Issue was resolved quickly
- Higher than expected **microphonic sensitivity** found in first cryomodule
  - Investigation guiding attention to string longitudinal modes
  - Microphonic detuning **budget is 5 Hz RMS**



Detuning limit of C100 cavities with 12 kW of available rf power at several different operating gradients, with 460  $\mu\text{A}$  design beam current



Initial test data from C100-1 CM in CEBAF June 2011 - courtesy Kirk Davis



# CEBAF Upgrade Challenge – Simultaneous Facility Upgrade



Reliable acid transfer?



Cryomodule assembly?




New cleanroom?

Activity Name	Start Date	Finish Date	FY 10	FY 11				FY 12				FY 13					
			FQ 4	FQ 1	FQ 2	FQ 3	FQ 4	FQ 1	FQ 2	FQ 3	FQ 4	FQ 1	FQ 2	FQ 3	FQ 4		
<b>Accelerator Down Periods...</b>	5/16/11 5/15/12	11/15/11 5/15/13															
<b>12 GeV Cryomodule Schedule</b>																	
1.3.1.2 Cavity String Assembly	10/25/10	2/13/12															
1.3.1.3 Cryomodule Assembly	1/21/11	6/14/12															
1.3.1.4 Cryomodules Acceptance Test	6/1/11	7/19/12															
1.3.1.5 Cryomodule Installation & Test	8/8/11	4/9/13															
<b>TEDF Schedule</b>																	
<b>Early Start/Finish</b>																	
6.3.1.2 TED Building Construction	9/27/10	12/30/11															
6.3.1.3 TL Addition Construction	10/1/10	2/3/12															
6.3.1.4 TL Renovation	4/1/11	1/31/13															

C. E. Reece and A. Reilly, *A New Home for SRF Work at JLab--the Technology and Engineering Development Facility*, TUP0061 this conference.

# Injector Upgrade Program

- Energy increase in the injector section from 10 up to 14 MeV
- Increase in current from 60  $\mu\text{A}$  to 150 – 250  $\mu\text{A}$



## S-DALINAC

Freq.: 3 GHz  
Duty cycle: cw  
Temp.: 2 Kelvin  
Max. E.: 130 MeV  
Max. curr.: 20-60  $\mu\text{A}$


Kürzeder et al., *Adv. in Cryog. Eng.* **55A** (2010) 831

**In operation since 1991**

# Cavity improvements by firing



## Improvement of the quality factor



Status:



- 7 of 14 cavities fired
- Q increased from typ.  $8 \cdot 10^8$  to  $1.5 \cdot 10^9$

Effect on accelerator performance (combined with other measures):


Increased energy  
**60 MeV (2007)**  
**80 MeV (2008)**

*R. Eichorn et al., Proc. LINAC 2008 (2008) 395*

# Cold leaks related to helicoflex gaskets




Imprint on the cavity flange



R. Eichhorn et al., Cryo-Opps Workshop 2010

# Waveguide to coaxial power coupler with low transversal fields





$$V_{\text{acc}} \approx 7 \text{ MV}$$

$$Q_{\text{ext}} \approx 5 \cdot 10^6$$

$$\text{kick} \approx -(2,2+i \cdot 3,2) \cdot 10^{-6}$$



M. Kunze et al., Proc. LINAC 2004 (2004) 736





# Waveguide cold-warm transition

Special waveguide to reduce heat radition

small bars inside the waveguide  
cooled down to 77 K



with the appropriate distance  
the RF reflection is minimized  
at working frequency



-> Poster: R. Eichhorn et. al.


Flexible WR-284 waveguides (custom product)

- stainless steel
- copper plated




# Upcoming Upgrades (2011-2013), fully financed

- Installation of a third recirculation path allows 130 MeV in cw operation (currently 85 MeV)



- Installation of two scraper systems (injector arc and extraction beam line): halo free beam with excellent energy definition
- Improvement of the LLRF system and non-isochronous beam dynamics



- 1: Diagnostic station, IR-imaging and biological IR experiment
- 2: Femtosecond laser, THz-spectroscopy, IR pump-probe experiment
- 3: Time-resolved semiconductor spectroscopy, THz-spectroscopy

- 4: FTIR, biological IR experiment
- 5: Near-field and pump-probe IR experiment
- 6: Radiochemistry and sum frequency generation experiment, photothermal deflection spectroscopy


**thermionic DC gun**  
 250 kV  
 <80 pC  
 $\leq 260$  MHz  $\sim 500$  ps  
 $\sim 10$  mm mrad

**RF buncher**  
 260 MHz  
 +1,3GHz  
 compr.  $\sim 100:1$

**linac**  
 1,3 GHz  
 $\sim 20$  MeV @ 10 MeV/m  
 CW

**magnetic bunch compressor**  
 $R_{56} < 500$  mm

**linac**  
 1,3 GHz  
 $\sim 20$  MeV @ 10 MeV/m  
 CW




**helium liquifier LINDE**  
 200 W @ 1,8 K




**Superconducting Radio Frequency Photo Gun**  
 9.5 MeV  
 80 pC / 1 nC  
 $\leq 13$  MHz  $\sim 5-20$  ps  
 $\sim 1-3$  mm mrad



- performance of the four TESLA cavities @ ELBE



Cavities produced by ACCEL Instruments  
 In CW operation since 2002 (cavities C1, C2) and 2005 (C3, C4)  
 Gradient limit is field emission



- ELBE Superconducting RF Photoinjector**
- New Injector for the ELBE SC Linac
- Test Bench for SRF Gun R&D




- 1: Time resolved semiconductor spectroscopy, THz-spectroscopy
- 2: Femtosecond laser, THz-spectroscopy, IR pump-probe experiment
- 3: Diagnostics station, IP-imaging and biological IP experiment

- 4: FTIR, biological IR experiment
- 5: Near field and pump-probe IR experiment
- 6: Radiochemistry and sum frequency generation experiment, microscopy

Installation of electron beamline to ELBE (dogleg) was finished in 2010

## • SRF Gun cavity performance




In CW:  
 Max. 16 MV/m peak field  
 = 6 MV/m acc. gradient  
 = 3 MeV beam energy

Improvement  
 requires new cavity  
 JLab collaboration



standard  
 RRR 300  
 Nb cavity


large grain  
 Nb cavity



Cavity gradient strongly determines  
 beam energy, maximum bunch charge & beam quality

# 10 kW Solid State Power Amplifier

**Bruker BioSpin S.A. Wissembourg, France**



Two amplifiers has been in routine operation since 2010

# Acknowledgements

- **Mike Drury** served as the project manager of the C50 project
- **Kirk Davis** is the source of all microphonic characterization measurements at JLab
- *Many* other members of the Jefferson Lab staff also made numerous vital contributions to the JLab work summarized here
- **Ralf Eichhorn** provided information on progress at S-DALINAC
- **Jochen Teichert** provided information regarding recent ELBE activities

# SRF Challenges to Operational Electron Linacs

## Conclusion

- While designs and technology continue to develop, the very real challenges of affording thoroughly vetted designs and effective quality assurance remain quite present in multiple domains that are crucial to the operational success of SRF-based particle accelerators.
- The pressure to realize peak performance reliably and efficiently in this context is unrelenting – but a worthy challenger with which to contend.