

Towards a Multi TeV Linear Collider; Drive Beam Generation with CTF3

H.H. Braun / CERN, on behalf of the CTF3 collaboration

- Introduction CLIC & CTF3
 CTF3 status and achievements
- CTF3 outlook







CLIC aim:

develop technology for e^{+} collider with E_{CMS} = 3 TeV covering full LHC physics reach with complementary lepton collision experiments

Physics motivation:

"Physics at the CLIC Multi-TeV Linear Collider : report of the CLIC Physics Working Group," CERN report 2004-5

Present goal:

Demonstrate all key feasibility issues by 2010

BASIC FEATURES OF CLIC

- High acceleration gradient
 - "Compact" collider 3 TeV with overall length < 50 km
 - Normal conducting accelerating structures
 - High acceleration frequency
- Two-Beam Acceleration Scheme



- Cost-effective & efficient
- Simple tunnel, no active elements
- Central injector complex
 - "Modular" design, can be built in stages

CLIC TWO-BEAM SCHEME





Next slides resembles almost the previous, but we have changed 6 details.

Who finds them first ?



Recent changes of key CLIC parameters

Main Linac RF frequency	$30 \text{ GHz} \Rightarrow 12 \text{ GHz}$
Accelerating field	150 MV/m ⇒ 100 MV/m
Overall length @ E _{CMS} = 3 TeV	33.6 km ⇒ 47.6 km

Why?

Very promising results of earlier Molybdenum test structures not reproduced for test conditions closer to LC requirements (i.e. long RF pulses, low breakdown rate, structures with HOM damping)

Copper structure tests don't indicate advantage of frequencies>12 GHz for achievable gradient

Parametric cost model indicates substantial cost savings for 12 GHz/100 MV/m (flat minimum for this parameter range)

Increase chance of feasibility demonstration by 2010

100 MV/m is lowest gradient for a 3 TeV machine

⇒ See Walter Wuensch's talk Thursday

CLIC RF power source layout





Motivation and Goals of CTF3 collaboration

- Build a small-scale version of the CLIC RF power source, in order to demonstrate:
 - full beam loading accelerator operation
 - electron beam pulse compression and frequency multiplication using RF deflectors
- Provide the RF power to test the CLIC accelerating structures and components
- Tool to demonstrate until 2010 CLIC feasibility issues identified by ILC-TRC in 2003



CTF3 collaboration official members

Country	Institute	
20 member states	CERN	
Finland	Helsinki Inst. of Physics	
France	DAPNIA	
	LAL	
	LAPP	
India	BARC	
	RRCAT	
Italy	LNF	
Pakistan	NCP	
Russia	BINP	
	IAP	
	JINR	
Spain	CIEMAT	
	IFIC	
	UPC	
Sweden	Uppsala University	
Switzerland	PSI	
Turkey	Ankara Universities	
USA	NWU	
	SLAC	

collaboration board

chairman *M. Calvetti / LNF*

spokesperson G. Geschonke / CERN



CTF3 build by a collaboration like a particle physics experiment



CTF3 in 2006



Fully beam loading operation in CTF3



theoretical RF-to-beam efficiency: 96%



CTF3 Drive Beam Acc. Structures (3 GHz) – SICA (Slotted Iris – Constant Aperture):

- 32 cells
- 1.2 m long
- $2\pi/3$ mode
- 6.5 MV/m av. acc. gradient for 3.5 A beam current
 - HOM damping slots



Full beam loading operation in CTF3 -Demonstration for CLIC operation

CLIC: no RF pulse compression length of the drive beam pulse: 100 μs

Demonstration at CTF3:



Setup: no RF pulse compression for this experiment (with exception of MKS03) 1.5 μs long pulses

Adjust RF power and phase and beam current, that fully loaded condition is fulfilled



Full beam loading operation in CTF3 - Demonstration for CLIC operation

Idea: Delay always one klystron pulse after the beam pulse and measure relative energy in spectrometer 10 and compare with calculations.

An exact knowledge of the structure input power, the beam current and the energy gain is essential.

MKS05	MKS06	MKS07	
in	in	in	total energy
out	in	in	lower energy



- o "missing" acceleration (energy gain per structure)
- o deceleration due to direct beam loading

from calculations (beam current)

measured RF-to-beam efficiency: 95.3 % Theory: 96% (~4 % ohmic losses)

How does the bunch frequency multiplication work?





Phase coding and bunch frequency multiplication in delay loop



Commissioning of the Delay Loop - SHB system

Key parameters for the SHB system: 1) time for phase switch < 10 ns (15 1.5 GHz periods) 2) satellite bunch population < 7 % (particles captured in 3 GHz RF buckets)

phase switch:

satellite bunch population:



Phase switch is done within eight 1.5 GHz periods (**<6 ns**).

Satellite bunch population was estimated to ~8 %.



Summary of recent CTF3 Achievements

Nominal beam production and stable acceleration of 3.5 A beam with full pulse length without significant emittance growth. Wakefields kept under control with HOM damping+detuning and strong transverse focusing.

Measured performance is consistent with predictions from beam dynamics simulations.

- Measured RF power to beam energy transfer efficiency of 95% in fully loaded operation for normal conducting linac ! Proves that drive beam production is as efficient as predicted.
- Demonstration of bunch frequency multiplication with delay loop using RF deflector cavities and phase coding with rapidly phase switched subharmonic buncher. This is a key ingredient to achieve bunch train compression.
- Routine 24h, 7 days a week operation of fully loaded linac for 30 GHz production \Rightarrow fully loaded operation can be very reliable and stable.

Next step: Combiner Ring commissioning spring 2007

CERN: Layout, infrastructure, cabling, magnets, power supplies, installation CIEMAT: Septa magnets, sextupoles, correctors, extraction Kickers INFN: RF deflectors, wiggler, vacuum chambers, BPM (BPI) LAPP: BPM electronics LURE: quadrupoles BINP: magnet realization

Some remarks about CLIC parameter change and CTF3

Bunch repetition frequency of drive beam can be readily chosen as 6, 9, 12, 15 GHz by varying number of stacking turns in combiner ring and fine tuning of ring circumference with wiggler. Drive beam can produce RF on any harmonic of these frequencies. This makes adaptation of CTF3 drive beam to new frequency straight forward !

Definitive frequency choice was urgent, since ordering of RF components for CLEX two beam test has to start now.

Functionality and Specifications for TL2 (commissioning spring 2008)

Transport of drive beam from combiner ring extraction to CLEX

Bunch length manipulation with R_{56} variable in the range -0.35m< R_{56} <0.35m, with compensated T_{566} .

Emittance dilution < 10% (for 150 MeV, $\varepsilon_{x,y}$ =100 µm)

Vertical achromat for 50 cm vertical displacement to adapt for different floor level of CLEX relative to EPA building

"Tailclipper" consisting of a fast kicker plus a collimator dump to adjust beam pulse length for drive beam in two beam test stand and TBL



For more details \Rightarrow talk by Amalendu Sharma (Tuesday)



CLEX building

June 2006

THE DER.

25.10.2006

31.8.2006

Jan 2007





Construction on schedule Equipment installation from May 2007, Beam foreseen from March 2008

CLEX Glossary

CLEX=CLIC EXperimental area

TBTS=Two Beam Test Stand Testbed for 12 GHz RF tests of drive beam decelerating structures (PETS) and main beam accelerating structures. Demonstration of two beam acceleration

TBL=Test Beam Line Feasibility demonstration of CLIC drive beam decelerator

CALIFES=Concept d'Accélérateur Linéaire pour Faisceau d'Electrons Sonde 3 GHz probe beam injector to simulate main beam in TBTS

TL2'

switchyard for drive beam and drive beam diagnostics

ITB=Instrumentation Test Beam Option for 2nd beamline connected to CALIFES for development and test of beam diagnostic equipment

Layout of CLEX-A (A=Accelerator housing) floor space



Space reservations

- CALIFES 23.2 m from cathode manipulator arm to exit flange of spectrometer
- **TBTS 16.6 m from output spectrometer to end of beam dump**
- TBL 31.4 m from dogleg bend to end of beam dump
- ITB 16.0 m from 2nd dogleg magnet to end of beam dump (optional, not funded yet)

180 MeV Probe Beam Injector



ALITES = Concept d'Accélérateur LInéairepour Faisceau d'ElectronsSonde

choice of architecture :

- 1 photo-injector
- 3 LIL sections: 1 for compression and 2 for acceleration
- 1 beam line with diagnostics (leading to 2-beam teststand)





Probe Beam RF Gun









CERN installation



Fiber-optics coding system



UPPSALA UNIVERSITET

Two Beam Test Stand



Roger Ruber 17-Jan-2007

CTF3 Collaboration Meeting - Two Beam Test Stand

Conclusions

- New CLIC key parameters to adapt to recent structure test results and outcomes of cost optimizations
- CTF3 installations and machine experiments on schedule for feasibility proof by 2010
- Organization of CTF3 as an international collaboration modeled after big particle physics experiment works astonishingly well !