NAME OF MACHINE Groningen Isochronous	Cyclotron DATE Aug. '78
INSTITUTION Kernfysisch Versneller I	nstituut
ADDRESS Zernikelaan 25, Groninge	n, The Netherlands.
R.H. Siemssen	REPORTED by
HISTORY AND STATUS	MAGNET
DESIGN, date 1963 MODEL tests 1964–1966	POLE FACE diameter 280 cm; R extraction 121 cm
ENG. DESIGN, date 1966-1968	GAP, min 22.4 cm; Field 20 kG at $\times 10^6$ max 45 cm; Field 10 kG
CONSTRUCTION, date 1968-1970	max 45 cm; Field 1() kG ampere turns
FIRST BEAM date (or goal) 1970	AVERAGE FIELD at R ext 16 kg ampere turns
MAJOR ALTERATIONS <u>central region (1972)</u>	CURRENT STABILITY + 5 parts/10 ⁶ ; B _{max} /⟨B) 1 .25
OPERATION, 126 hr/wk; On Target 84% hr/wk	NUMBER OF SECTORS 3; SPIRAL, max 56 deg POLE FACE COIL PAIRS: AVF/sec;
	Harmonic correction 5 / sector
	Rad grad/sec or Circ coils12
USERS' SCHEDULING CYCLE — weeks COST, ACCELERATOR \$ 4 \pm 10^6	WEIGHT: Fe 650 tons; Coils 29 tons
	CONDUCTOR, Material and type aluminum
COST, FACILITY, total	STORED ENERGYMJ
Groningen oniversity	COOLING SYSTEM demin. water
ACCELERATOR STAFF, OPERATION and DEVELOPMENT	POWER: Main coils 360 max, kW
	Trimming coils 100 max, kW
SCIENTISTS 2 ENGINEERS 1 TECHNICIANS 10 CRAFTS 2	YOKE/POLE AREA 113 %
TECHNICIANS 10 CRAFTS 2 GRAD STUDENTS involved during year 1 OPERATED BY Res staff or 8 Operators 4)	SECTOR ANGLE (Sep Sec) - deg
GRAD STUDENTS involved during year 1	ION ENERGY (Bending limit) $E/A = 160 ext{ g}^2/A^2 ext{ MeV}$
OPERATED BY V Res staff or 8 Operators	(Focusing limit) $E/A =80$ q/A MeV
BUDGET, op & dev	
FUNDED BY Groningen University and	ACCELERATION SYSTEM
Foundation F.O.M.	DEES, number 1 angle 180 deg
RESEARCH STAFF, not included above	BEAM APERTURE 2.5 cm; DC BIAS 0.5 kV
USERS, in house 20 outside 8	TUNED by, coarse mov. short fine trim.cap.
GRAD STUDENTS involved during year11	TUNED by, coarse $\underline{mov.short}$ fine $\underline{trim.cap}$. RF $\underline{4.7}$ to $\underline{13.9}$ mHz, stable $\pm\underline{5}$ /10 ⁶
RES. BUDGET, in house	Orb F to mHz; GAIN, max 140kV/turn
Foundation F.O.M.	DEE-Gnd, max 70 kV, min gap 1 cm STABILITY, (pk-pk noise)/(pk RF volt) 3.10 ⁻⁴
FACILITIES FOR RESEARCH	
SHIELDED AREA, fixed m ²	RF PHASE stable to ±deg
movable (450)	RF POWER input, max 150 kW
TARGET STATIONS 8 in 6 rooms	
STATIONS served at same time, max	Type <u>series tube</u>
MAG SPECTROGRAPH, type Q3D	FREQUENCY MODULATION, rate()/sec
COMPUTER, model 3 PDP 15	MODULATOR, type
OTHER FACILITIES	BEAM PULSE, width
In-beam gamma ray facility	VACUUM SYSTEM
Gamma multiplicity set-up	PUMPS, No., Type, Size 2 diffusion pumps
Scattering chambers	Ø 50 cm, one 3000l/s cryopump
Beam pulser	OPERATING PRESSURE 2 µTorr,
REFERENCES/NOTES	• • • • • • • • • • • • • • • • • • • •
1) 3 more target stations and one	PUMPDOWN TIME hrs
more room in 1979.	ION SOURCES/INJECTION SYSTEM
2) axial injection in design stage.	Livingston (2 types)
3) computer control: start in 1979.4) 8 half-time operators.	PIG (in development)
7, 0 harr time operators.	EXTRACTION SYSTEM
	electrostatic 55°
	manua1 3)
	malla1 ,

ENTRY	NO.	44	(cont.)				

BEAM PROPERTIES

CHARACTERIST	IC BEAMS			BEAM PROPERTIES	
		₹ ₹	Achieved	Measured 5 40	Conditions
	Particle	(MeV)	(Me∨)	Pulse Width 5-40 RF deg	µA of MeV
ENERGY	α	25	140	Phase Exc, max RF deg	μA ofMeV
	$\frac{\alpha}{12_{C}3+,4+}$	50 -	200	Extract Eff 50 %	μA ofMeV
	1604+		60	Res, ΔΕ/Ε 0.3 %	μA of MeV
				Emittance	
CURRENT *)		(μA)	(μΑ)	$(mm-mrad) \left\{ rac{30}{20} axial \$	μA of MeV
				OPERATING PROGRAMS, time di	st
External				Basic Nuclear Physics	80%
				Solid State Physics	%
				Bio-Medical Applications	%
				Isotope Production	<i>'</i>
		(part/s)	(part/s)	Development	10 %
Secondary				radiation damage st	udies 3 %
			-		%

PLAN VIEW OF FACILITY, NOTEWORTHY FEATURES, OPERATION SUMMARY, ADDITIONAL REFERENCES plan view and status report: Dermois et al., these Proceedings.

beam currents for light ions limited by septum dissipation.

300 nA analysed beam on target typical
beam currents for C and O beams limited by Livingston source:
5-400 en A external.