



LEIR Commissioning and Performance

Christian Carli

on behalf of the I-LHC and LEIR teams

Acknowledgements:


LEIR is the result of the work of many people from several departments at CERN and outside CERN,


Special thanks to M.Chanel for help and advice

- Introduction
- Overview of the LHC Ion Injector Chain
- LEIR Overview
- LEIR Commissioning and first Runs
- LEIR Performance
 - “Early” LHC Ion Beam
 - Nominal LEIR Operation
 - Comparison with design values
 - Dynamic Vacuum and Beam Life-Time
- Summary

Introduction

- LHC (Large Hadron Collider) main diet : protons.
- In addition, ion operation during several weeks per year :
 - ALICE experiment optimized to observe ion collisions
 - CMS and ATLAS intend to take data with ions as well
 - Initially Pb ↔ Pb operation
 - Later (likely, but not in baseline) :
 - p ↔ Pb
 - Lighter ions (e.g. In, Kr, Ar, O).





- No way to satisfy LHC needs with the pre-LHC-era ion chain.
- Accumulation with electron cooling in LEIR to produce the bright beams needed (chosen amongst several proposals after tests in the 90ies).

- Nominal Lumi achievable in LHC ? (LHC limitations: collimation, bound free pair production), demanding for whole chain!
- Early LHC Ion Operation Scheme :
 - Lower Luminosity $5 \times 10^{25} \text{ cm}^{-2} \text{ s}^{-1}$ (instead of $10^{27} \text{ cm}^{-2} \text{ s}^{-1}$) useful for first physics
 - Nominal bunch population (instrumentation),
 - Simplified injector chain and faster LHC filling,
 - Gain experience on LHC ion operation without danger to damage the machine.

Overview of the ion chain for LHC

Protons
Pb Ions


LHC (two ring collider):

- Filling with 12 SPS batches and 592 bunches during ~10min/ring
- Limitations: Collimation, Ions capturing the electron from an electron positron pair

SPS:

- Accumulation of up to 13 PS/LEIR cycles
- Limited by space charge tune shift, IBS ?

Transfer PS to SPS:
Stripping Pb^{54+} to Pb^{82+} in low β insertion



PS:

- Provides bunch structure (spacing) for nominal beam
- Complicated RF gymnastics (with new low level RF) for nominal beam)


Ion Linac 3 :

- New ECR source (200 μ A of Pb^{27+}) in collaboration with CEA Grenoble)
- 5 Hz repetition rate
- Stripping Pb^{27+} to Pb^{54+}
- Energy ramping for LEIR injection

“Low Energy Ion Ring” LEIR:


- “New” accumulator (using existing LEAR hardware) added to ion chain
- Transforms several long Linac3 pulses into short dense bunches
- Multiturn injection with stacking in momentum and both transverse phase spaces
- New state-of-the-art electron cooler constructed by a BINP team

Overview of the ion chain for LHC



Parameter	Linac 3	LEIR3		PS		SPS		LHC	
		nominal	early	nominal	early	nominal	early	nominal	early
energy per nucleon	4.2 MeV	4.2 MeV		5.9 GeV		72 MeV		2.76 TeV	
Charge state	27→54	27 → 54		54 → 82		82		82	
Shots accumulated		~5-7	1	1	1	8,12,13	4	12	16
LHC bunches/shot (filling)	≤ 1	4	1	4	1	≤ 52	4	592	62
Ions/LHC bunch		2.25 10 ⁸		1.2 10 ⁸		0.9 10 ⁸		0.7 10 ⁸	
Ions/shot (filling)	11.5 10 ⁸	9 10 ⁸	2.25 10 ⁸	4.8 10 ⁸	1.2 10 ⁸	≤ 47 10 ⁸	3.6 10 ⁸	415 10 ⁸	43 10 ⁸
Bunch spacing		350 ns		99.8 ns	1350ns	99.8 ns	1350ns	99.8 ns	1350 ns
Norm. rms emittance	0.25 μm	0.7 μm		1.0 μm		1.2 μm		1.5 μm	
Long. emitt./LHC bunch ($4 \pi \sigma_E \sigma_t$)		0.025 eVs/n		0.05 eVs/n		0.24 eVs/n		1 eVs/n	
rms bunch length		50 ns		1 ns		0.41 ns		0.25 ns	
Cycle/Filling time	>200ms	3.6s	2.4s	3.6s	2.4s	~50 s	~15 s	~10 min	~4 min
β^*								0.5 m	1.0 m
Initial luminosity (10 ²⁷ cm ⁻² s ⁻¹)								1	0.05
Initial lumi. decay time (2 experiments)								~5.5 hrs	~ 10 hrs

LEIR Overview






Accumulation alternates :

- Elaborate multiturn injection :
 - Stacking in three phase planes,
 - Needs momentum ramping and dispersion at injection,
 - 70 turns ($200 \mu\text{s}$) with $>50\%$ efficiency every 200 to 400 ms.
- Fast electron cooling :
 - New cooler constructed (BINP)




- Basic shape: square
 - with long bending section in corners
 - four long straights
- Requirements (rather different for injection and cooling):
 - Injection and cooling in adjacent straights
 - Injection: large (normalized) dispersion,
 - Cooler: small dispersion (large momentum spread injected) and $\beta \sim 5$ m
 - Neglecting cooler periodicity two and symmetry
 - Sufficient acceptances and suitable working point
 - Cooler introduces coupling:
 - Compensated with short solenoids (plus skew quads)
 - Additional focusing compensated globally (readjustment of all quad families and trim power converter close to cooler)
 - No periodicity any more, but still one symmetry plane.

LEIR Overview




- Lattice functions for one half of LEIR and working point (black: nominal working point, grey: alternative working points)

LEIR – Acceleration and Eddy Currents




- Acceleration (transverse optics perturbations):
 - C-shaped magnet & vacuum chamber not isolated w.r.t. ground,
 - Net current along the chamber,
 - Gradient “seen” by beam,
- Correction needed:
 - Readjustment of quad currents (5 families),






Measured Quadrupole currents along the machine cycle with compensation of gradients in bends during ramp

LEIR Commissioning and first runs (brief Summary)



- Injection Line in Spring 2005
 - In parallel to Ring Installation
 - Some difficulties with Matching and Controls
- Ring commissioning start in autumn
 - Start with O^{4+} (expected longer life-time ??)
 - Controls (new developments for LHC applied/tested with LEIR)
 - Circulating beam and good injections efficiency rather quickly
 - Progress slowed down due to short life-time: Ions hit a Beam Ionisation Profile Monitor
 - Weak signs of cooling only
 - Pick-up Cable problem:
 - Ramp induced currents damage pick-up cables
 - Ramp temporarily reduced





LEIR Commissioning and first runs (brief Summary)



- Shutdown in January & February 2006:
 - Replacement/improvement of Ionisation Profile Monitor (absorbers)
 - Definite fix of Pick-up cable problem
- Completion of LEIR commissioning with Pb⁵⁴⁺
 - Some work on injection matching needed again
 - Hardware fixes during “shutdown” very beneficial
 - Cooling and accumulation observed quickly (better life-time)
 - Acceleration and ejection and transfer to the PS injection
- LEIR commissioning completed on 12th May 2006
(early beam demonstrated – two injections and faster acceleration)
- First LEIR run in autumn 2006 to provide “early” to the PS
 - Fast start with beam (after delay due to cooler collector vacuum leak)
 - Fluctuations of injection line and efficiency due to PS stray field
- Second LEIR run started in August 2007 (provide beam to the SPS)
 - Again smooth start-up and operation


LEIR Performance – “early” beam




■ Properties of the “Early beam” in LEIR measured this year:

- One Linac3 shot just sufficient: $2.25^8 10 \text{ Pb}^{54+}$ ($1.2 10^{10}$ charges) required
- Longitudinal emittance: measurements gives rms emittance for entire nucleus
 - $(4/208n) * 1.3 \text{ eVs} = 0.025 \text{ eV/n}$ (as specified)



LEIR Performance – “early” beam



- Transverse emittances:
 - application gives one rms physical emittances
 - Horizontal: $\epsilon_{rms}^* = 0.5 \mu\text{m}$ (larger than in 2006, but o.k.)
 - Vertical: $\epsilon_{rms}^* = 0.2 \mu\text{m}$






LEIR Performance – nominal beam



- Evolution of longitudinal Schottky spectra during accumulation (measured with a commercial FFT spectrum analyser)


LEIR Performance – nominal beam



RMS Emitt. = 1.94 eVs BF = 0.316
 90% Emitt. = 8.4 eVs Ne = 4.8E9
 Mtchd Area = 11.3 eVs Duration = 219 ns
 Mom. Spread = 9.78E-4 fs0;1 = 1510;1160 Hz

■ Properties of the “nominal beam” in LEIR measured this year:

- Accumulation of up to 5 shots => intensity needed after accumulation
- Loss at beginning of ramp (more pronounced for higher intensities) => only ~2/3 of design intensity at ejection
- Emittances well within specifications




LEIR Performance – Comparison with Design

Parameter	Nominal		“early”	
	design	obtained	design	obtained
Linac3 current (μA)	50	25	50	25
Cycle time (s)	3.6	3.6	2.4	2.4
Inj. efficiency (%)	50	50	50	50
Accumulated. Int. (10^8 Pb^{54+})		~ 10		~ 2.5
Int. for PS (10^8 Pb^{54+})	9	~ 7	2.25	2.25
Hor. norm. rms emitt. (μm)	0.7	0.5	0.7	0.52
Vert. norm. rms emit. (μm)	0.7	0.2	0.7	0.24
Long. emitt. $4\pi \sigma_E \sigma_\tau$ per bunch (eVs/n)	0.05	0.04	0.025	0.025

- Early beam: design performance achieved (smaller emittances)
- Nominal beam: design intensity at ejection not (yet) obtained (small emittances)

LEIR Performance – Dynamic Vacuum and Beam Life-Time




Avalanche-like pressure rise :

- ions lost due to rest gas electron capture (or loss) ($\text{Pb}^{54+} \rightarrow \text{Pb}^{53+}$),
- every lost ion desorbs many rest gas molecules.



LEIR upgrades based on measurements at Linac 3 (AT/VAC & Linac 3 team)

Limitation of tests in '97 successfully cured !




Loss pattern of Pb^{53+} ions around the LEIR ring with collimators and homogeneous gas density

LEIR Performance – Dynamic Vacuum and Beam Life-Time




- Beam intensity (yellow trace) versus time after long accumulation
- About $16 \cdot 10^8$ Pb^{54+} ions accumulated (saturation) – not the record
- Beam life-time ~ 14 s (with cooling !!)
- Dynamic beam life-time not a limitation at present (for “normal” cycles)
- Small influence of position of movable collimators

Summary and Outlook



- LEIR successfully installed and commissioned:
 - Commissioning completed in May 2006 with the demonstration of the “early” LHC ion beam
- LEIR becoming an operational machine:
 - “Early” beam delivered in routine operation for PS and SPS
 - Transfer of LEIR operation to the new Common Control Center
 - Work in parallel on nominal beam (not considered a priority), to sort out technical problems and, to better understand the machine
- Outlook:
 - First LHC Pb ion run probably in 2009 ?
 - Studies on SPS ion fixed target experiments with lighter ions just started
 - LEIR run next year ? (may be with lighter ions in view of SPS fixed target)

LEIR Injection




Principle :

- bumper moves orbit inwards,
- energy ramping moves orbit outwards,
- constant betatron amplitude for incoming beam.

Result :

- long pulses pulses and good efficiency,
- Large momentum spread, relatively small emittances,
- Good for fast accumulation with electron cooling.



1st turn of incoming beam

After 3 turns

End of injection (70 turns)

After collapse of the bump