



Tera Electron Volt  
 Energy  
 Superconducting  
 Linear  
 Accelerator



# Review of Superconducting -vs- Normal-Conducting Accelerator Systems for Linear Colliders



# Luminosity ( $\mathcal{L}$ ) and Beam Power ( $P_{\text{beam}}$ )

---

For NLC & TESLA,  $\mathcal{L}$  Scales Approximately as

$$\mathcal{L} \sim P_{\text{beam}} / (\epsilon_y)^{1/2}$$

where

$\epsilon_y$  = Normalized Vertical Emittance at IP

$P_{\text{beam}}$  = Linac Wall Plug Power (Limited to a Few 100 MW)  
× AC -to- Beam Efficiency (Function of RF Technology)

=  $N_e$ : Number of  $e^+/e^-$  per Bunch  
×  $N_b$ : Number of Bunches Per Pulse  
×  $f_{\text{rep}}$ : Pulse Repetition Rate  
×  $E_b$ : Final Beam Energy

# Linear Collider RF Technologies




- Normal-Conducting RF Accelerator Structures
  - Want high RF frequency to be efficient with lower RF energy per pulse (thus fewer rf components) and higher gradient (thus a shorter linac).
    - Downside is higher wakefields and thus tighter alignment tolerances.
  - NLC/JLC uses 11.4 GHz RF (X-Band), 4 times the SLAC Linac frequency.
    - NLC cost is optimum with an unloaded gradient of 70 MV/m.
  - CLIC uses 30 GHz RF.
    - The 3 TeV collider design requires 170 MV/m unloaded gradient.
- Super-Conducting RF Accelerator Cavities
  - Exploit low cavity losses to deliver energy to beam efficiently and slowly, so less expensive, low peak power sources can be used.
    - Downside is the large damping rings required for the long bunch trains.
  - TESLA operates at 1.3 GHz based on surface resistance – cavity size tradeoff.
    - Design gradient of 23 MV/m based on initial goal: cost optimum higher.

# NLC/JLC Rounded Damped-Detuned Structure (RDDS)


- Made with Class 1 OFE Copper.
- Cells are Precision Machined (Few  $\mu\text{m}$  Tolerances) and Diffusion Bonded to Form Structures.
- 1.8 m Length Chosen so Fill Time  $\approx$  Attenuation Time  $\approx$  100 ns.
- Operated at 45 °C with Water Cooling. RF Losses are about 3 kW/m.
- RF Ramped During Fill to Compensate Beam Loading (21%). In Steady State, 50% of the 170 MW Input Power goes into the Beam.

RDDS Cutaway View  
Showing 8 of 206 Cells



Two RDDS Cells

# TESLA Cavities




- Made with Solid, Pure Niobium (Weak Flux Pinning)
- Nb Sheets are Deep-Drawn to Make Cups, which are E-Beam Welded to Form Cavities.
- Cavity Limited to Nine Cells (1 m Long) to Reduce Trapped Modes, Input Coupler Power Losses and Sensitivity to Frequency Errors.
- Operated at 1.8-2 K in Superfluid He Bath (Surface Resistance Very Sensitive to Contaminates and Temperature: Increases 50 fold at 4.2 K). RF losses ( $Q_0 \approx 10^{10}$ ) are  $\approx 1$  W/m.
- $Q_{\text{ext}}$  Adjusted to Match Beam Loading ( $Q_{\text{beam}} \approx 3 \times 10^6$ ). In Steady State, Essentially 100% of the 230 kW Input Power Goes into the Beam.
  - ↳ Cavity Fill Time = 420  $\mu\text{s}$ .

# Simplified RF System Layout

## (NLC vs TESLA Efficiencies and Average Power)

RF Distribution (Compression in NLC Only)  
(85% vs 94%)



# NLC Linac RF Unit

Low Level RF System


One 490 kV 3-Turn Induction Modulator

Eight 2 KW TWT Klystron Drivers (not shown)

Eight 75 MW PPM Klystrons

Delay Line Distribution System (2 Mode, 4 Lines)

Eight Accelerator S structure Sextets



510 MW  
396 ns

Single Mode Extractor

Klystron RF Pulse  
75 MW, 3168 ns

2 Mode  
Launcher

Six 0.9 m Accelerator Structures  
(85 MW, 396 ns Input Each)

58.6 m

Beam Direction →




# Linac Tunnel (4.3 m ID)

Waveguide  
to Transport RF

Girder Supporting  
3 Accelerator Structures


Quadrupole Magnet on  
Mover Stand






# TESLA RF Station: One Klystron Feeds Three Cryomodules Each Containing Twelve, Nine-Cell Cavities

Length = 50 m, Filling Fraction with Quads = 75%




Future:  $2 \times 9$  Superstructure  
One Feed per Pair, 6 % Shorter


Cryomodule 1 of 3





# TESLA Tunnel



# 30 GHz RF Power Source for the CLIC 3 TeV Collider





300 MW AC Power  
9.8% AC to Beam Efficiency



# X-Band (11.4 GHz) KLYSTRONS

Solenoid Focused Tubes: Have Ten, 50 MW Tubes for Testing, However Solenoid Power = 25 kW.

Developing **Periodic Permanent Magnet (PPM)** Focused Tubes to Eliminate the Power Consuming Solenoid.








# SLAC 75 MW PPM Klystron Program



**XP1:** After a Number of Fixes, Achieved Stable Performance over 70 MW at 3  $\mu$ s, Limited by the Modulator.




**XP3:** Next Generation Tube Designed for Manufacturability

- Diode Version (No RF Cavities) Has Been Successfully Tested. ↗
- First Two Klystrons Have Not Performed Well.
  - Will Autopsy and Rebuild Them

**Long Term:** Sheet Beam Klystron

- Lower Cost.
- Well-Suited for Gridded Gun, Which Would Simplify the Modulator.



# KEK X-Band Klystron Program




- KEK is working with Toshiba to develop PPM tubes as well - the JLC RF system design requires only 1.5  $\mu$ s long klystron pulses.
- Most recent 75 MW tube (PPM-2) basically meets design goals, but full power testing was limited by the modulator.

PPM-2:	Design	Achieved
Peak power	75 MW	75.1 MW at 505 kV
Efficiency	55%	56%
Pulse width	1.5 $\mu$ s	1.4 $\mu$ s at 74 MW 1.5 $\mu$ s at 70 MW
Repetition rate	150 Hz	25 Hz

- Developing new tubes with goals of 60% efficiency (PPM-3: starting test) and easier manufacturability (PPM-4: in design).
- Also working on a 150 MW multi-beam klystron.



# TESLA Klystron Development



## GOAL

Reduce HV Requirements  
and Improve Efficiency  
(Lower Space Charge)  
with  
Multiple Beam Klystron

Use Seven 18.6 A, 110 kV  
Beams to Produce 10 MW  
with a 70% Efficiency

Thales TH1801  
MultiBeam Klystron

Spec's:  
10 MW, 10 Hz, 1.5 ms  
with 4 kW Solenoid Power

First Tube Achieved 65%  
Efficiency at 1.5 ms, 5 Hz and  
Was Used in TTF

2.5 m



Photo of TH1801 Tube  
(top) and Cathode (bottom)





# INDUCTION MODULATOR :


10 Core Test: 22 kV, 6 kA, 3  $\mu$ s Pulses

SUM MANY LOW VOLTAGE (~ 2 kV)  
SOURCES INDUCTIVELY

INDUCTION CIRCUIT (1 OF N)



Insulated Gate Bipolar Transistors




10 cm

Driver Circuit

# NLC Eight Klystron Induction Modulator

## (1 GW Pulsed Power)

Drive 8 Klystrons with a 500 kV, 2 kA, 3  $\mu$ s Pulse Generated from 76, 2.2 kV Induction Cores Summed Through a 3-Turn Secondary.





# Induction Modulator Prototype


Results with a Water Load  
(500 kV, 600 A)



76  
Cores

5045 S-Band Klystron  
Used for Testing


Water Load



Three Turn Secondary

# TESLA Modulator

Use FNAL Design in Which a Bouncer Circuit Offsets the Voltage Droop (19%) During Discharge of a Capacitor Bank






# Program to Improve High Gradient Structure Performance

(70 MV/m Unloaded Gradient Goal for 0.5 & 1 TeV Collider)


- Compare performance versus different:
  - Initial structure group velocity (5 % and 3% c) and length (20, 53 and 105 cm).
  - Cell machining and cleaning methods.
  - Structure type: standing-wave -vs- traveling-wave.
  - ↪ Have processed 12 structures (5000 hours at 60 Hz).
- Systematic study of rf breakdown:
  - Measure breakdown related RF, light, sound, X-rays, currents and gas in structures, WG's and cavities.
  - Measure surface roughness/cleanliness/damage with SEM, EDX, XPS and AES.
- Improve structure handling and cleaning methods.

53 cm Traveling-Wave Structure  
(3.3% c to 1.6% c Group Velocity)









## Example of Low Group Velocity Structure Performance at 70 MV/m (120 Hours of Operation at 60 Hz with 400 ns Pulse Widths)



- Breakdown rate in structure body (**blue** events) = 0.2 per hour or about one in a million pulses.
  - NLC goal is < 0.1 per hour: measure from < 0.1 to 0.3 per hour in five structures.
- Breakdown rate in the two coupler cells (**green** and **red** events) = 5.5 per hour
  - Rates in other structure couplers vary from 0.1 to 5 per hour → **suspect pulse heating at the coupler waveguide openings as the root cause.**


# SEM Photos of Structure Input Coupler Iris and Input Waveguide Openings





# Traveling-Wave Structure Program

- Test couplers with lower pulse heating and surface fields.
  - Several possible designs: rounded edge, mode converter, inline taper and choke joint.
- Beginning tests of 150 degree per cell structures that have NLC-acceptable iris radii and low group velocity.
  - Dipole modes are detuned.
- Designing ‘NLC-ready’ structure with manifold wakefield damping - to be tested in early 2003.







# Standing-Wave Structures

- In NLC, standing-wave structures would operate at the loaded gradient of 55 MV/m.
- In recent tests, measured breakdown rates of  $< 1$  per 8 million pulses at this gradient and no discernable frequency change after 600 hours of operation.
- Pulse heating in coupler likely limiting higher gradient operation – will be reduced in future structures.
- Working to incorporate wakefield damping to make them a viable NLC candidate.

15 Cell, 20 cm Standing-Wave Structure








# Cavity Development


- Goals during past decade: increase cavity gradients from 5 to 25 MV/m and reduce cavity costs by a comparable factor.
- Built on experience from industrial fabrication of cavities for CEBAF.
- Improved material QC and introduced new cavity preparation procedures, including 1400 °C annealing with a titanium getter, ultra-pure, high pressure water rinsing and high-power processing.
- Have achieved gradient goal and now working to increase operating level to 35 MV/m to allow a future TESLA upgrade to 800 GeV cms.



# Field Emission in a Superconducting RF Cavity




## Map of Temperature Increase Caused by Field Emission






# High Gradient Performance

Excitation Curves Measured in the Vertical Cryostat for Cavities from the Third Production Series



Average Cavity Gradients at  $Q_0 \geq 10^{10}$  Measured in the Vertical Cryostat for (a) the First Three Production Series and (b) Cavities Installed in the First Five Eight-Cavity Cryomodules



# High Gradient Studies


Results Using Electro-Polishing (EP)

Technique Developed at KEK in which Material is Removed in an  $H_2SO_4$ , HF Mixture Under Current Flow

-VS-

Buffered Chemical Polishing (BCP)

BCP Surface  
(1  $\mu\text{m}$  Roughness)





← 0.5 mm →

EP Surface  
(0.1  $\mu\text{m}$  Roughness)



← 0.5 mm →




# CLIC Structure Development

High gradient studies:


- Recently achieved 150 MV/m peak unloaded gradient in a low group velocity structure with tungsten irises.
- Testing limited by power source pulse length: 15 ns available, 130 ns required.

Developing wakefield damping and detuning methods at 30 GHz.

- TDS design (see below) successfully tested at ASSET.



Cross-sectional View of the Tapered-Damped Structure (TDS) Geometry.




Photograph of a TDS Cell with Damping Waveguides and SiC loads.

# Next Linear Collider Test Accelerator (NLCTA)

- Construction Started in 1993 Using First Generation RF Component Designs.
- Goals: RF System Integration Test of a Section of NLC Linac and the Efficient, Stable and Uniform Acceleration of a NLC-like Bunch Train.
- In 1997, Demonstrated 15% Beam Loading Compensation of a 120 ns Bunch Train to  $< 0.3\%$ .




## NLCTA Linac RF Unit (One of Two)





# Eight-Pack Test Phase I: Multi-Moded SLED II (Begin Testing in Early 2003)






# Eight-Pack Test Phase II: Full Power, Integrated Test of Essential NLC RF System Components (Full-Scale Testing Begins in Mid-2004)

## Setup Includes:


- Low Level RF System
- 490 kV, 3-Turn Induction Modulator
- Eight 2 KW TWT Klystron Drivers (not shown)
- Eight 75 MW PPM Klystrons
- Reduced Delay Line Distribution System (2 Mode)
- Two Accelerator Structure Sextets (11 m Total)








# The TESLA Test Facility (TTF)



Eight Cavity Cryomodules




TTF Linac



## TESLA Test Facility Phase II: FEL User Facility in the nm Wavelength Range

- 1 GeV Beam Energy Achieved Using 6 Cryomodules with 8 Cavities Each, About 50 m of Accelerator.
- One Cryomodule Will Contain 8 Electro-Polished Cavities.
- Provides Testbed for Klystrons and Modulators Developed with Industry.
- High Gradient Test Program to Start in Summer of 2003.



# Energy Upgrades



- NLC: 1 TeV CMS
  - Fill second half of each tunnel with RF components (linac tunnel length remains the same).
  - Run with same linac beam parameters as 500 GeV operation. Linac AC power doubles.
- TESLA: 800 GeV CMS
  - Run at 35 MV/m with 50% higher beam power (linac tunnel length remains the same).
  - Requires doubling 2 K cooling capacity and number of klystrons and modulators. Linac AC power increases by 50%.
- CLIC
  - Lengthen linac and drive beam.
  - Drive accelerator requires proportionally higher modulator capacity, cooling and AC power.

# Summary



- Both TESLA and NLC/JLC have major rf system tests planned in the next 2-3 years to validate collider operation to 800-1000 GeV cms energies.
  - TESLA TTF2 including a cryomodule operating at 35 MV/m.
  - X-Band 8-Pack rf source powering structures to 70 MV/m.
- CLIC is building the CTF3 two-beam facility (operation in 2006), which will provide a longer pulse power source for high gradient testing.
- Detailed comparison of linear collider designs will be published this October (TRC Report).