


Status & Challenges for LCLS

David H. Dowell
Stanford Linear Accelerator Center
(on Behalf of the LCLS Team)

Free Electron Laser Conference
Berlin, Germany
August 2006

- **Status of LCLS Construction**
- **Overview of the Challenges**
- **Schedule**
- **Summary**

The LCLS will use the last 1/3 of the SLAC linac to create an x-ray FEL




LCLS Design Parameters

<i>Fundamental FEL Wavelength</i>	1.5	15	Å
<i>Electron Beam Energy</i>	13.6	4.3	GeV
<i>Normalized Slice Emittance (rms)</i>	1.2	1.2	mm-mrad
<i>Peak Current</i>	3.4	3.4	kA
<i>Energy Spread (slice rms)</i>	0.01	0.03	%
<i>Bunch/Pulse Length (FWHM)</i>	≤ 200	≤ 200	fs
<i>Saturation Length</i>	87	25	m
<i>FEL Fundamental Power @ Saturation</i>	8	17	GW
<i>FEL Photons per Pulse</i>	1	29	10 ¹²
<i>Peak Brightness @ Undulator Exit</i>	0.8	0.06	10 ³³ *


* photons/sec/mm²/mrad²/ 0.1%-BW

Injector and Bunch Compressor 1 Installation is in Progress at Sectors 20 and 21

Commissioning will begin in Early 2007



LCLS Accelerator and Compressor Systems



BC1 Chicane Support and Translation Stage





Spectrometer Dipole



Dog-Leg-1 Dipole



Injector Quadrupoles




**Gun-Spectrometer
Quadrupole**



Injector Solenoid #2


Cathode Drive Laser Operating at Sector 20



Drive Laser Installed & Vault Ready for Installation



Injector Vault



Drive Laser







Workers



fs Streak Camera

RF Gun Fabrication and Cold RF Testing Finished & Preparing for High-Power Tests




Klystron Gallery at S20 Looking Toward the Undulator and End Stations



Linac is 10 m below gallery

Single Undulator Test (SUT) at ANL





New Magnetic Measurements Facility (MMF)





**MMF Measurement
Bench**



**Undulators being
shimmed at the MMF**


LCLS Site Plan




View of the Research Yard, Looking back toward the Linac



Construction has begun in the SLAC Research Yard with removal of the Final Focus Test Beam (FFTB)




View east toward the experimental halls



Technical Challenges for Angstrom FEL's

- **Gun emittance**
 - Cathode emittance, uniformity, and quantum efficiency
 - RF field quality
 - gun solenoid field uniformity and alignment
- **Drive laser reliability, stability and 3D shaping (UV diagnostics)**
- **Emittance preservation**
 - Optical aberrations and CSR
 - Wakefields
- **Beam Instabilities (CSR, Longitudinal space charge)**
 - Laser-Heater
- **Bunch length diagnostics and control**
- **Alignment**
 - gun to solenoid etc.
 - undulator
- **Magnetic Measurements**
 - Beamline components
 - New measurement facility for undulators
- **RF power stability**
- **Vibrations**
- **Temperature stability and control**

Thales Drive Laser System for LCLS



3D RF Design of Gun


- **Z-coupling:**
 - reduces pulsed heating
 - increases vacuum pumping
- **Racetrack to minimize quadrupole fields**
- **Deformation tuning to eliminate rf tuners**
- **Iris reshaped reducing field 10% below cathode**
- **Increase 0-pi mode separation to 15MHz**
- **All 3D features included in modeling:**
 - laser port and pickup probes
 - 3D fields used in Parmela simulation

RF Parameters	
f_0 (GHz)	2.855987
Q_0	13960
β	2.1
Mode Sep. Δf (MHz)	15
$E_0:E_1$	0.999:1


C. Limborg et al., "RF Design of the LCLS Gun", LCLS-TN-05-3

L. Xiao et al., "Dual feed rf gun design for the LCLS," Proc. 2005 Particle Acc. Conf.



Compliments of Z. Li & L. Xiao



Cathode Qualification System (CQS)




AFM measurement of cathode surface





Compliments B. Kirby


Magnetic Measurements and Calibrations are being performed on all beamline magnets



Gun Solenoid on Magnetic Meas. Test Stand




Injector Diagnostics Are Essential



Slice-Emittance Measurement Simulation

Transverse RF-deflector at 1 MV




Compliments P. Emma


Alignment and Measurement of Everything is Important: Straightness of Injector Linac Section

Coordinate measurement machine measurement
of s-band linac showed a significant bow

Injector S-band Section on CMM



Nearly straightened already (Aug. 21, '06)




Vibration Tolerances have been Determined for all Beamline Components, Especially Solenoids & Quadrupoles


Magnet Name	Δx_{rms} sensitivity [μm]	Δy_{rms} sensitivity [μm]	σ_{rms} tolerance [μm]
S1	1.2	1.2	0.10
S2	2.615	2.850	0.50
QA01	2.615	2.850	0.10
QA02	1.864	3.338	0.10
QE01	25.023	21.28	0.50
QE02	12.427	9.899	0.50
QE03	2.493	4.259	0.10
QE04	3.918	4.203	0.10
QM01	1.615	1.652	0.10
QM02	6.088	1.007	0.10

LCLS Physics Req. Doc. 1.1-008, P. Emma

QM04	1.244	3.158	0.10
QA11	7.854	4.228	0.10



Vibration measurements performed on similar gun and solenoid for E-163 Experiment




Measurement compliments of J. Turner

Undulator Support System

■ Fixed Pedestal

- Designed to be very stable in temperature due to concerns of thermal expansion shifting the quadrupoles
 - Insulated
 - Filled with sand
 - Note: Hall temperature stabilized to +/- 1 deg F





slide compliments S. Milton, ANL


In-Situ Measurement of Undulator K using Angle-Integrated Spontaneous Spectra for 2 Undulators

- Insert 2 ~adjacent undulators.
- Measure e^- energy per pulse.
- $(\Delta\omega/\omega)_{\text{rms}} \approx 0.2\%$, measured to 0.006% resolution.
- Use Si crystal on 111-axis to meas. angle-integrated high-energy spectrum edge.
- Scan undulator x-position ($\Delta K/K = -0.2$ to $+0.2\%$).

See talk by J. Welch,
Session 8, Thursday



Undulator Segment Supports




See talk by H-D. Nunn

E-Beam Alignment Strategy for LCLS Undulators

Session 8, Thursday


Design of Region Between the Undulators



Undulator RF Beam Position Monitor



LCLS Installation and Commissioning Time-Line



Summary

- ***LCLS construction has begun:***
 - ***Laser building at Sector 20 finished***
 - ***Drive laser delivered, installed & operating***
 - ***RF gun fabricated and high-power testing in Sept.***
 - ***Beamline through BC1 installation begun***
 - ***Final Focus Test Beam (FFTB) removed for LCLS construction***
 - ***Undulators arriving from ANL and being magnetically shimmed in new Magnetic Measurement Facility (MMF)***
- ***LCLS design addresses many of the varied technical challenges of Angstrom FELs***
- ***Commissioning of Injector through BC1 to begin in early 2007***
- ***On schedule for first light in 2008 and beam for users in 2009.***