



Status of the Control System for HICAT at an advanced stage of Commissioning Functions, Restrictions and Experiences

T. Fleck
GSI

16. October 2007



CONTENT

1. DESCRIPTION OF THE FACILITY
2. DESCRIPTION OF THE ACCELERATOR
3. STATUS OF COMMISSIONING
4. FUNCTIONS
5. RESTRICTIONS
6. EXPERIENCES

HICAT FACILITY

General Conditions


- Part of the clinic in Heidelberg
 - 1300 patients/year
 - High reliability and stability
 - Term of 25 years
 - Only two operators
-
- First combined proton / heavy ion therapy device in Europe operated by a hospital
 - Two horizontal treatment rooms
 - Target room for medical research
 - Rotatable gantry structure



HICAT FACILITY


Patient Treatment

- Only device using intensity-controlled raster scan method
- Different ions, energies up to 430MeV/u
- 250 energies, 6 foci, 15 intensities (EFI)
→ LIBC (List of Ion Beam Characteristics)




Key Aspects Control System

- Part of a medical product (MDD)
- 500 components
- μ s timing
- Pulse-to-pulse variation
- Modes for commissioning / QA / therapy
- Interface to therapy CS



ACCELERATOR



CONTROL SYSTEM

- Design and functional specifications from GSI
- Realization by an industrial partner (could decide about implementation)
- Commissioning by GSI
- Handing over to operation company (HIT) by GSI
- CS briefing by industrial partner



Implementation:
OS Windows XP / RTX
Oracle Database
TCP/IP based communication
Real-time bus for μ s-timing
Special device control units
C++ and Delphi (GUIs)

CONTROL SYSTEM

Device Control Units

- designed as standard for all beam guiding devices
- 64 MB RAM / 32 MB flash
- FPGA for real-time control (100 MHz)
- 7 device classes / interchangeable
- Special timing master DCU
- Special DCUs with interface to the therapy control system for e.g. fast beam cutoff



Beam Diagnostic Devices

- NI PXI systems
- Trigger pulses provided by special DCUs


Further Systems

- Ion sources
- rf generators
- Vacuum CS
- Personal safety system

STATUS OF COMMISSIONING

- Commissioning for horizontal treatment rooms almost finished:
 - Verified device settings for protons / carbon ions
 - Beam properties meet therapy requirements for most EFI-combinations
- Beam requests by therapy control system
- Integration of all devices finished
- First ion beam in gantry within next few weeks

- Commissioning shifts: GSI / SAG (24/6), HIT-support



FUNCTIONS

Virtual Accelerators

- Device settings and/or control of all necessary elements
 - Experimental VAccs
 - Therapy VAccs including all EFI parameters

Device Settings for Therapy VAccs

- EFI dependencies have to be considered
- Interpolation of whole EFI parameter space necessary
- Persistent storage of device settings

FUNCTIONS

Beam Requests / Operation Modes



- (10 Hz Stability cycles)
- 5 Hz Linac mode
- Pulse to pulse variation of
 - Beam parameters (EFI)
 - Source-target combination
- Procedures for QA
- Therapy control system (safe patient mode)

Measurement / Verification

- Online Data visualization during cycle (magnets / beam diagnostic)
- Snapshot data of all components
- Storage of snapshot data



FUNCTIONS

Calculation of Device Settings and Verification



FUNCTIONS

Online Data and Logged History Data



RESTRICTIONS

Present Restrictions

- No read values outside accelerator cycles
- Standby mode has to be implemented
- Control of dipoles zero magnetic field
- Integration of e.g. cooling water temperature monitoring
- No real parallel operation of ion sources
- Common look and feel (Application programs still prototypes)

EXPERIENCES

- **Major problems during commissioning:**

- Time schedule (6 months delay of CS functionality)

- Lacking time for extended CS tests

- Bottleneck for beam diagnostic data

- Performance and stability

- Complexity of EFI dependencies

- Implementation of automated procedures / therapy protocols

- Only few CS experts

- **Additional requirements came up**

- **On-site CS support by industrial partner necessary**

- **Remote login and experts on call important**

- **User aspects need high priority**

- **Industrial partner: high flexibility / short reaction time /
good cooperation**



Thanks for your attention

Further details / discussion:
poster presentations TBBP39 and RPPB29



[www.klinikum.uni-heidelberg.de/
Heidelberger-Ionenstrahlen-
Therapie-HIT.1165.0.html](http://www.klinikum.uni-heidelberg.de/Heidelberger-Ionenstrahlen-Therapie-HIT.1165.0.html)