

Highlights of Accelerator R&D at Shanghai Light Sources Cluster

Zhentang Zhao

Shanghai Advanced Research Institute (SARI), CAS



Outline

- Shanghai Light Sources Cluster overview
- Accelerator facilities
 - ➤ Shanghai Synchrotron Radiation Facility (SSRF)
 - ➤ Shanghai Soft X-ray Free-Electron Laser (SXFEL)
 - ➤ Shanghai Hard X-ray Free-Electron Laser (SHINE)
- R&Ds of accelerator key technologies
- Summary


Light Source Cluster @Zhangjiang

Zhangjiang High-Tech Park@Shanghai




Large research infrastructures cluster: Zhangjiang Photon Science Facilities

Advanced Light Source Cluster @ Zhangjiang




Accelerator Light Source Facilities

SSRF: Shanghai Synchrotron Radiation Facility



SSRF: Shanghai Synchrotron Radiation Facility

- SSRF is a 3.5GeV third generation light source, consisting of a 150 MeV linac, a full energy booster, and a storage ring with 432m circumference, and currently 23 operating beamlines.
- The SSRF project was launched in Jan. 2004 with the groundbreaking made in Dec. 2004. Its dedication was made in Apr. 2009; Its phase-II beamline project started in Nov. 2016.
- SSRF began its user operation in May 2009. It has served more than 34000 users from with high performance operation fruitful experiment results.



Energy: 3.5 GeV

Emittance: 4.2 nm-rad

Circuference: 432 m

Current: 260±0.5mA (top-up)

SSRF: Phase-II Beamline project

- > 16 New BLs: to expand the application fields
- ➤ Light Source Improvements: more short straight sections, more ID devices, bunch stretching system, backup cryogenic system.
- ➤ User supporting system: labs for sample preparation, including material, chemical, environmental, biological and medical science, in-situ facilities, data center for users
- Lab for BL engineering: optics, mechanics, vacuum, control and electronics, FEA, test beamline
- ➤ Utilities and Logistics: buildings for end station of super-long beamline, user supporting labs, user training and data center

 Spin-ARPES


 Nano-ARPES















SXFEL: Shanghai Soft X-ray FEL Facility




SXFEL: Shanghai Soft X-ray FEL Facility





SXFEL: Shanghai Soft X-ray FEL Facility


SXFEL Facility, located in the SSRF campus, consists of a 1.5 GeV linac and two undulator lines with 5 experimental stations in the water window region



Total length	532m	
Electron energy	1.5 GeV	
Charge	500pC	
Peak Current	700A	
Emittance	1.5 nm-rad	
Global energy spread	0.1%	
Photon energy	0.2 – 0.6 keV	
Pulse length	~100 fs	
Peak photon power	1 GW	
Repetition rate	10 - 50 Hz	

	SASE beamline	HGHG beamline	
Energy range	1.2-12 nm (100-1000 eV)	2.4~24nm (50~500eV)	
Pulse energy	330µJ @100eV,47µJ @620eV	64μJ @56eV , 5μJ @500eV	
Photon flux /pulse	4.6x10 ¹¹ @620eV 5x10 ⁹ @500eV ~2.9x10 ¹² @50eV		
Energy resolution (ΔE/E)	0.04%~0.2% 0.008%~0.04%		
Energy resolving power of spectrometer (Ε/ΔΕ)	~3x10 ⁴ @620 eV	~4x10³ @200eV	
Spot size	~3µm ~10µm		
Pulse width (fs)	117fs@620eV 50 fs@300eV		

SXFEL-UF undulator lines



> FEL1: SASE FEL line with 10 IVUs





> FEL2: Seeded FEL line with 20 undulators




SASE line: lasing at 2 nm!

May 14, 2021





SHINE: Shanghai High repetition rate XFEL and Extreme light facility



Accelerator Layout of SHINE







Main Parameters of SHINE

Range

3.1

5.9

12

3.6

Nominal

3.1

5.9

12

2.28

Total facility length/km

Tunnel diameter/m

2K Cryogenic power/kW

RF Power/MW

FEL Line

FEL-III

Photon energy/keV

Photon number per pulse @15keV

Max pulse repetition rate/MHz

Beam energy/GeV	8.0	4-8.6	FEL-I		
Bunch charge/pC	100	10-300	Photon energy/keV	3-15	3-15
Max rep-rate/MHz	1	up to 1	Photon number per pulse @12.4keV	>1010	>1011
Beam power/MW	0.8	0 - 2.4	Max pulse repetition rate/MHz	0.66	1
Photon energy/keV	0.4-25	0.4-25	FEL-II		
Pulse length/fs	20-50	5-200	Photon energy/keV	0.4-3	0.4-3
Peak brightness	5×10^{32}	$1 \times 10^{31} - 1 \times 10^{33}$	Photon number per pulse @1.24keV	>1012	>1013
Average brightness	5×10 ²⁵	$1 \times 10^{23} - 1 \times 10^{26}$	Max pulse repetition rate/MHz	0.66	1
					Harris and the second s

> XFEL Facility +100 PW Laser Facility

10-25

 $>10^{9}$

0.66


Nominal


Objective

10-25

 $>10^{10}$

Facility Layout of SXFEL





SHINE Beamlines and End-stations

FEL-I Hard X-ray End-stations

- HSS: Hard X-ray Scattering and Spectroscopy
- CDS: Coherent Diffraction Endstation for Single Molecules and Particles
- SEL: Station of Extreme Light
- > XFEL + 100 PW Laser System

FEL-II Soft X-ray End-stations

- AMO: Atomic, Molecular, and Optical Science
- SES: Spectrometer for Electronic Structure
- SSS: Soft X-ray Scattering and Spectroscopy


FEL-III Hard X-ray End-stations


- HXS: Hard X-ray Spectroscopy
- SFX: Serial Femtosecond Crystallography
- CDE: Coherent Diffraction Imaging
- HED: High Energy Density Science


R&Ds of Accelerator Key Technologies

Coherent FEL studies

Novel methods and techniques have been developed for extending the seeded FEL capabilities to shorter wavelength and higher repetition rate









Coherent FEL studies


➤ A series experiments for EEHG and EEHG-HGHG cascade has been performed for fully coherent soft X-ray FEL






Coherent FEL studies


➤ New methods and techniques have been proposed for the next generation light source: fully coherent, high rep-rate radiation based on storage ring.





Bunch by bunch 3D position measurement technology

- 1st Bunch by bunch precise 3D position measurement system built @ SSRF in the world
- Very powerful tools for machine study
 - Every individual bunch position can be tracked with resolution of 5um in transverse plane and 0.2ps in longitudinal plane
 - 3D trace of Refilled charge during injection can be extracted
- Open source data analyze package has been developed and release at GitHub, suitable for any other electron storage ring






FIG. 11. The evolution in energy phase space of an injected bunch after injection.


Insertion Devices for SSRF

- In-vacuum undulator
- Cryogenic permanent magnet undulator
- Superconducting wiggler
- Superconducting undulator



DEPU in SSRF







Apple knot undulator for SSRF-II



SCW for SSRF

CPMU for SSRF

Superconducting undulator for SSRF

Undulators for SXFEL and SHINE

- Short period period in-vacuum undulator for SXFEL
- Small gap undulator for SXFEL
- Elliptical polarized undulator for SXFEL
- Horizontal polarized undulator for SHINE
- Vertical polarized undulator
- Superconducting undulator for SHINE



4m H-polarization U68 undulator for SHINE



4m V-polarization U68 undulator for SHINE



4m superconducting V-polarization undulator for SHINE



IVU16 for SXFEL




U235 for SXFEL




EPU for SXFEL

RF accelerating structures

- C-band HG accelerating structure
- X-band accelerating structure
- S-band accelerating structure









C-band high gradient accelerating structure for SXFEL 37MV/m on average, 41.7MV/m on maximum



X-band accelerating structure for SXFEL linearizer





S-band accelerating structure for SXFEL and Sirius

RF pulse compressors

- C-band SLED pulse compressor for SXFEL
- X-band SLED pulse compressor for SXFEL
- S-band SLED pulse compressor for SXFEL
- C&X-band spherical pulse compressor
- Top-flat output controlled by LLRF




C-band SLED for SXFEL




S-band SLED for SXFEL

RF Mode of Spherical PC




Flat-top output





C&X-band spherical pulse compressor (PC)



Adaptive control LLRF for Flat-top output

Transverse deflecting systems (TDS)


- S-band TDS for bunch length (BL) diagnostics
- C-band TDS for bunch length (BL) diagnostics
- X-band TDS for BL, fs timing and FEL diagnostics



S-band TDS for SXFEL 10 MV deflecting voltage on maximum Beam energy is 250 MeV



C-band TDS for SXFEL 30 MV deflecting voltage on maximum Beam energy is 1500 MeV









X-band TDS for:

- 1. BL measurement
- 2. Beam-laser fs timing
- FEL diagnostics for two undulator lines

1.3GHz SRF Cryomodule for SHINE

- Cryomodule prototype: SHINE cryomodule design adopts the TESLA technology and refers to EXFEL and LCLS-II
 - 1.3GHz 9-cell cavity prototype: (1300.2 +/- 0.1)MHz, from BCP to EP and high-Q0 recipe. Eight BCP_ed cavities (Q0> 1E10 @ 16 MV/m) integrated to the first cryomodule.
 - Fundamental power coupler: double-window structure, 7.0 kW full reflection power ability
 - Cryostat: double-layer magnetic shielding (< 5 mGauss), thermal shielding, cryogenic pipes
 - Tuner: mechanical (450kHz) with piezo tuner (+/- 1kHz), 1Hz resolution
 - Cryomodule: first prototype assembled and cooldown to 2.0K, horizontal test system commissioned









Cavity & FPC


Clean Assembly ISO4

Cold mass


Cryomodule in tunnel


1.3GHz SRF Cryomodule for SHINE

- High-Q treatment recipe: three groups developed different high-Q0 recipe
 - IHEP: based on EP and Mid-T, fine grain 9-cell cavity
 - SARI: based on EP and high-Q0 recipe, fine grain single cavity
 - PKU: based on BCP&EP, N-doping, N-infusion and Mid-T, large grain/fine grain single cell cavity




- 6 FG 9-cell cavities, high Q achieved for Q0>3.5e10 @ Eacc=18 MV/m.
- Min gradient 24 MV/m.





high Q achieved for Q0>5.7e10 @ Eacc=16 MV/m



- LG3: Light doping N2 2min + A 6min
- Q0~4.1 e10 @16MV/m

500 MHz SRF cryomodule

Cryomodule Composition:

- SC niobium cavity;
- Fundamental power coupler;
- HOM damper;
- Tuner;
- Liquid helium cryostat.

Parameters	Technical Specification	
Working frequency	499.654 MHz	
Cavity voltage	1.5~2.0 MV	
Tuning bandwidth	\pm 150 kHz	
Cavity unloaded quality factor	$> 5.0 \times 10^8 $ @Vc = 2.0 MV	
External quality factor	$(1.5 \pm 0.3) \times 10^5$	
Module length	3045+/-5 mm	




Fig. The structure design of 500 MHz SC cryomodule



Fig. The 500 MHz SC cryomodule integration in the test tunnel






Fig. The Horizontal test results of 500 MHz SC cryomodule

Superconducting Third Harmonic Cavity

- The third harmonic SRF cryomodule was installed into tunnel and cooled down to 4.2 K, frequency detuned, with 200 mA beam;
 - ✓ One 2-cell cavity to provide high harmonic voltage up to 1.8 MV
 - √ Compact design to have a shorter cryomodule length, ~ 2.3 m
 - ✓ Lower loss factor of HOM by adopting fluted beam pipe
 - ✓ SiC HOM absorber and mechanical tuner & piezo tuner operated at room temperature.







Home-made Digital Instrument Development

- Digital BPM processors
 - 125MHz for SSRF and SXFEL
 - 1GHz for SHINE
- ps timing system
 - White Rabbit timing system for SXFEL and SHINE
 - Event system for SSRF and SAPT
- fs synchronization system
- LLRF control unit
- PS control unit



Event timing system



White rabbit timing system



125MHz DBPM for SXFEL and SSRF



1GHz DBPM for SHINE



LLRF controller for SSRF and SHINE



PS controller for SSRF and SHINE

CBPM technology


- CBPM technology had been investigated since 2014
- All key components, including C-band sensor, low noise RF front end and high sampling rate (1GHz)
 DBPM processor, have been designed and fabricated locally.
- Resolution of 300 nm has been achieved and satisfied SXFEL requirement
- Still fighting for 100 nm resolution required by SHINE












273 nm @ 500pC· \pm 300μm (SXFEL)



Summary

Summary

- ➤ For establishing a world-class photon science center at Shanghai, a cluster of accelerator based light sources had been developed.
- ➤ SSRF had been in operation since 2009 and 16 more beamlines will be added during SSRF-II project.
- ➤ Construction of SXFEL has been making progress, and the SXFEL is in the FEL commissioning stage, aiming at serving users in 2022;
- ➤ SHINE is a high rep-rate hard X-ray FEL facility, with an 8 GeV CW SCRF linac, a 100PW laser system, 3 phase-I undulator lines and 10 end-stations, is under development;
- ➤ Key technology R&D programs have been initiated to support all facilities construction.

