9th Internat iOG pue 'australian of the second sec **DESIGN AND STATUS OF THE MICROTCA.4 BASED LLRF SYSTEM FOR TARLA**

C. Gumus^{*}, M. Hierholzer, K. Przygoda, H. Schlarb, C. Schmidt, DESY, Hamburg, Germany A. Aksoy, A. Aydin, Ankara University, Ankara, Turkey

The Turkish Accelerator and Radiation Laboratory in cAnkara (TARLA) is constructing a 40 MeV Free Electron ELaser with continuous wave (CW) RF operation. In order to control and monitor the four superconducting (SC) PTESLA type cavities as well as the two normal conductging (NC) buncher cavities, a MicroTCA.4 based LLRF 5 system is foreseen. This highly modular system is further Eused to control the mechanical tuning of the SC cavities by control of piezo actuators and mechanical motor Etuners. This paper focuses on giving brief overview on hardware and software components of LLRF control of TARLA, as well as updates on the ongoing integration tests at DESY.

FACILITY INFORMATION

of this work TARLA facility - located in Ankara - will be the first particle accelerator of Turkey with the Free Electron ELaser (FEL) of 3–250 μ m. Other usages will be the Bremsstrahlung radiation and the fixed target experi-iments. The Technology Lab of DESY is responsible for idelivering a turn-key system for Low Level Radio Fre-Equency (LLRF) control to TARLA. There are six cavities that need to be controlled by LLRF system. Four of these cavities are TESLA type 1.3 GHz superconducting whereas others are normal conducting buncher cavities operating with 1.3 GHz and 260 MHz respectively. The RF operation will be continuous wave (CW) with the ex-Srameters are on Table 1.

BY Apart from the hardware delivery and the commission-Using of the complete system, DESY is also cooperating with TARLA to train personnel in order to make sure that Eknow-how is transferred.

terms Main design of the accelerator is quite similar to the BELBE in HZDR-Dresden / Germany where difference is 5 that TARLA uses piezos on SC cavities. Since ELBE is Ealso in the process of switching their control system to MicroTCA.4 standard, parallel development is ongoing [1]. The main construction on TARLA facility has been ٩ finished and accelerator modules have been delivered.

* cagil.guemues@desy.de

Parameter	Unit	Base Value	Upgraded Value
Beam Energy	MeV	0 - 40	0 - 40
Max. Bunch Charge	pC	77	115
Max. Average Beam Current	mA	1	1.5
Horizantal Emittance	mm mrad	<15	<15
Vertical Emittance	mm mrad	<12	<12
Longitudinal Emittance	keV ps	<85	<85
Bunch Length	ps	0.4 - 6	0.3 - 6
Bunch Repetition	MHz	13	0.001 - 52
Macro Pulse Duration	μs	10 – CW	10 – CW

Table 1: Machine and Beam Parameters

LLRF DESIGN

1 - CW

1 - CW

Hz

Overview

Macro Pulse

Repetition

The overall LLRF system consists of 6 RF station controls and the corresponding mechanical tuner control components. In additional to RF and mechanical tuning of the cavities, additional drift compensation modules (DCM) will be installed to compensate the slow drifts on RF signal paths caused by humidity and temperature. The RF amplification after the LLRF system is realized by Solid State Power Amplifiers (SSPA). As for the control system environment, EPICS will be used on the LLRF system.

Using the MicroTCA.4 technology standard, each cavity is controlled by one Advanced Mezzanine Card (AMC) and Rear Transition Module (RTM) pair. The AMC with a FPGA, contains the control loop and PCIe component while the RTM has mostly the analog part of the signal path. Each AMC + RTM pair is connected to a CPU-AMC card to transfer data over the MicroTCA backplane using PCIe bus [2].

The synchronization of all LLRF controls is realized by applying the same main clock and reference signals generated by a Master Oscillator (MO).

07 Accelerator Technology

Mechanical tuning of the cavities is done via stepper motors. Moreover, SC cavities are also equipped with piezos which will be controlled by PZT4 RTM.

All the LLRF components and their spare parts will be housed in one single rack, shown in Figure 2. with inter rack cabling and custom top patch panel for connecting RF signals, motor cabling, IT connections etc. Furthermore this rack also houses the master oscillator which allows for an optimal connection of the LLRF system to the master clock.

Crate Layout

Foreseen crate occupation can be seen on Figure 1. Apart from crate management board (MCH) and power supply, main crate components are listed below. The further information on listed hardware can be found in [3].

- CPU-AMC: from Concurrent Technologies, Runs on Ubuntu 16.04 LTS contains all servers for operation
- DAMC-SIS8300L2: Digitizer board from Struck (10 Channel 125 MS/s 16 bit)
- DAMC-x2Timer: Main timing board used to synchronize LLRF system
- DRTM-DWC8VM1: Down conversion from 1.3 GHz to 54 MHz intermediate frequency.
- DRTM-DS8VM1: Direct sampling board used for 260 MHz buncher cavity
- FMC25-AMC: FMC Carrier Board having MD22 Motor control card
- PZT4-RTM: Piezo Control RTM



Figure 1: TARLA Main Crate Occupation

Current Schedule and Rack Layout

All the hardware components will be delivered to DESY site for initial tests. After the system integration one rack containing all the hardware with the cabling will be shipped to TARLA around Q2 of 2019. Currently complete system integration is taking place at DESY.

This includes hardware tests of the individual components, firmware design for the LLRF controls, server deployment etc.

It is also intended to ship the spare crate before hand around Q3 of 2018 to pre-test the system on site in order to identify challenges before main rack is shipped. This spare crate will be used to commission the NC buncher cavities.

During the system integration, additional proof of concept setups is being constructed at Cryo Module Test-Bench (CMTB) facility at DESY. These setups are mostly for testing the piezo operation using PZT4 and CW-RF operation tests with 1.3 GHz TESLA type cavities [4].

Once the hardware is shipped next stage will be functionality and performance demonstration on site. Acceptance is done for a set of default machine operation parameters. Finally, several upgrades to the system like beam position monitors, beam based feedbacks is planned.



Figure 2: TARLA Rack (Front View)

Figure 2 shows the TARLA Rack with most of the hardware installed. Main components are two crates with one being the main and other as spare. Local Oscillator

07 Accelerator Technology

T31 Subsystems, Technology and Components, Other

9th International Particle Accelerator Conference ISBN: 978-3-95450-184-7

a Generation Module (LOGM) is responsible from dis-Etributing the 1354 MHz LO, to DWC8VM1 RTM boards for down conversion to 54 MHz. There will be a custom apatch panel for routing the RF, interlock and IT signals at Afthe top of the rack.

EPICS INTEGRATION

of the TARLA is using EPICS Control System on site. This Brequires that all the servers that are running on the crate must be interfaced to EPICS to have common ground. This interfacing is possible with the ChimeraTK frame-

to the ChimeraTK Framework

In order to access the data from the MicroTCA.4 crate bidirectionally over PCIe bus, the ChimeraTK framework was developed in DESY. The scope of this framework fo-Ecuses on abstracting specifics of underlying system as well as giving user the ability to create portable user ap-plications across different control system choices [5].



Ferent control systems such as EPICS, DOOCS, OPC-UA Setc. This gives ability to re-use the LLRF server written for one facility at another facility with completely differ-Sent control system. Same LLRF server written for TARLA is currently used in ELBE.

All the LLRF servers as well as watchdog running runthe ining on MicroTCA.4 system, are developed using getested at the DESY site. First successful close loop LLRF goperation on dummy load using the MicroTCA.4 crate ChimeraTK framework. Currently these servers are being

with the LLRF server written on ChimeraTK framework has been demonstrated.

The graphical user interface for control panels developed using Control System Studio (CSS). Figure 3. shows the first LLRF expert panels designed with CSS. Features such as logbook entry, history of PVs, user login will be added to the interface.

CONCLUSION

The Technology Lab of DESY will be delivering a turn -key LLRF system to TARLA to monitor and control 4 SC cavities and 2 NC buncher cavities. Additional control for the mechanical tuning of the cavities will also be part of the system. The LLRF control electronics is based on the MicroTCA.4 technology standard where each cavity controlled with one AMC + RTM pair.

Currently, the system integration is taking place at DESY site. This includes hardware test, software and firmware design and complete system integration. Since TARLA is using EPICS as the control system, server integration using ChimeraTK framework is currently ongoing. The LLRF expert panels have been designed and successfully interfaced to LLRF servers. All electronics housed in a single rack, will be shipped to TARLA around Q2 of 2019.

REFERENCES

- [1] M. Kuntzsch et al., "MicroTCA.4-Based LLRF for the Superconducting CW LINAC ELBE- Status And Outlook" in LLRF Workshop 2017, Barcelona, Spain 16-19 October 2017, p.4
- [2] PICMG Micro Telecommunications Computing Architecture Short Form Specification https://www.picmg.org/
- [3] MicroTCA Technology Lab, https://techlab.desy.de/products/
- [4] K. Przygoda, et al., "MicroTCA.4 Based Single Cavity Regulation Including Piezo Controls" 7th International Particle Accelerator Conference, Busan, Korea, 8-13 May 2016
- [5] G. Varghese et al., "CHIMERATK A Software Tool Kit for Control Applications" in 8th International Particle Accelerator Conference, Copenhagen, Denmark, 14-19 May 2017

Content from this work may WEPMF054 2492