

Operation Status and Upgrade of CSNS

Shinian Fu, Sheng Wang

China Spallation Neutron Source
Institute of High Energy Physics, CAS



Outline


- Project Overview
- Accelerator Commissioning
- User Operation
- Upgrade Plan
- Summary

1, Project Overview

Project Design



- The phase-I CSNS facility consists of an 80-MeV H^- linac, a 1.6-GeV rapid cycling synchrotron(RCS), beam transport lines, a target station, and 3 instruments.

Project Phase	I	II
Beam Power on target [kW]	100	500
Proton energy [GeV]	1.6	1.6
Average beam current [μA]	62.5	312.5
Pulse repetition rate [Hz]	25	25
Linac energy [MeV]	80	300
Linac type	DTL	+SC
Linac RF frequency [MHz]	324	324
Macropulse. ave current [mA]	15	40
Macropulse duty factor	1.0	1.7
RCS circumference [m]	228	228
RCS harmonic number	2	2
RCS Acceptance [$\pi mm\text{-}mrad$]	540	540
Target	1	1
Spectrometers	3	20



The first high-energy high-intensity proton accelerator in China

H⁻ Linac Design






EMQ option in FFDD lattice for DTL

Electrostatic chopper in LEBT


	Ion Source	RFQ	DTL
Input Energy (MeV)		0.05	3.0
Output Energy(MeV)	0.05	3.0	80
Pulse Current (mA)	20/40	15/30	15/30
RF frequency (MHz)		324	324
Chop rate (%)		50	50
Duty factor (%)	1.3	1.05	1.05
Repetition rate (Hz)	25	25	25

Linac installed in the tunnel



RCS Design

- Lattice of 4-fold symmetry, triplet.
- 227.92m circumference.
- Four long straight sections for injection, acceleration, collimation and extraction.
- 24 main dipoles with one power supply.
- 48 main quadrupoles with 5 power supplies.
- Ceramic vacuum chambers for the AC&pulsed magnets.
- 8 RF ferrite loaded cavities to provide 165 kV.





Dipole magnet



Quadrupole and Extraction magnet



Ring RF



Collimator



Central control




Power supply for magnet

Blue: constructed 3

Red: Near future instruments 7


Green: CSNS upgrade project 10



Decoupled & Poisoned Hydrogen Moderator (20K)

Coupled Hydrogen Moderator (20K)


Decoupled water moderator (300K), plan change to Decoupled Hydrogen (20K)




Target Station



Scattering Halls



Key Milestones (on schedule)



Budget and Expenditure (within budget)

- The total budget approved is 1.86632 B RMB (268M US\$), actual investment is 1.8740665 B RMB (268.7M US\$)
- The expenditure of the equipment's is within the budget
- The deficit of the civil construction is paid by the local governments

NO.	Systems	Approved Budget (Million RMB)	Actual Investment (Million RMB)
1	Accelerator	62,664.66	62,362.90
2	Target and Instrument	39,763.04	41,161.86
3	Utilities	21,853.81	24,914.20
4	Others	62,350.49	58,967.69
Total		186,632	187,406.65

2, Accelerator Commissioning

Beam commissioning in 2017

- ✧ 1 of 4 DTL klystrons was not available in 2017.
- ✧ RCS was commissioned with 60MeV linac beam from 3 DTL tanks.
- ✧ It took 67 days to reach the beam power of 10kW.

Linac
(10 days)

2017.04.15~04.2

RCS/DC
(10 days)

2017.05.26~06.0

RCS/AC
(13 days)

2017.06.30~07.1

RCS/DC
(8 days)

2017.07.13~07.2

RCS/AC
(8 days)

2017.07.21~07.2

RCS/AC
(18 days)

2017.08.11~08.

First beam
on target, first
neutron beam

2017.08.28

Increase beam
power to 10 kW

2017.11.01~11.09

Beam commissioning in 2018

- ✧ In the beginning of 2018, 4 DTL tanks were available and the beam commissioning were resumed.
- ✧ It took 18 days to recover the beam power to 10kW with 80MeV linac beam.
- ✧ From the Jan. 22, the beam was delivered to target for neutron spectrometers commissioning and user operation
- ✧ By mid-March, the beam power is increased to about 25kW.

Time table of commissioning in 2018:


- ✓ Jan. 4~13 Linac to 80MeV
- ✓ Jan. 14~17 RCS/DC
- ✓ Jan. 18~21 RCS/AC
- ✓ Jan. 22~ Commissioning of instruments and user operation
- ✓ March Beam power increased to ~25kW

■ Frontend beam commissioning

- From low duty to high duty: 50 $\rightarrow$ 500 μ s, 1 $\rightarrow$ 25 Hz
(chop rate: 0 $\rightarrow$ 50 %).
- Then, 90 hours continuous operation @25Hz, 500 μ s, 50% chop rate.
- **Best transmission rate for RFQ: 94%。**



	Design	Measured
Ion source current [mA]	20	31
MEBT Peak current [mA]	15	17
MEBT Beam energy[MeV]	3.0258	3.02 ± 0.015
Chopping rate [%]	50	50
Pulse width [μ s]	420	500
Pulse repetition rate [Hz]	25	25
Emittance (π mm mrad)	0.22	0.27




■ DTL tanks

- DTL 1-3 : Apr. 2017, Tank-3 output 15mA beam @60MeV.
- DTL 4: Jan. 2018, 80MeV beam.

	Measured (MeV)	Designed (MeV)
DTL1	21.81	21.67
DTL2	41.67	41.41
DTL3	60.80	61.10
DTL4	80.57	80.09

CT Display				2018-02-01 14:10:51
LEBT CT01	27.59	mA	LEBT Trans	70.3 %
LEBT CT02	19.39	mA	MEBT Trans	99.4 %
MEBT CT01	16.19	mA	RFQ Trans	83.5 %
MEBT CT02	16.10	mA	DTL1 Trans	98.3 %
DTL CT01	15.83	mA	DTL2 Trans	99.6 %
DTL CT02	15.77	mA	DTL3 Trans	98.1 %
DTL CT03	15.47	mA	DTL4 Trans	100.3 %
LRBT CT01	15.51	mA	DTL Trans	96.4 %



能量计算

LEBT&DTL MEBTCTmin 0 MEBTCTmax 4 数值范围0-4, 分别代表 MEBTCT01-MEBTCT05

Energy>Select3 LRCTmin 3 LRCTmax 7 数值范围0-7, 分别代表 DTLCT01-03, LRCT01-LR-CT05

调整间隔 0

计算能量值 80.364111 MeV


能量计算说明:
首先, 选择需要计算的腔体编号, 左上角的布局用于选择MEBT腔体或LRBT&DTL腔体的能量, 即为MEBT、腔体LRBT&DTL
其次, Energy>Select腔体编号为0-3, 一次代表20MeV、40MeV、60MeV、80MeV, 该选项仅对LRBT&DTL腔体起作用
再次, 根据需要进行设置调整间隔数

■ RCS——storage mode (DC)


MOPTS068/Shou-Yan Xu

WEPRB040/Xiao Li

- For controlling beam loss, we started RCS operation with storage mode at single shot.
- June 2017, the storage beam was firstly extracted from the ring.




Beam transmission rate higher than 98% through the




Measured signal of the extracted beam

■ RCS accelerating mode (AC)



July 2017 RCS started AC mode: the first shot of beam survive only for 4ms, not reaching the final energy.





On the same day, beam was accelerated to 1.6GeV design energy. And soon transmission rate reached almost 100%

■ First beam on target on schedule

- August 2017 the first proton beam hit on the target and produced spallation neutrons. This a important milestone for CSNS project.

- Beam commissioning confirms a good performance in design, manufacture and commissioning.



Design Goal (Sept. 2011)

Beam power	Rep. rate	Ave. Curr.	Beam Energy	Neutron Effi.	Neutron Flux
100 kW	25 Hz	63 μ A	1.6 GeV	0.1 (n/p/sr)	2×10^7

- Keep the potential of upgrading beam power to 500kW.
- **1/10 beam power** is required for acceptance, and the design goal will be met in 3 more years.

Achieved in Acceptance (Aug. 2018)  **All achieved or exceeded**

Beam power	Rep. rate	Ave. Curr.	Beam Energy	Neutron Effi.	Neutron Flux
10 kW	25Hz	6.3 μ A	1.6GeV	0.005(n/p/sr)	10^5
23 kW	25Hz	14.5 μ A	1.6GeV	0.125	2.5×10^6

CSNS Passed State Acceptance on Aug. 23 2018


The review committee agreed that the performance of the CSNS has **reached or is even better than the planned acceptance goal**. The highest neutron efficiency of the target station and the three initial instruments reached the international level.

The review committee concluded that some significant innovative technologies in accelerators, target station and instruments were achieved at CSNS.




3, User Operation

CSNS commissioning and operation overview




Operation statistics (until now)



Availability is 80%

Operation statistics (from last summ. maint. to now)



Availability is 91%


Operation in 2018 (2800 Hours for user)

Fault of RFQ RF source
(4616 tetrode)


Spark of RFQ cavity
& DTL RF source

Operation with high
availability

2018/01/22 00:00:00 - 2018/10/31 08:00:00




High availability after summer maintenance




With accumulation of the operation experience, the availability of accelerator was quickly increased. After the summer maintenance, the availability is above 94%.

Downtime statistics (up to now)




Downtime statistics (from last summ. Maint. to now)




Problem of RFQ spark

TUPTS038/H.F.OUYANG

- The chopped beam lost in the vane of RFQ, is confirmed to be the reason of RFQ spark
- By rotating the chopper 45 degrees, most of the chopped beam passed through the slit between to adjacent vanes.




RFQ vane at entrance



Upgrade the RF source of RFQ

- The stability of the RFQ 4616 tetrode is one of the main cause of fault.
- The short lifetime and price of 4616 tetrode.
- The retired klystron from DTL, can be used for RFQ, zero cost.





Broken of the Quadrupole coil

- High voltage discharges had caused insulation failures of one RCS-272Q quadrupole magnet due to short distance between the magnet coil and its U-type fixture.
- To avoid the similar failure, all the U-type fixtures of the quadrupole magnets were replaced by the new ones with increased insulation distance.




Water leakage in RTBT tunnel

Water Leakage alarm appeared in the RTBT interface during the operation. By using the endoscope, it was found that a ceramic water pipe of the quadrupole was broken, and was replaced.



Leakage position



Leakage detection
Page

Problem of RTBT DC Power Supply

TUPMP023/Jun Li


- For these PS, we use the same power module constructed through serial or parallel connection. The single module outputs is 400A/35V (14KW).
- There are total 140 modules, 37 sets .
- Because of high power density and strict processing technology, power supply has found some problems in mass production. It took lots of time to resolve these problems.



Tunnel robot

WEPGW046/Ling Kang

- A “tunnel robot” was developed as a platform for auxiliary maintenance and measuring. It can move by recognizing the QR codes in the floor, and can carry the manipulator and alignment instrument works in the tunnel.
- It conducted the vibration measurement of the magnets and vacuum pipes



Plan for operation schedule for the first half of 2019


>3600 hours for user in all year

Plan T	Plan M	Plan A	Plan D	Plan W
3000hrs	624hrs	504hrs	168hrs	48hrs

Jan			Feb			Mar			Apr			May			Jun		
TUE 1	T	T	FRI 1	T	T	FRI 1	T	T	MON 1	A	A	WED 1	T	T	SAT 1	T	T
WED 2	T	T	SAT 2	T	T	SAT 2	T	T	TUE 2	A	A	THU 2	T	T	SUB 2	T	T
THU 3	T	T	SUN 3	D	D	SUN 3	T	T	WED 3	A	A	FRI 3	T	T	MON 3	M	M
FRI 4	T	T	MON 4	D	D	MON 4	M	M	THU 4	A	A	SAT 4	T	T	TUE 4	T	T
SAT 5	T	T	TUE 5	D	D	TUE 5	T	T	FRI 5	A	A	SUN 5	T	T	WED 5	T	T
SUN 6	T	T	WED 6	D	D	WED 6	T	T	SAT 6	A	A	MON 6	M	M	THU 6	T	T
MON 7	M	M	THU 7	D	D	THU 7	T	T	SUN 7	A	A	TUE 7	T	T	FRI 7	T	T
TUE 8	T	T	FRI 8	D	D	FRI 8	T	T	MON 8	T	T	WED 8	T	T	SAT 8	T	T
WED 9	T	T	SAT 9	D	D	SAT 9	T	T	TUE 9	T	T	THU 9	T	T	SUN 9	T	T
THU 10	T	T	SUN 10	W	W	SUN 10	T	T	WED 10	T	T	FRI 10	T	T	MON 10	M	M
FRI 11	T	T	MON 11	W	W	MON 11	M	M	THU 11	T	T	SAT 11	T	T	TUE 11	T	T
SAT 12	T	T	TUE 12	T	T	TUE 12	T	T	FRI 12	T	T	SUN 12	T	T	WED 12	T	T
SUN 13	T	T	WED 13	T	T	WED 13	T	T	SAT 13	T	T	MON 13	M	M	THU 13	T	T
MON 14	M	M	THU 14	T	T	THU 14	T	T	SUN 14	T	T	TUE 14	T	T	FRI 14	T	T
TUE 15	T	T	FRI 15	T	T	FRI 15	T	T	MON 15	M	M	WED 15	T	T	SAT 15	T	T
WED 16	T	T	SAT 16	T	T	SAT 16	T	T	TUE 16	T	T	THU 16	T	T	SUN 16	T	T
THU 17	T	T	SUN 17	T	T	SUN 17	T	T	WED 17	T	T	FRI 17	T	T	MON 17	M	M
FRI 18	T	T	MON 18	M	M	MON 18	A	A	THU 18	T	T	SAT 18	T	T	TUE 18	T	T
SAT 19	T	T	TUE 19	T	T	TUE 19	A	A	FRI 19	T	T	SUN 19	T	T	WED 19	T	T
SUN 20	T	T	WED 20	T	T	WED 20	A	A	SAT 20	T	T	MON 20	M	M	THU 20	T	T
MON 21	M	M	THU 21	T	T	THU 21	A	A	SUN 21	T	T	TUE 21	T	T	FRI 21	T	T
TUE 22	T	T	FRI 22	T	T	FRI 22	A	A	MON 22	M	M	WED 22	T	T	SAT 22	T	T
WED 23	T	T	SAT 23	T	T	SAT 23	A	A	TUE 23	T	T	THU 23	T	T	SUN 23	T	T
THU 24	T	T	SUN 24	T	T	SUN 24	A	A	WED 24	T	T	FRI 24	T	T	MON 24	M	M
FRI 25	T	T	MON 25	M	M	MON 25	A	A	THU 25	T	T	SAT 25	T	T	TUE 25	M	M
SAT 26	T	T	TUE 26	M	M	TUE 26	A	A	FRI 26	T	T	SUN 26	T	T	WED 26	M	M
SUN 27	T	T	WED 27	M	M	WED 27	A	A	SAT 27	T	T	MON 27	M	M	THU 27	T	T
MON 28	M	M	THU 28	T	T	THU 28	A	A	SUN 28	T	T	TUE 28	M	M	FRI 28	T	T
TUE 29	T	T				FRI 29	A	A	MON 29	M	M	WED 29	M	M	SAT 29	T	T
WED 30	T	T				SAT 30	A	A	TUE 30	M	M	THU 30	T	T	SUN 30	T	T
THU 31	T	T				SUN 31	A	A				FRI 31	T	T			
Jan			Feb			Mar			Apr			May			Jun		

T	Target
M	Maintenance
A	Machine Study
D	Shut Down
W	Warm Up


4, Upgrade Plan




Phase-I status and **phase-II upgrade**

Layout of the CSNS Linac in Phase-II

Option1:



Option2:



Similar SC Cavities Developed at IHEP for ADS

	Cavity type	Freq. (MHz)	β_g	Energy (MeV)	Max. Vacc. (MV)
Injector I	Spoke012	325	0.12	3.2-10	0.82
Main Linac	Spoke021	325	0.21	10-34	1.32
	Spoke040	325	0.40	34-178	2.79
	Elliptical063	650	0.63	178-367	7.68
	Elliptical082	650	0.82	367-1500	15.47



RCS upgrade tasks

TUPTS048/Wang Sheng

- ✧ Secondary harmonic MA loaded cavities
- ✧ New injection system
- ✧ Upgrade of part of AC power supply
- ✧ Some new beam instruments, upon the experiences of present beam commissioning
- ✧ Magnetic field measurement for AC mode with different injection energy: 250,300,350,400MeV
- ✧ Beam dynamics studies, upon present commissioning


MA Loaded Cavity for RCS as 2nd -harmonic buncher

- **Present ferrite loaded cavity**

- Length: 2.7m
- RF voltage: 27kV

- **New Secondary MA cavity**



- Length: 1.8m
- RF voltage: 36kV



We are lack of experiences of development of high power MA loaded cavity in China.

Domestic MA strips development

WEPRB051/Wu Bin



Prototype measurement results indicate the domestic products are comparable with Japanese products.

Summary

- CSNS construction finished successfully **within budget and on time**.
- Accelerator beam commissioning has been completed with a good results.
- We reached **50kW** beam power on target for user operation with availability higher than 90%.
- CSNS started user operation and meanwhile will gradually raise beam power to 100kW.
- **500kW** upgrade is under planning, and the upgrade project is foreseen to be launched as long as we realize 100kW.

THANK YOU!

