

National Synchrotron Light Source II

Experience of the first six years operations and plan in NSLS-II



*Guimei Wang for the NSLS-II team
National Synchrotron Light Source II
Brookhaven National Lab
IPAC21, May 24-28, 2021, Campinas, Brazil*



U.S. DEPARTMENT OF
ENERGY


Office of
Science

BROOKHAVEN
NATIONAL LABORATORY


Poster: MOPAB079

National Synchrotron Light Source II

- NSLS-II is a 3 GeV, 500 mA, high-brightness light source, funded by U.S. Department of Energy (DOE), at the Brookhaven National Laboratory
- One of the newest and most advanced synchrotron facilities in the world.
 - wide spectral range: IR to hard x-ray
 - high average spectral brightness
 - high flux density
 - >60 beamlines
- CD-0 was approved in 2005
- CD-3 was approved in 2009
- SR commissioning started in Mar. 2014
- In Feb. 2015, CD-4, the final milestone of the project, completed
- Total cost is \$912 Million
- 28 beamlines in top off operation at 400 mA
- Oct. 2019, demonstrated 500 mA beam current
- May. 2021, 3rd RF cavity in operation




NSLS-II: 6 years operations




- Commissioned 29 IDs sources (10 IVUs, 6 EPU, 6 DWs, 5 3PWs, 1 BM and 1 PU)
- High reliability has been maintained while we steadily increased beam current & IDs
- Normal operation with 2 cavities limits our performance (max 400 mA)
- Forced to decrease ops current to 220 mA due to the failure of one cavity in Apr. 2019

Yearly Statistics by subsystems


Downtime FY17 (hr)



Downtime FY18 (hr)



Downtime FY19* (hr)



- | | | | |
|------------------|----------------|-------------|--------------|
| Controls | Cryo | Diagnostics | EPS |
| Ops/Other/Unsure | Power Supplies | PPS | Beamline PPS |
| Utilities | Vacuum | Power Dins | Mechanical |


Main contributors of machine downtime are from utility, PS, cryo plant, RF, PPS and ID

- RF: in 2018 ran at a lower voltage to avoid frequent trips due to vacuum leak
 - Lost RF cavity C in 2019 → 3.5 months of operations at 220 mA
- Cryo Plant: cold box warm up ~monthly after burst disc event in June 2017
- Power Supplies: majority of FY18 downtime due to single booster PS event, frequent kicker failures
- ✓ Utilities: cooling water quality caused an increase in ground current faults and trips due to magnet overheating, required ~5 hrs to flush
- ✓ PPS: developing control system diagnostics to record and identify root causes, door switches replaced
- ✓ ID: sheared cooling water line in the C3 IVU when a drive shaft connecting 2 halves broke

Fast Orbit Feedback improvement



- Stage-to-stage latency characterization
- Improved corrector PS bandwidth from 3/1 kHz to 6.3 /4.1kHz (H/V)
- Removed BPMs extra 100us delay in firmware
- FOFB loop total latency: 250 μ s
- Bandwidth of the FOFB system increase from 250 Hz to 400 Hz/300 Hz (H/V)
- The orbit beam instability improved by 30%/10% (H/V)
- Typical ID source position/angle integrated motion [1-500 Hz]: 0.6% (H) and 7% (V)
- Long term stability: local bump feedback on ID BPM/xBPM interact with FOFB to reach μ m

FOFB stage-to-stage latency and improvements



NSLS-II: Sukho Kongtawong


ID source position stability feedback ON/OFF




Sukho Kongtawong, Recent improvements in beam orbit feedback at NSLS-II, NIMA 976 (2020) 164250

Low vertical beam emittance

- 8 pm diffraction vertical emittance: using skew quads to control coupling (Yongjun)
- Low emittance study and operation
 - Dedicated low emittance study (Mar. 2017)
 - 8 pm operation at 275 mA and 375 mA (Mar. 2017, July 2018).
 - Survey among beamlines of low emittance operation.
 - HXN: observed 25% increase (VS model 45%) in peak intensity
 - CHX: Interference patterns show a significant increase in the visibility/contrast with the reduced emittance



- ID coupling correction
 - Some ID Gap change affects V emittance dramatically and beam lifetime
 - Developed coupling lookup function with 15 skew quads (Yoshi)
 - Maintain beam emittance at the pin-hole camera very well (w/o: 7.0-7.2 pm/7.1-11.4 pm)
 - Installed dedicated SQ at C17 AMX in May 2017




Path to high current: Ceramic chambers

- SR ceramic chambers: 4 fast kickers for beam injection (critical) and 1 pinger for beam dynamics studies
- Require Titanium coating 2 μm thickness over the entire inner surface with $\pm 10\%$ uniformity

Issues

- Observed heating and vacuum activity during first high current studies in Feb. 2016
- Kicker chamber 2 reached $> 100^\circ\text{C}$ @ 400mA. Discovered Titanium coating flaked off and chamber discolored
- Due to limited space, RTDs were installed at the end of chambers to monitor temperature
- High uneven localized heating or abrupt temperature changes
- Chamber failure can cause two days downtime

2016: Ceramic chamber temperature



Damaged Kicker 2 chamber




Path to high current: Ceramic chambers (CONT.)

Improvements


- Replaced damaged kicker chamber
- Installed cooling system
- Replaced RF springs between flanges and bellows
- Installed IR camera to monitor heat distribution
- Procured 5 new ceramic chambers and applied Titanium coating in-house. Installed three chambers in May. 2017-Sep. 2018
- Ceramic Temperature reduced to ~ 40 °C @400 mA

In-house coating development

- DC magnetron sputtering
- Central anode to initiate discharge
- Integrated thickness monitor
- New coating method successfully improved ceramic chamber thermal performance in operations



2019: Ceramic chamber temp.



Path to high current: RF springs

- 770 RF Springs installed in Storage Ring

Issues

- Certain temp. sensors indicated temperature $> 80^{\circ}\text{C}$
- Improper RF spring installation caused trapped mode heating
- Temp. sensors installed at discrete locations do not show all hot spots

Improvements

- In-situ thermal survey: discovered that majority of heated flanges were located at straight sections
- Installed IR cameras to monitor heat distribution
- Developed new RF spring installation procedure
- Replaced 39 RF springs since 2017 to reduce heating
- Install 770 1-wire sensors at flanges

Improper installation of RF springs


[0.4mm] [2.2mm]




C16 temp. with IR camera



Before: with RF springs improperly installed



After: RF spring installed properly



Systems required to reach 500 mA, 8 pm-rad in operation

- Based on our recent commissioning / operating experience further progress is limited

Limitations

Overheating of chambers

Stress on injector

Redundancy against an RF cavity loss

Operating modes
150 mA, 2RF, 7 beamlines AS IN FY15
400 mA, 2RF, no THC, 30 pm rad TODAY
500 mA, 3RF, no THC, 8 pm rad TODAY
500 mA, 3RF, no THC, 8 pm rad + HEX + MIE
500 mA, 4RF, THC , 8 pm rad + HEX + MIE

I_{ave}^2 A ²
4.5
12.0
19.8
20.0
7.8

Q/shot nC
2.0
7.5
9.4
9.4
8.0

I limit, mA if 1RFC failed
150
220
450
370
500

Conclusions

- Need Third Harmonic Cavity (THC) for any performance beyond today's
- For full performance and expected beamline suite need THC + 4th RF system


Systems required to reach 500 mA, 8 pm-rad in operation (CONT.)

4RF system: supply power loss of all ops IDs + new (HEX, MIE) @500 mA (Refer to Jim's talk)


Third Harmonic Cavity (THC): bunch lengthen

- Increase bunch length by a factor of 2 including gap fill and bunch lengthen effect (3.5 for ideal case)
- Lower heating
 - Power loss lower by a factor of 2.8
 - The ceramic chamber and bellows temp. will reduce with THC
 - Can handle 600 mA heating with predicted temperature upto 70 °C

Bunch length and lifetime w/o HC



Heating w/ and w/o THC



Summary and outlook

- Achieved 400 mA top off routine operation
- Provided 5000 hrs operations with 97% reliability for 28 beamlines
- Achieved designed beam emittance, $\epsilon_x = 0.9$ nm-rad and $\epsilon_y = 8$ pm-rad
- FOFB system was improved to large bandwidth 400/300 Hz and reach 0.6% (H) and 7% (V) beam size
- Demonstrate beam current 500 mA. Improvements include in-house ceramic coating, RF spring installation correction and 100s new temp. sensors added to monitor vacuum components heating
- 3rd RF cavity was installed in Apr. 2021 and is operating at 400 mA now
- To reach 500 mA, 8 pm reliable operation, 4 RF systems to support all IDs during operation and third harmonic cavity

Acknowledgements

- Accelerator division director: T. Shaftan
- Accelerator Coordination: G.M. Wang, J. Choi, Y. Hidaka, R. Smith, B. Wahl
- Accelerator Physics: V. Smalyuk, G. Bassi, X. Yang, Y. Li, L.H. Yu
- Beam Operations group: E. Zitvogel, R. Filler, T. Summers, M. Santana, G. Weiner, E. Zeitler, R. Rayner, C. Gardner, P. Marino...
- RF group: J. Rose, F. Gao, J. Cuppolo, J. Culpin, B. Holub, C. Marques...
- ID group: T. Tanabe, J. Rank...
- Vacuum group: C. Hetzel...
- Diagnostics and Instrumentation group: D. Padrazo, B. Bacha, B. Kosciuk, J. Mead
- Electrical Engineering: G. Ganetis, S. Buda, A. Castablanco, D. Oldham, W. Louie
- Controls: Y. Tian, K. Schroff, Y. Hu, K. Ha
- Mechanical Engineering group: L. Doom, S. Sharma, M. Loftus, A. Hussein, C. Spataro, F. Karl...