




IPAC'22, Bangkok, Thailand, June 12-17, 2022



High intensity ion beam accelerator facilities HIAF and CiADS status and demonstration of key technologies

Hongwei Zhao

On behalf of HIAF&CiADS team

**Institute of Modern Physics (IMP),
Chinese Academy of Sciences, Lanzhou, China**



OUTLINE

- **Brief introduction and construction status of HIAF & CiADS**
- **Key technology R&D and demonstration**
 1. High-intensity highly-charged heavy ion beam production
 2. Fast ramping power supply with full energy storage
 3. Magnetic alloy core loaded RF system
 4. 17-20 MeV/CW 5-10 mA front-end demo-facility of proton SC linac **for CiADS**
- **Summary and conclusion**

} **for HIAF**




HIAF&CiADS brief introduction

- **HIAF:** High Intensity heavy ion Accelerator Facility
- **CiADS:** China Initiative Accelerator Driven System
- Being built by IMP in Huizhou of Guangdong Prov.
- Two of 16 large-scale scientific infrastructure facilities approved by China Government during the 12th 5-year-plan 2016-2020

- **HIAF:** Nuclear physics research
- **Total budget:** 2.8 B CNY ¥ (424 M USD \$)
- **Schedule:** 2018-2025
- Construction started officially Dec. 2018

- **CiADS:** Nuclear waste transmutation
- **Total budget:** 4.0 B CNY ¥ (606 M USD \$)
- **Schedule:** 2021-2027
- Construction started officially July. 2021






HIAF layout and parameters


External target station

Nuclear Matter
Hyper-nuclear
High-E irradiation



HIAF key parameters

	SECR	iLinac	BRing	HFRS	SRing
Energy (MeV/u)	0.014 (U ³⁵⁺)	17 (U ³⁵⁺)	835 (U ³⁵⁺)	800 (U ⁹²⁺)	800 (U ⁹²⁺)
Intensity	50 pμA (U ³⁵⁺)	28 pμA (U ³⁵⁺)	2×10 ¹¹ ppp (U ³⁵⁺)	-----	10 ¹⁰ ppp (U ⁹²⁺)
Operation mode	DC	CW or pulse	fast ramping 12T/s 3Hz	Momentum -resolution 1100	DC, deceleration
Emittance or Acceptance π·mm·mrad dp/p		5 / 5	200/100 0.5%	±30/±15 ±2%	40/40 1.5%



iLinac:
Superconducting linac injector



HIAF technical challenge

- **High-intensity highly-charged heavy ion beam production and acceleration**
- **Two-phase painting injection to increase BRing injection efficiency and overcome space charge limit**
- **Fast ramping rate (12T/s) of BRing magnets to mitigate ionization beam loss and dynamic vacuum effect**

Key technology R&D and Prototyping

- **28 GHz SECRAL-II and 45 GHz FECR ECR ion sources**
- **Fast ramping power supply with full energy-storage technology for BRing dipole magnet**
- **Magnetic alloy core loaded RF system**

Civil construction site

HIAF-SRing tunnel

HIAF-BRing tunnel

CiADS

HIAF

CiADS site

Equipment test building
No.2

HIAF operation building
No.2

1# Cryogenic center


Office building No.1

Office building No.2

Cooling water building

Electric-power
transformer station

Equipment test building
No.1





HIAF civil construction status








HIAF components fabrication

■ Most of the components are in mass production




BRing dipole magnets



Components of HFRS superconducting magnets



iLinac HWR015 cavities



Components of SRing electron cooler



BRing collimator



HIAF planed milestones and time schedule

2019	2020	2021	2022	2023	2024	2025
Civil construction						
		Electric power, cooling water, compressed air, network, cryogenic, supporting system, etc.				
ECR design & fabrication		SECR installation and commissioning				
	iLinac design and fabrication			iLinac installation and commissioning		
Prototypes of PS, RF cavity, chamber, magnets, etc.			fabrication	BRing installation & commissioning		
				HFRS & SRing installation & commissioning		
				Terminals installation		
Day One exp.						


- The first ion beam provided by **SECR** in the end of 2022;
- The first ion beam from **iLinac** in the end of 2024;
- The first ion beam injected, accelerated and extracted from **BRing** in May 2025



CiADS layout and parameters

CiADS could be the world first MW-level ADS facility

- **T1: Fast reactor, LBE target**
Demonstrate high power ADS and transmutation
- **T2: Target exp., liquid metal and granular target**
- **T3: material irradiation and full power dump**
- **T4: low power dump 50 kW**




CiADS key parameters

Thermal Power (Reactor + Beam)	10 MW
Proton beam Energy (MeV)	500
Beam density (mA)	5
Operation modes	CW / Pulse
Target Max. power (MW)	≤ 2.5
Target material	LBE
Reactor K_{eff}	$\sim 0.75 / \sim 0.96$
Reactor thermal power	$\sim 7.5 / \sim 9.76$




Physics design of CiADS proton linac



Parameters of the SRF cavities

	HWR010	HWR019	HWR040	Ellip062	Ellip082
Freq. (MHz)	162.5	162.5	325	650	650
Quantity	9	24	60	30	28
Dyna. load @ 2K	2.9	4.4	5.7	23	25
Ep @ op. (MV/m)	26	28	28	29	29
Ep @ cp. (MV/m)	31	32	31	31	32



Beam envelope along the linac



CiADS technical challenge

- **Minimize the beam loss and maintain a long-term high reliability and availability of the high power proton SC linac (500 MeV/5mA)**
- **High power spallation target (2.5 MW). Phase I: LBE target; Phase II: Granular flow target**
- **Coupling between the reactor, the target and the high power proton beam**

Key technology R&D and Prototyping

- **17-20 MeV/CW 5-10 mA front-end demo-facility of CiADS linac for reliability demo.**
- **Target prototype R&D (LBE target and granular flow target)**
- **Prototyping for fast subcritical reactor vessel, heat exchanger and LBE centrifugal Pump**




CiADS civil construction status






CiADS facility in prototyping and engineering design




650 MHz SSAMP @ 150 kW




HWR010


HWR015



HWR040




Ellip082



Ellip062


SRF cavities



Target Prototype



CiADS planned milestones and time schedule






OUTLINE


- HIAF & CIADS brief introduction and construction status
- **Key technology R&D and demonstration**
 1. **High-intensity highly-charged heavy ion beam production**
 2. Fast ramping power supply with full energy storage
 3. Magnetic alloy core loaded RF system
 4. 17-20 MeV/CW 5-10 mA front-end demo-facility of proton SC linac
- Summary and conclusion



High-intensity highly-charged heavy ion beam production by SECRAL II



Ion Beam	SECRAL (eμA) (2015-2019)
$^{16}\text{O}^{6+}$	6700
$^{40}\text{Ar}^{12+}$	1420
$^{40}\text{Ar}^{16+}$	620
$^{40}\text{Ar}^{18+}$	15
$^{40}\text{Ca}^{11+}$	710
$^{78}\text{Kr}^{18+}$	1030
$^{78}\text{Kr}^{28+}$	146
Xe^{26+}	1100
Xe^{30+}	365
Xe^{42+}	16
$^{209}\text{Bi}^{31+}$	680
$^{209}\text{Bi}^{41+}$	100
$^{209}\text{Bi}^{50+}$	10
$^{238}\text{U}^{33+}$	450
$^{238}\text{U}^{35+}$	315




■ Demonstrated a good long-term stability

Record beam intensities (red numbers) produced by IMP SECRAL I & II




The world first 4th generation ECR ion source FECR



FECR key parameters

Microwave	45 GHz/20 kW
Magnet conductor	Nb ₃ Sn
Axial fields (T)	6.5/1.0/3.5
Sextupole field (T)	3.8@r=75 mm
Maximum field (T)	11.8 T
Maximum stress (MPa)	150
Magnet bore (mm)	>Ø160
Stored energy (MJ)	1.6
Extraction (kV)	50
Typical beam	1.0 emA U ³⁵⁺



- Beams and intensities expected from FECR

- 3-5 times higher than the existing record beam intensities


$^{129}\text{Xe}^{30+}$	>1000 μA
$^{129}\text{Xe}^{45+}$	> 50 μA
$^{209}\text{Bi}^{31+}$	>1000 μA
$^{209}\text{Bi}^{55+}$	> 50 μA
$^{238}\text{U}^{35+}$	>1000 μA
$^{238}\text{U}^{41+}$	> 200 μA
$^{238}\text{U}^{56+}$	> 30 μA



FECR Nb₃Sn magnet




The magnet mechanical structure was designed by collaboration with ATAP magnet group at LBNL

Bladder & Keys assembly







1/2 Prototype of FECR Nb₃Sn magnet



■ Sextupole was energized only



■ Sextupole and one solenoid were energized




- Manufacturing and 8 times energizing tests of the 1/2 prototype Nb₃Sn magnet took more than **5 years**
- The sextupole quenched at 70%-90%, sextupole+one solenoid reached 77% design current
- 2 of the 6 sextupole coils turned out to have performance degradation or minor damage
- Learned a lot of lessons and experiences, manufacturing, assembling, quench protection, flux jump,



FECR full-scale Nb_3Sn magnet status

**Almost ready for cooling down and energizing
But need to verify the quench protection system carefully**




The magnet was manufactured and assembled by collaboration with XSMT company in Xi-an



Fast ramping power supply with full energy storage for dipole magnets

- To reduce beam loss , 12 T/s ramping rate is required for the HIAF BRing dipole magnets.
- Challenge for the dipole power supply: High peak power, very fast ramping rate (38000 A/s), high tracking precision, very low current ripple and voltage fluctuation.

Excitation current/voltage	3900A/3600 V 3 Hz
load inductance	116 mH
Load Resistance	36.4 mΩ
Current changing rate	± 38000 A/s
Flat top/top/bottom error	$\leq \pm 0.2$ A $\leq 5.1 \times 10^{-5}$
tracking error	$\leq \pm 0.2$ A $\leq 5.1 \times 10^{-5}$




- A innovative power supply topology and technology proposed for HIAF BRing dipole magnets

Variable forward excitation; full energy storage technology; high-power-pulse technology with FPGA-based full-digital controllers.



Prototype of fast ramping power supply with full energy storage

- A prototype power supply with full current and power has been developed. The key technologies and the innovative design with variable forward excitation and full energy storage technology at high-power pulse have been verified.




The prototype power supply was tested successfully with 4 real BRing dipole magnets connected in series
**Achieved results: maximum current 4000 A/3600 V, ramping rate 38000 A/s
repetition rate 3 Hz, tracking error $\pm 9.62 \times 10^{-5}$**




Magnetic alloy core loaded RF system for HIAF BRing

- RF system of HIAF BRing: high RF voltage 240 kV and short rise time $\leq 10\mu\text{s}$ for beam compression



Voltage and phase waveform



- MA core production line was built through collaboration between IMP and a domestic company


- Key technology:** 14 μm ribbon production, ribbon shearing, 1~2 μm insulation silica coating, constant tension horizontal winding, atmosphere annealing and water proof coating



Ribbon shearing



1~2 μm silica coating



Constant tension horizontal winding



Atmosphere annealing



Water proof coating



Performance of the magnetic alloy core produced

■ Independent development of MA core


Over ten years development from small($\phi 90$), medium ($\phi 460$), to large size ($\phi 780$) MA core.




95 × 65 × 25mm



460 × 230 × 25mm





750 × 345 × 35mm



780 × 360 × 35mm

■ Breakthrough in MA core manufacturing Q value: (0.65~0.3) @ (0.1~20MHz) $\mu'_p Q_f$: 5.3GHz @ 0.3MHz





Oil-cooling MA core loaded cavity and RF system manufactured




MA RF system




Two-TH558-tube amplifier cabinet

RF power test was carried out: Gap voltage/one cavity **50kV@0.3~2.1MHz**


The third harmonic suppression better than 25 dB




Cavity pick-up voltage



Voltage of ramping mode



Harmonic suppression




Harmonic at ramping mode



17-20 MeV/5-10 mA front-end demo facility for CiADS linac


■ 2011-2017. SC linac 10-25 MeV/ CW 0.2-1.1 mA
IMP collaborated with IHEP.

■ 2018- 2021. Upgrade to 20 MeV/CW 10 mA
Demonstrate 10 mA CW beam



ions	P, H ₂ ⁺ , α
Frequency	162.5 MHz
Current	10 mA
E _{in} RFQ	40 keV
E _{out} RFQ	3.1 MeV
E _{out} SC linac	20/30/40MeV
Cryo. Temp.	4.5 K



• Supported by “Strategic Priority Research Program” of the Chinese Academy of Sciences.






High power CW SC proton linac reliability demonstration

- Operation from Jan. 20 to Mar. 10, 2021 **The world first demonstration**



IS arcs, maybe mistake of MPS and RRS Logic
RFQ waveguide temp. alarm PS Arc, R manually



CM2-1 coupler Vac IS arcs, R manually

Availability: 126.1 kW, op. time **108 hs**, availability **93.6%**

Beam current: 174.4 kW, **10.08 mA**, op. time 12 hs

High power: 20.18 MeV, 10.18 mA, beam power **205.5 kW**







RAMI analysis for the continuous operation test

Operation Period: 9:42, Mar. 4, 2021 ~21:43, Mar. 8, 2021;

Operation time: 108 hrs (pre-set by the reviewers)

Downtime: 6.85 hrs, 93.6% availability

Distribution of downtime and trips from subsystem



108 hours operation at 17.18MeV/7.5mA

12 hours operat. 17.27MeV/10mA

Trip sources	Downtime (s)		Trips		Avg time (s)
RF	6360	26%	18	41%	353
Cryogen.	0	0%	0	0%	0
Ion source	1103	4%	8	18%	138
Vacuum	7598	31%	3	7%	2533
Magnet	0	0%	0	0%	0
PS	1244	5%	2	5%	622
Diagn.	35	0%	1	2%	35
Control	8317	34%	12	27%	693

- Failures and trips caused by ion source, vacuum, PS and control can be solved.
- RF contributes the main parts of the trips



Summary and Conclusion

■ HIAF and CiADS facilities being built in Huizhou by IMP.

- Most of HIAF components in mass production and civil construction completed 50%. The first beam commissioning of iLinac and BRing planed in 2024-2025.
- CiADS in key technology R&D and facility engineering design. The first beam commissioning of CiADS linac is planed in June 2025.

■ Key technology R&D and demonstration for HIAF&CiADS, achieved a good progress.

- A lot of record beam intensities for highly charged heavy ions were produced by SECRA II. 45 GHz FECR Nb₃Sn magnet almost ready for cryogenic energizing after 7 years development.
- Fast ramping power supply with full energy storage successfully developed for HIAF BRing dipole magnet, reached 4000 A/3600 V, ramping rate 38000 A/s, 3Hz.
- Large size and high performance MA core was developed successfully. Oil-cooling MA core loaded cavity and RF system were manufactured and tested, reached designed performance.
- Reliability and availability at 17 MeV/CW 7.5 mA for 108 hours and 17 MeV/CW 10 mA for 12 hours continuously operation were demonstrated for the first time for a proton SC linac, as a low energy demo-facility for CiADS.



Acknowledgement

Thanks Jiangcheng Yang, Yuan He and Liangting Sun for preparing a few slides !

Thanks HIAF and CiADS teams for hard working and achieving good progress !

Thanks a lot all those experts and colleagues from the domestic and international Labs for your help, collaborations and fruitful discussions !

Thank you for your attention !