

The European X-ray FEL *Accelerator Layout*


Reinhard Brinkmann, DESY
for the XFEL Group




TESLA

The Superconducting Electron-Positron Linear Collider with an Integrated X-Ray Laser Laboratory

Technical Design Report



March 2001






TESLA XFEL

First Stage of the X-Ray Laser Laboratory

Technical Design Report Supplement



October
2002

TDR update 2002:

Separate linac for XFEL

(maintain common site & same s.c. linac technology)




- De-coupling from LC regarding construction & operation (and: approval)
- Gain in operational flexibility

Decision by German Government Feb. 2003:

Go ahead with XFEL as European Project, commitment for funding 50% of estimated 684 M€ (year 2000 price basis)


New site: XFEL – LC synergy argument no longer valid

- Use existing infrastructure on DESY site
- Acc subsystems (injector, cryogenics, modulators,...) on DESY site
- Linac tunnel 15 – 30m underground in urban area
- User facility in rural area, place for possible extension
- Legal procedure for construction (*Planfeststellung*) in preparation → permission by end of 2005




New site: XFEL – LC synergy argument no longer valid

- Use existing infrastructure
- DESY site
- Accelerator and cryogenic infrastructure
- DESY site
- Linac tunnel underground
- User facilities for possible expansion
- Legal possibilities for construction in preparation for the end of 2004




User facility - Beam lines




SASE undulators 0.1 – 6nm, magn. Length 150 – 80m

- Variable gap (min 10mm) → independent λ -tuning, electron/photon beam alignment
- Options: fast independent switch of FEL process for sequence of U's, sub-fs pulses by modulation with ultra-short laser, seeding, ...

XFEL schedule:



- TTF / VUVFEL
 - Pilot facility for the XFEL (s.c. linac, beam dynamics/diagnostics, FEL process, user operation...)
- LCLS
 - first to reach SASE in Å regime
 - Common interests & fruitful cooperation
- EUROFEL
 - Coordinated FEL R&D in Europe, co-funding by EU recently approved



Ongoing Project Organisation at European Level

XFEL Steering Committee (Chair: H. Schunck, BMBF)

- Representatives of all countries intending to contribute to the XFEL facility
- 1st meeting Feb. 2004
- Work out MoU for construction and operation of the European XFEL by 2005

WG on Scientific and Technical issues STI (chair: F. Sette, ESRF)



- 1st meeting Apr. 1-2, 2004
- Reach consensus on the scientific goals and the overall layout of the facility
- Prepare technical report as part of the MoU

WG on Administrative and Funding issues AFI (chair: H.F. Wagner, BMBF)

- 1st meeting March 19, 2004
- Work out legal framework and organisational scheme for construction & operation
- Explore and reach consensus on the cost breakdown and spending profile


Parameter considerations - Choice of beam energy

Conservative assumption on slice energy spread: 2.5 MeV (expect ~1 MeV including incoherent SR)




→ 17.5 GeV for 1Å

Wavelength vs. acc gradient



Nominal linac energy 20 GeV, includes ^{57}Fe line @ 0.8Å


Basic Accelerator Layout



Main linac	
Beam energy	20 GeV
acc gradient	22.9 MV/m
Bunch spacing	200 ns
beam current	5 mA
power → beam p. klystron	3.8 MW
incl. 10% + 15% overhead	4.8 MW
matched Q_{ext}	$4.6 \cdot 10^6$
RF pulse	1.37 ms
Beam pulse	0.65 ms
# bunches p. pulse	3250
Rep. rate	10 Hz
Av. Beam power	650 kW

TESLA

3 kl. built by French company, operated @ design spec TTF



var. Q_{ext} with adjustable coupler and/or waveguide tuner

Prototypes from US & J industry
THP39, THP45



De-rated 10MW MBK

TUP80, THP49




Bouncer-type modulator

THP52




5 MW RF source





eight 9-cell Nb cavities at 2K, $Q_0=10^{10}$

12m TTF-like acc. modules





TTF / VUVFEL: pilot facility for the XFEL



M5 Test with RF, $Q_0 = 8 \cdot 10^9$ at 25 MV/m

→ D. Kostin, THP32




S. Simrock, WE103

T. Jezynski et al., TUP78

W. Cichalewski et al., TUP98


State-of-the-art electropolished cavities

→ L.Lilje, WE102 A. Matheisen et al., THP95



- 40 MV/m achieved *without* 1400C baking/Titanisation
- One cavity installed in module and tested with beam at 35MV/m

Operational flexibility – duty cycle




Sketch of possible future CW operation mode

If Å FEL radiation at lower beam energy comes in reach (better injector/beam quality, advanced FEL concepts, ...) → high duty cycle, up to CW, can become an attractive option

Linac layout & cryogenics consistent with this option (at $E_{\text{acc}} = 7...8$ MV/m), different RF system has to be added

Maintain good RF → beam efficiency with moderate over-coupling (87 Hz bandwidth, expect <10 Hz rms microphonics)



Sketch of future CW operation mode cont'd


Beam energy [GeV]	6.5
Acc gradient [MV/m]	7
Beam current ^{\$} [mA]	0.18
Bunch spacing [μ s]	5.5
RF power / module [kW] (incl. overhead)	~20
Dynamic cryo load 2K [kW]	~2.4

*B. Petersen,
MOP87*

\$: total beam power of 1.2 MW sufficient to operate simultaneously 4 undulator beam lines at beam dump limit of 300kW

If user demand for very high average power, ERL option is conceivable

Injector & bunch compressor




Start-to-end beam simulations:

ASTRA (DESY) - space charge dominated e-beams
TraFiC4/CSRtrack(DESY) - self-consistent CSR effects
MAFIA (TUD/CST) - general e.m. field solver for wakefields etc.


elegant (Argonne Natl. Lab.) - e-beam tracking with wakefields

GENESIS1.3 (DESY) - 3D SASE FEL code

FAST (DESY/JINR) - fast SASE FEL code for parameter optimization




Example of start-to-end analysis: TTF1 FEL




after bunch compressor

at entrance of undulator




Emittance (x-solid, y-dashed)

Peak current




Emittance (x-solid, y-dashed)

Peak current



Slice energy spread

Longitudinal phase space




Slice energy spread

Longitudinal phase space

Emittance from photocathode RF gun injector

Transverse Emittance





- 1nC charge
- uniform transverse distribution
- longitudinal flat-top with 2 ps rise time
- incl. thermal emittance

$$\epsilon_n = 0.9 \mu\text{m}$$

Y. Kim et al., TUP57

powered by SLAC 9804


RF gun development at PITZ, DESY-Zeuthen




On-going programme:

- increase the gradient on the cathode from 40 MV/m to 60 MV/m
- further improve the transverse and longitudinal laser profile (collab. Max-Born Institute, Berlin)
- PITZ gun now part of TTF-II/VUVFEL injector (commissioning started, not yet flat long. laser profile)


Bunch compressor – single stage/double chicane



*Y. Kim et al.,
EPAC2004*





END of LINAC with 60 slices



END of LINAC with 60 slices

Estimate of beam jitter at undulator – challenging stabilisation issues

Model calculation: RF phase/amplitude jitter 0.05%/0.02%, laser timing 0.1ps,...



Possibility of intra-pulse RF feedback with SRF helpful



Potential advantage of 2nd stage compressor under study

Y. Kim et al., TUP58

Bunch patterns / beam distribution

Generation of bunch train patterns:

- **At the source**
varying transient effects in the entire accelerator (handled e.g. by the LLRF system)
- **At the beam delivery / distribution system**
more challenging kicker devices



Conclusions

- **The 20 GeV s.c. linac** based on the technology developed by the TESLA collaboration and successfully demonstrated at TTF **is an ideal driver for the Free Electron Laser facility**, offering a broad range of operating parameters in its baseline design and with future upgrade options.
- **With the R&D work towards industrial production of major components, the preparations for the site at DESY and the European project organisation under way, we should be ready to go into construction phase in ~2 years from now.**