



# KEKB INJECTOR LINAC AND UPGRADE FOR SUPERKEKB

## S. Michizono

for the KEK electron/positron Injector Linac  
and the Linac Commissioning Group


### KEK

- **KEKB injector linac**
  - Brief history of the KEK electron linac
  - Continuous injection (CI) scheme
  - Maintenance and R&D at CI scheme
- **Upgrade for SuperKEKB**
  - Schematic -----*MOP31 S.Ohsawa et al.*
  - Rf source ----- (*rf window*) *THP58 S. Michizono et al.*
  - SKIP -----*THP61 T.Sugimura et al.*
  - Acceleration structure -----*THP29 T.Kamitani et al.*
  - Dummy load
- **Summary**



# KEKB B-Factory

# KEKB schematic



Superconducting cavities (HER)

Belle detector

ARES copper cavities (HER)

ARES copper cavities (LER)

TRISTAN tunnel


8 GeV  $e^-$   $\rightarrow$  HER

3.5 GeV  $e^+$   $\rightarrow$  LER

$e^+$  target



# Operation Statistics






100,000 hours operation since 1982





# Operation status


- Total operation time reached 100,000 hours on March, 2003.
- Machine failure is limited less than 5 %.





# Continuous Injection (CI) Scheme

## traditional








# Beam on time after CI scheme

Careful beam tuning and short maintenance are required at CI.







# Dip test

- In order to find out the emission decrease of the klystrons, dip tests are applied to all the klystrons.
- Deeper dip -> operation near the shoulder.
- heater off time: 60 sec.
- Total measurements: within 10 min.

Example of emission decrease








# Dip test


- Periodical measurements of the dip  
-> find out the emission decrease with time





# Energy spread feedback

- Feedback systems
  - Energy feedback -> done
  - Position feedback -> done
  - Energy spread feedback -> tested with 8 electrodes BPM





# KEKB INJECTOR LINAC AND UPGRADE FOR SUPERKEKB

---

**S. Michizono**

**for the KEK electron/positron Injector Linac  
and the Linac Commissioning Group**

**KEK**


- **KEKB injector linac**
  - Brief history of the KEK electron linac
  - Continuous injection (CI) scheme
  - Maintenance and R&D at CI scheme

➔ **Upgrade for SuperKEKB**

- Schematic
- Rf source
- SKIP
- Acceleration structure
- Dummy load
- Summary



# Schematic of SuperKEKB




Super-B Factory at KEK



## Upgrade of the injector linac

- 8 GeV  $e^-$  / 3.5 GeV  $e^+ \Rightarrow$  8 GeV  $e^+$  / 3.5 GeV  $e^-$



- S-band (2856 MHz)  $\Rightarrow$  C-band (5712 MHz) (#3 ~ #5 sectors)





# Linac Accelerator module

(From S-band To C-band)

MOP31 S.Ohsawa et al.

Present S-band accelerator module

New C-band accelerator module




Accel. field gradient = 21 MV/m

Accel. field gradient = 42 MV/m

# Overview of C-band rf system

- ✦ C-band rf system from #3 to #5 sector
- ✦ **Forty eight klystrons** are installed (instead of 24 S-band klystrons)

RF System Diagram C-band Plan(example)



48 C-band klystrons





# KEKB INJECTOR LINAC AND UPGRADE FOR SUPERKEKB

**S. Michizono**

for the KEK electron/positron Injector Linac  
and the Linac Commissioning Group




**KEK**

- **KEKB injector linac**
  - Brief history of the KEK electron linac
  - Continuous injection (CI) scheme
  - Maintenance and R&D at CI scheme
- **Upgrade for SuperKEKB**
  - Schematic
  - ➔ **Rf source (LLRF, Modulator, high-power klystron, rf window)**
  - SKIP
  - Acceleration structure
  - Dummy load
- **Summary**



# Driver klystron



Retune the existing C-band 200 kW klystron for weather observation station (MELCO).  
Driver klystron (SB) can deliver >100 kW (35 kV)  
**Same modulator** and HV supply to S-band system used.





# Compact modulator

- By using inverter P.S., the modulator size can be 1/3 (4.7 m → 1.8 m).
- Present PFN and Thyatron are reused at new modulator.



Compact modulator



# C-band klystron

**TOSHIBA**

**TENTATIVE**

**TOSHIBA PULSED KLYSTRON  
AMPLIFIER  
E3746**

- C-band 50 MW klystron is commercially available. (developed by KEK for linear collider)

Toshiba E3746 is a C-band high power amplifier klystron designed for linear accelerators.


The E3746 delivers 50MW peak output power in 2.5  $\mu$ s pulse.

Output power is extracted through two WR187 standard waveguides in parallel. One port output is also possible with the specific power combiner .

The electron beam is focused by a series-coil electromagnet. The specific focusing electromagnet VT-68926 is available.

A Scandate dispenser cathode is employed, ensuring high reliability and long tube life.

Y. Ohkubo, H. Yonezawa, T. Shintake, H. Matsumoto and N. Akasaka,  
“High THE C-BAND 50MW KLYSTRON USING TRAVELING-WAVE OUTPUT STRUCTURE”,  
Linac98, Chicago, p.932.






## R&D of c-band rf window

- ✧ Requirements: 50 MW 2  $\mu$ s ( $\leftrightarrow$  S-band 50 MW 4  $\mu$ s)
- ✧ About Sixty S-band rf windows are successfully operated in KEKB linac. (MTBF > 40,000 h.)  
Electric fields should be less than rf windows used in S-band linac.
- ✧ Mix-mode window (TE<sub>11</sub>+TM<sub>11</sub>) enables to lower the edge electric field.

	S-band	C-band
Electric field at center of the ceramics [MV/m@50MW]	3.7	3.1
Electric field at edge of the ceramics [MV/m@50MW]	1.7	0.8
Maximum electric field on the ceramics [MV/m@50MW]	5.5	3.7
Band width [MHz] (VSWR<1.2)	600	210





**THP58 S. Michizono et al.**





# Mix-mode rf window




THP58 S. Michizono et al.



# Resonant ring in the shield

- ◇ High power tests of the window was carried out by resonant ring.
- ◇ Rough tuning: spacer
- ◇ Fine tuning: operation frequency (5712->5710.2 MHz)





THP58 S. Michizono et al.





# Results at resonant ring

- ✧ Maximum operation power of **300 MW** ( $2 \mu s$ ), corresponding to **6-times larger** than specification (50 MW).
- ✧ Only **3-times rf trips** during 8 hours operation at 300 MW.





THP58 S. Michizono et al.



# SKIP (SuperKEKB Injector Pulse compressor)

- Mode:  
TE015(SLED)-> TE038(LIPS)
- Similar cavity size to present S-band SLED.
- Higher Q value.
- Output 200 MW @43 MW input
- Power magnification:4.7  
(lower than calculated value(5.5) due to slower switching time)

$Q_0=13200$ , coupling  $\beta = 6.6$



THP61 T.Sugimura et al.



# KEKB INJECTOR LINAC AND UPGRADE FOR SUPERKEKB

**S. Michizono**

for the KEK electron/positron Injector Linac  
and the Linac Commissioning Group

**KEK**


- **KEKB injector linac**
  - Brief history of the KEK electron linac
  - Continuous injection (CI) scheme
  - Maintenance and R&D at CI scheme
- **Upgrade for SuperKEKB**
  - Schematic
  - Rf source (LLRF, Modulator, high-power klystron, rf window)
  - SKIP
  - **Acceleration structure**
  - Dummy load
- **Summary**





# C-band accel. section (First prototype)


54 regular cells                      1m-long  
iris diameter 2a:                      12.44 ~ 10.41 mm  
Based on present S-band acceleration structure



Filling Time  $t_f = 234$  nsec

THP29 T.Kamitani et al.

# C-band accel. section installed in KEKB linac (2003 September)



S-band section

C-band section

*THP29 T.Kamitani et al.*






# Beam acceleration study

Energy gain measured by  
changing acceleration phase

## Energy Gain by C-band unit





THP29 T.Kamitani et al.




# Inside of the acceleration structure

- Discharge every 10 min. even after conditioning.
- It took place around input coupler (rf wave analysis).
- Discharge traces observed input coupler and first disk.




Discharge location analyzed by rf waves.


**THP29 T.Kamitani et al.**



Coupler from inside



Coupler iris from outside




First disk (2a)






# Second acceleration structure

- Thicker iris
- Wider coupler length @ 2<sup>nd</sup> acceleration structure
- High power test @ Aug.,2004.



1<sup>st</sup> coupler



2<sup>nd</sup> coupler

**THP29 T.Kamitani et al.**




# Dummy load

Newly designed 2kW


Matsumoto-type  
dummy load

- 26 SiC cylinders
- SiC diameter 12 mm

High power test OK  
up to 2 kW (100 MW peak)



## Heat distribution



Cor



# Summary

---

- S-band linac has been operated > 100,000 hours.
- The failure rate is about 5% and it contributes to the stable KEKB operation.
- C-band R & D is in progress.
- High power test of the prototype C-band accelerator module has been performed since October 2003.
- Most of the components are working well.

(Remaining issues)

Breakdown at input coupler -> improve @ 2<sup>nd</sup> acc. structure  
inverter P.S. troubles -> long term operation

(related presentations tomorrow)

- **Rf window :** *THP58 S. Michizono et al.*
- **SKIP:** *THP61 T.Sugimura et al.*
- **Acc. structure** *THP29 T.Kamitani et al.*