

PROGRESS TOWARD 2 K HIGH PERFORMANCE HALF-WAVE RESONATORS AND CRYOMODULE



ZACHARY CONWAY
Argonne National Laboratory


19 July 2017
Lanzhou, Gansu China

COLLABORATORS:
M.P. KELLY
M.J. KEDZIE
S.H. KIM
B.M. GUILFOYLE
H. GUO (IMP)
T.C. REID

OUTLINE

Test Assembly of the HWR Cryomodule Cold Mass/Lid

- Half-Wave Resonators
- Cryomodule Overview
- Half-Wave Resonator Processing and Testing
- Future Work



For FNAL's Proton Improvement Plan II's (PIP-II) Project details refer to MOYA05, M.P. Kelly & A. Rowe's "SRF Technology for PIP-II and III"

For power coupler details look forward to FRXBA03, M.P. Kelly's Presentation "Coaxial Power Coupler Development at ANL"

HALF WAVE RESONATOR DEVELOPMENT

▪ SRF 2015:


- Two prototypes finished and tested.
- Low field $R_{res} \sim 2.5 \text{ n}\Omega$.
- Peak surface fields $\sim 90 \text{ MV/m}$ and 95 mT , electric and magnetic respectively.

▪ Now:

- Finished fabrication and processing of 7 production HWRs.
- 2.0 K testing of 5 of the 7 finished.
- Low field $R_{res} \sim 2.5 \text{ n}\Omega$.
- Reaching higher peak surface fields.


Cavity Type	HWR
Freq. (MHz)	162.5
β	0.112
I_{eff} (cm, $\beta\lambda$)	20.68
E_{pk}/E_{acc}	4.7
B_{pk}/E_{acc} (mT/(MV/m))	5.0
QR_s (Ω)	48.1
R_{sh}/Q (Ω)	272

Electromagnetic Field Intensity



E-Field

H-Field




HWR Nb Parts

2.0 K HWR CRYOMODULE OVERVIEW

Conduction Cooled Leads (FNAL)

Sub-Atmospheric HTXG Output



- 2 MV with < 2 W dynamic thermal load per HWR.
- ANL designed & fabricated for PIP-II @ FNAL.
- Continued ANL/FNAL collaboration: low-particulate cleaning, hydrogen degassing, sub-atmospheric heat exchanger, precision alignment, etc


80 K ENGINEERING COOLDOWN

Cryomodule Alignment




Cryomodule Assembly

Alignment Measurements




Cool Down Data




HWR FABRICATION

- Careful electrostatic discharge and conventional machining.
- Niobium sheet used to form reentrant noses (high E_{peak}) had scratches and dents removed via hand polishing prior to forming.
- All high field surfaces polished with 60, 120, 240, 300 and 400 grit sandpaper.
- BCP polished parts for 5-10 minutes at $T < 25 \text{ C}$ prior to welding. Not just the weld seam but the heat affected zone +.
- Post fabrication chemical polishing.

HWR @ FNAL for H-Degassing





HWR @ BNL for H-Degassing




Many thanks to FNAL (A. Rowe, M. Merio) and BNL (S. Seberg, K. Smith, W. Xu) for hydrogen degassing.

HWR POLISHING


- All processing done in the joint ANL-FNAL surface processing facility.
 - M.P. Kelly and T.C. Reid 2017 Supercond. Sci. Tech. 30 043001
- Processing after fabrication = 5 μm BCP, 120 μm EP, hydrogen degassing, 20 μm EP.



HWR 2.0 K OFFLINE RESULTS




2.0 K HWR RESIDUAL RESISTANCE



EXAMPLE: HWR5 FIELD EMISSION

E_{pk} (MV/m) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140


B_{pk} (mT) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



HWR PROCESSING AND TESTING ISSUES


Not every process was smooth:

- During first HWR4 test a glow discharge was initiated in the power coupler.
- During first HPR of HWR5 the HPR water hose cracked and HPR pressure was very low.
 - First test was poor, $E_{acc} < 6$ MV/m.
 - Second test was shown on the previous slide.
- During bulk EP of HWR6 an aluminum cathode was improperly inserted into the cavity. An electrical arc occurred early in the EP process.



Power Coupler



- 1) Broken vacuum pump.
- 2) Bad cavity vacuum.
- 3) Coupler discharge during 1st test.



HWR4 TEST ING AND PROCESSING HISTORY

E_{pk} (MV/m) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140

B_{pk} (mT) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150




V_{gain} (MV) 0 1 2 3 4 5 6

HWR6 TEST AND PROCESSING HISTORY

E_{pk} (MV/m) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140

B_{pk} (mT) 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150



V_{gain} (MV) 0 1 2 3 4 5 6

FUTURE WORK

- 6 of 8 HWRs ready for installation in the cryomodule.
- The last 2 HWRs have been processed and are ready for 2.0 K testing.
- 1 HWR requires more diagnostics.
- 134 MV/m and 144 mT peak surface electric and magnetic fields, respectively, achieved in recent HWR testing.
 - Special attention to surface cleaning and surface roughness.
- How to go to higher E_{peak} ?
 - Increased HPR water pressure is marginal.
 - Smoother surface?
 - Already mirror smooth after EP.
 - Alternative surface cleaning process?
- Assemble and commission the cryomodule.

