

## Progress in SRF CH-Cavities for the HELIAC CW Linac at GSI

M. Miski-Oglu<sup>1,2</sup>

K. Aulenbacher<sup>1,2,4</sup>, W. Barth<sup>1,2,5</sup>, M. Basten<sup>3</sup>, C. Burandt<sup>1,2</sup>, M. Busch<sup>3</sup>,  
T. Conrad<sup>3</sup>, F. Dziuba<sup>1,2,4</sup>, V. Gettmann<sup>1,2</sup>, M. Heilmann<sup>2</sup>,  
T. Kürzeder<sup>1,2</sup>, S. Lauber<sup>1,2,4</sup>, J. List<sup>1,2,4</sup>, H. Podlech<sup>3</sup>,  
U. Ratzinger<sup>3</sup>, A. Rubin<sup>2</sup>, M. Schwarz<sup>3</sup>, A. Schnase<sup>2</sup>, S. Yaramyshev<sup>2,5</sup>

<sup>1</sup>HIM, Helmholtz Institute Mainz, Mainz, Germany

<sup>2</sup>GSI Helmholtzzentrum, Darmstadt, Germany

<sup>3</sup>IAP, Goethe Univ. Frankfurt, Frankfurt, Germany

<sup>4</sup>KPH, Johannes Gutenberg Univ., Mainz, Germany

<sup>5</sup>National Research Nuclear Univ., Moscow, Russia

## FAIR requirements:

- high beam currents
- low repetition rate (max. 3 Hz)
- low duty factor (0.1 %, pulse length for SIS18 only 100 µs)


## “Super Heavy Element” requirements:

- relatively low beam currents
- high repetition rate (50 Hz)
- high duty factor (100 %, pulse length up to 20 ms)

## – Material Science at GSI

- Heavy Ions ( $m > 200$ )
- High Beam Energy (up to 10 MeV/u)
- Continuous Beam Energy Variation (1.5 – 10 MeV/u)

# Recent layout of the future superconducting cw HELIAC\*




Design parameters sc cw-LINAC		
$A/q$		$\leq 6$
Frequency	MHz	216.816
Beam current	mA	$\leq 1$
Injection energy	MeV/u	1.4
Output energy	MeV/u	3.5–7.9
Length	m	20
CH cavities	#	12
Rebuncher	#	4
Solenoids	#	8

- Multigap CH cavities
- Cavities with short lengths (<1 m) and small transverse dimensions (<0.5 m)
- Modular construction with 4 cryomodules
- Each containing 3 CH cavities, 1 buncher, 2 solenoids
- $E_a = 7.1 \text{ MV/m}$  enables compact linac design
- **R&D on Demonstrator Cavity**

\* HELmholtz LInear ACcelerator

# Motivation for Superconducting Multi Cell CH-Cavity



360MHz  
Prototype



325 MHz CH



217 MHz  
Demonstrator/CH0




217 MHz  
CH1/CH2

- Room temperature IH structures have unprecedented high efficiency with real estate gradients up to 4 MV/m ([HSI IH-Injector @ GSI](#))
- Expectation on superconducting CH-structures: Mechanical stability, high accelerating voltage per cavity


# Field Profiles of CH-Cavity

$H_{211}$  mode of "pillbox" cavity


H field



E field



E field along beam axis




- Drift tubes are alternating connected to “+” and “-” potential
- Cross-bar-H-mode cavity → CH cavity
- Multigap drift tube cavity for the acceleration of protons and ions in the low and medium energy range ( $0.05 < \beta < 0.6$ )
- Accelerating voltage up to 6 MV

# 360 MHz Prototype (H. Podlech@SRF'07 Beijing)


## Main Parameters

- $\beta=0.1$
- $f=360 \text{ MHz}$
- 19 gaps
- RRR=250
- length=1048mm
- diameter=277mm
- $E_p/E_a=5.2$
- $B_p/E_a=5.7$



## Results

- $E_a=7 \text{ MV/m}$
- $U_a=5.6$
- $Q_0=7 \times 10^8$
- $E_p=36 \text{ MV/m}$
- $B_p=40 \text{ mT}$



## Next Steps


- 325 MHz, 7 cell,  $\beta=0.1$
- 217MHz, 15 cell,  $\beta=0.059$

# RF Design of the Demonstrator Cavity CH0 (F. Dziuba)

(based on beam dynamic design by S. Mineav 2009)

## Design Challenges

- 217MHz double frequency of HLI Injector
- $\beta=0.059$
- Small transverse dimensions
- Minimal peak fields
- $E_{acc}=5.5\text{MV/m}$  (conservative)
- Mechanical stability
- Suppression of multipacting
- Frequency tuning
- Meet resonance frequency during manufacturing



## Parameters 217 MHz Cavity CH0


$\beta$		0.059
Frequency	MHz	216.816
Accelerating cells		15
Effective length ( $\beta\lambda$ )	mm	612
Diameter (inner)	mm	409
Tube aperture	mm	18 / 20
Wall thickness	mm	4
$df/dp^*$	Hz/mbar	50
$G$	$\Omega$	52
$R_a/Q_0$		3240
$R_a R_S$	$k\Omega^2$	168
$E_a$ (design)	$\text{MV/m}$	5.5
$E_p/E_a$		6.3
$B_p/E_a$	$\text{mT}/(\text{MV/m})$	5.7

\*without He vessel

# Manufacturing of Demonstrator/CH0 cavity (Research Instruments)


## Manufacturing Steps

- Production of stems with tubes
- Welding of inner cross bar structure (girders, stems, bellow tuners)
- Welding of cylinder walls



## Manufacturing Steps


- Production of stems with tubes
- Welding of inner cross bar structure (girders, stems, bellow tuners)
- Welding of cylinder walls
- Production of end caps
- Control of resonance frequency after each following steps with pressed end caps
- Trimming and welding of 4 static tuners
- Trimming and welding of left end cap
- Trimming and welding of next 3 static tuners
- Trimming and welding of right end cup
- 50 µm BCP treatment
- Trimming and welding of last 2 static tuners



# Manufacturing of Demonstrator/CH0 cavity (Research Instruments)


## Manufacturing Steps

- Production of stems with tubes
- Welding of inner cross bar structure (girders, stems, bellow tuners)
- Welding of cylinder walls
- Production of end caps
- Control of resonance frequency after each following steps with pressed end caps
- Trimming and welding of 4 static tuners
- Trimming and welding of left end cap
- Trimming and welding of next 3 static tuners
- Trimming and welding of right end cup
- 50 µm BCP treatment
- Trimming and welding of last 2 static tuners
- 25 µm BCP treatment



## Manufacturing Steps


- Production of stems with tubes
- Welding of inner cross bar structure (girders, stems, bellow tuners)
- Welding of cylinder walls
- Production of end caps
- Control of resonance frequency after each following steps with pressed end caps
- Trimming and welding of 4 static tuners
- Trimming and welding of left end cap
- Trimming and welding of next 3 static tuners
- Trimming and welding of right end cup
- 50 µm BCP treatment
- Trimming and welding of last 2 static tuners
- 25 µm BCP treatment
- HPR
- 4K rf-test
- HPR
- Welding of He-Jacket




# Resonance Frequency During Manufacturing

## Manufacturing Steps


- Production of stems with tubes
- Welding of inner cross bar structure (girders, stems, bellow tuners)
- Welding of cylinder walls
- Production of end caps
- Control of resonance frequency after each following steps with pressed end caps
- Trimming and welding of 4 static tuners
- Trimming and welding of left end cap
- Trimming and welding of next 3 static tuners
- Trimming and welding of right end cup
- 50 µm BCP treatment
- Trimming and welding of last 2 static tuners
- 25 µm BCP treatment
- HPR
- 4K rf-test
- HPR
- Welding of He-Jacket






### Main properties of the tuning system:

- Enables slow & fast frequency adjustment
- Capacitive bellow tuner
- Max. mechanical displacement  $\pm 1$  mm ( $\approx \pm 60$  kHz)
- Lever with pivot point ratio  $\approx 2:1$
- Stepping motor with gear reduction ratio 50:1
- $0.05 \mu\text{m}$  per step  $\rightarrow$  very fine frequency adjustment
- Piezo actuator ,connected in series' with slow tuning unit
- Required displacement of piezo  $\pm 6 \mu\text{m}$  ( $\approx \pm 360$  Hz)
- All design goals have been achieved!




# High Power Coupler




Coupler design based on the work of S. Kazakov, Fermilab


- Capacitive coupling of RF power
- Divided into cold & warm part by 2 ceramic windows ( $\text{Al}_2\text{O}_3$ ), TiN coated
- 5 kW cw operation, cold window connected to  $\text{LN}_2$  supply
- 216.816 MHz operation frequency with 33 MHz bandwidth



# RF Tests of the Cavity at IAP and GSI






- Improved performance due to an additional HPR
- Low field emission activity
- High accelerating gradient
- Acceleration of ions over design up to  $A/q = 12$
- R&D for further improvement of rf-performance



	Vertical test w/o He vessel	Horizontal test with He vessel
$Q_0^{\text{low}}$	$1.44 \cdot 10^9$	$1.37 \cdot 10^9$
$R_S$	nΩ	36
$R_{BCS}$	nΩ	15
$R_{mag}$	nΩ	9
$R_0$	nΩ	12
$E_a$	MV/m	6.9
$Q_0$	$2.19 \cdot 10^8$	$8.14 \cdot 10^8$
$V_a$	MV	4.2
$E_p$	MV/m	43
$B_p$	mT	39

# Field Emission





- Rapidly increase of total losses @  $E_a = 5 \text{ MV/m}$  ( $E_p = 32 \text{ MV/m}$ )
- Strong indication for field emitter activation
- Reduced total losses after anew HPR
- Minor deviation of total losses from Ohmic law @  $E_a = 7.8 \text{ MV/m}$  ( $E_p = 49 \text{ MV/m}$ )
- Field emission is reduced due two anew HPR!

# Series Cavity

## Design goals






- Easier manufacturing
- Less static tuner
- 2 dynamic tuners
- Higher mechanical stability
- Minimal peak fields
- Less gaps → flexible beam dynamics
- Two identical cavities
- $\beta=0.07$
- $E_a=5.5\text{MV/m}$



## Design goals

- $E_a=7.1\text{ MV/m}$
- Unified stem geometry across CH3/CH4/CH5 “series”
- Individual  $\beta$


# Performance of “series”




- All cavities at 4K are limited by surface peak electric field  $E_p$ .
- Multipacting induced quench?

# Experimental setup of the demonstrator at GSI


Layout of demonstrator cryomodule



Demonstrator at GSI-High Charge State Injector (HLI)




# Matching Line for the Beam Test





- HLI provides  $\text{Ar}^{11+}$ ,  $\text{Ar}^{9+}$ ,  $\text{Ar}^{6+}$ ,  $\text{He}^{2+}$  @ 1,4 MeV/u
- Steering magnets
- Additional Re-Buncher
- Quadrupole doublet
- Profile Grid
- Phase probes for TOF measurement of beam energy (also as BPM)
- Beam current transformers for transmission measurement
- Bunch shape monitor (Feschenko monitor)
- Slit-Grid emittance measurement device
- **6d characterization of the beam**
- **Test Bench of components and procedures for future HELIAC**

# Beam Energy vs. RF-Phase and -Amplitude



- Beam energy measured by TOF
- Independent rf-calibration of pick-up
- Accelerating field calculated by CST
- Amplitude of the field scaled according rf-calibration
- Energy gain calculated by tracking of particles in E-field
- Agreement between measurement and calculation
- Smooth energy variation
- High beam transmission






## cw LINAC @ IAP


M. Basten  
M. Bush  
H. Podlech  
U. Ratzinger  
M. Schwarz



## Next Phase: Advanced Demonstrator




# Next Phase: Advanced Demonstrator



- New cryo module layout containing demonstrator CH cavity, 2 short CH cavities, 1 re-buncher and 2 solenoids
  - 4 rf Amplifiers are tendered
- Simplified cavity design (easier manufacturing & surface processing)
  - Rf-power couplers
- CH1 & CH2 are already in testing (delivery at 4<sup>th</sup> quarter of 2019)
  - Tuner mechanics
- Re-buncher cavity is designed and Nb material is ordered
  - cold BPM
- Cryostat is ordered, expected delivery Q2 2020
  - low level rf
- Solenoids are tendered
  - New radiation protection shelter
  - Connection to cryoplant


# New Cryomodule Layout



## Design features & improvements

- 4 rectangular service doors
- On site alignment of each component to the beam line with a laser tracker
- Assembly of RF power couplers and solenoid current leads through the doors
- Nuclotron suspension of single components
- Segmented support frame, mechanically and thermally coupled to outer tank (300 K)
- Thermal shield inside of support frame
- Segmented frame standing on dedicated points of the bottom of the cryostat
- Deformations of outer vessel during evacuation do not affect the position of the frame
- Trans. position of each component will be preserved within  $\pm 0.1$  mm during cool down


# New Cryomodule Layout



- Already ordered, expected delivery in 04/2020
- Built by Cryoworld, Advanced Cryogenic, Netherlands

CRYOMODULE CM1		
Inner length	mm	4500
Inner diameter	mm	1500
Material vessel		Stainless steel 1.4404
Insulating vacuum	mbar	$< 1 \cdot 10^{-6}$
Max. system pressure	bar	$< 0.5$
Operating temperature	K	4.2
Temperature thermal shield	K	40
Max. static losses (stand by)	W	$< 5$

# Infrastructure @ HIM



## Infrastructure in Mainz:

- Clean room environment
- Cavity bakeout 120°C
- High Pressure Rinsing
- Rail system for string assembly
- Setup for cavity RF testing at 4 K and 2 K
- Further improvement of cavity performance

### Rinsing off axis



# Outlook

- 
- |                |   |
|----------------|---|
| <b>02/2015</b> | Funding of the Advanced Demonstrator within POF3  |
| <b>09/2016</b> | Ordering of two short CH-cavities                 |
| <b>11/2018</b> | Tendering of cryostat                             |
| <b>05/2019</b> | Modification of radiation protection shelter @GSI |
| <b>10/2019</b> | Delivery of short cavities                        |
| <b>12/2019</b> | Link of testing area to STF cryoplant             |
| <b>04/2020</b> | Delivery of cryostat                              |
| <b>04/2021</b> | Assembly of cryomodule @ HIM                      |
| <b>10/2021</b> | Beamtest @ GSI                                    |

## Acknowledgments

CSCY: *H. Kollmus, C. Schröder, A. Beusch, M. Kauschke*

CSVs: *P. Horn, M. Schweda*

GA: *G. Gruber*

LRF: *E. Plechov, A. Schnase*

TRI: *T. Lüding*